

SCHEDULE FOR INTERIOR WORKS FOR UNIFORM LAYOUT IMPLEMENTATION IN PATTURAIKKAL AND WEST FORT BRANCHES, UNDER RBO-I THRISSUR, AO THRISSUR.					
Sl No.	Description of work	Quantity	Unit	Rate	Amount
I)	PATTURAIKKAL				
	<u>PROVIDING CORIAN TOP/ LAMINATE CHANGE AND MINOR INTERIOR WORKS.</u>				
1	Providing and fixing 6 mm marine flexy plywood of approved make with curved bend in front modesty to the existing surface of counters using necessary frames.	12	Sq.M		
2	CORIAN TOP:- Providing, fitting and fixing flexible solid surface material (Corian solid surface - 6 mm thick, DuPont make.) of approved shade and make as per drawing and design. Solid surface material is to be fixed with acrylic epoxy adhesive compound including surface and edge finishing and moulds. The fixing is to be done on exposed surface of counters, tables or any other surface as directed. The work is to be completed with all materials, accessories, labour, tools and tackles and in strict conformity with manufacturer's specification and recommendations. The job shall also include provisions for electrical, computer & telephone wiring conduits, switch boxes etc. All materials should be approved by the Bank. Executed plan and elevation area of the surface work shall be measured for finished work.	12	Sq.M		
3	Providing and fixing 6 mm ply wood finished with 1 mm laminate of approved make and shade to the existing table top finishing with necessary beedings etc complete.	16	Sq.M		
4	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing partition/ panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings etc. complete. Area of partition excluding existing glass area to be measured for payment.	180	Sq.M		
5	Remove the existing laminate and fix with new 1 mm laminate of approved make and shade	100	Sq.M		
6	Providing and fixing side portion glazing with "Blue Laminated / Lacquered transperated glass of 12mm thick of approved brand and shall be fixed with 'Doma' (or) equivalent brand 'SS ' 'D' brackets. The curved 12mm thick lacquered transperant toughened glass shall be fixed at front size in between counters as per drawing and shall be fixed suitably with 'SS' brackets.	5	Sq.M		
7	Providing and fixing front Modesty with 8 mm thick Aqua blue shade of Saint Gobain glass or equivalent fixed 3M stickering suitable at front vertical finished with 1 mm laminate.	6	Sq.M		
8	Painting the false ceiling with two coats of plastic emulsion paint of approved color	125	Sq.M		
9	Painting banking hall using approved quality ' Asian paint or equivalent two coats without putty finish.	225	Sq.M		
10	Providing PVC telescopic key board tray with channel	10	Nos.		
11	Removing the existing drawer channel and fixing new telescopic channel of approved make	30	set		
12	Providing and fixing Godrej auto lock	7	Nos.		

II)	WEST FORT				
	<u>PROVIDING CORIAN TOP/ LAMINATE CHANGE AND MINOR INTERIOR WORKS.</u>				
1	Providing and fixing 6 mm marine flexy plywood of approved make with curved bend in front modesty to the existing surface of counters using necessary frames.	18	Sq.M		
2	CORIAN TOP:- Providing, fitting and fixing flexible solid surface material (Corian solid surface - 6 mm thick, DuPont make) of approved shade and make as per drawing and design. Solid surface material is to be fixed with acrylic epoxy adhesive compound including surface and edge finishing and moulds. The fixing is to be done on exposed surface of counters, tables or any other surface as directed. The work is to be completed with all materials, accessories, labour, tools and tackles and in strict conformity with manufacturer's specification and recommendations. The job shall also include provisions for electrical, computer & telephone wiring conduits, switch boxes etc. All materials should be approved by the Bank. Executed plan and elevation area of the surface work shall be measured for finished work.	18	Sq.M		
3	Providing and fixing 6 mm ply wood finished with 1 mm laminate of approved make and shade to the existing table top finishing with necessary beedings etc complete.	7	Sq.M		
4	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing partition/ panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings etc. complete. Area of partition excluding existing glass area to be measured for payment.	214	Sq.M		
5	Remove the existing laminate and fix with new 1 mm laminate of approved make and shade	34	Sq.M		
6	Providing and fixing side portion glazing with "Blue Laminated / Lacquered transperated glass of 12mm thick of approved brand and shall be fixed with 'Doma' (or) equivalent brand 'SS ' 'D' brackets. The curved 12mm thick lacquered transperant toughened glass shall be fixed at front size in between counters as per drawing and shall be fixed suitably with 'SS' brackets.	7	Sq.M		
7	Providing and fixing front Modesty with 8 mm thick Aqua blue shade of Saint Gobain glass or equivalent fixed 3M stickering suitable at front vertical finished with 1 mm laminate.	10	Sq.M		
8	Painting the false ceiling with two coats of plastic emulsion paint of approved color	150.00	Sq.M		
9	Painting banking hall using approved quality ' Asian paint or equivalent two coats without putty finish	200.00	Sq.M		
10	Providing PVC telescopic key board tray with channel	10.00	Nos.		
11	Removing the existing drawer channel and fixing new telescopic channel of approved make	30.00	set		
12	Providing and fixing Godrej auto lock	10.00	Nos.		

13	FALSE CEILING:				
	Gypsum Board False Ceiling	18.00	Sqm		
	Providing and fixing of M/F suspended false ceiling as the detail given in the drawings. With G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprising				
	Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls alround perimeter side of the ceiling. The intermediate channels suspened from ceiling,through starp hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional perimeter channels (MF 6A)for light fittings, Air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws to from grids with 2 coats of plastic emulsion paint of approved color and one coat of putty over a coat primer etc, complete.				
14	Custom Made Full Height Solid Partition:	10	Sq.M		
	Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing.				
	Frame Work Detail:Aluminium sections of size 63.5 X 38.1X1.2 mm thk. of INDAL/JINDAL as internal frame structure,vertically at about 60cm centers varied along columns wall ends, junctions of walls, as necessary. Horizontally of the same size of frames at floor level,750 mm, 1500 mm,2100 mm, and roof level.				
	Lining Work: 6 mm Plywood of approved make on both sides of framework from floor level to 6"above false ceiling level, and to be finished with 1mm laminate of approved colour and shaped on both sides including necessary grooves and steam beach beadings.				
	Measurement for the partition area shall be considered from floor level to false ceiling level only.				
	TOTAL				
	GST				
	GRAND TOTAL				