No.	Description of work	Quantity	Unit	Rate	Amount
<u>[]</u>	SILVER HILLS BRANCH:-				
1	Providing and fixing 6 mm marine flexy plywood of approved make with curved bend in front modesty to the existing surface of SWO counters using necessary frames. The job shall also include provisions for electrical, computer & telephone wiring conduits, switch boxes etc. Executed plan and elevation area of the surface work shall be measured for finished work.	15	Sq.M		
2	CORIAN TOP:- Providing, fitting and fixing flexible solid surface material (Corian solid surface - 6 mm thick)of approved shade and make as per drawing and design. Solid surface material is to be fixed with acrylic epoxy adhesive compound including surface and edge finishing and moulds. The fixing is to be done on exposed surface of counters, tables or any other surface as directed. The work is to be completed with all materials, accessories, labour, tools and tackles and in strict conformity with manufacturer's specification and recommendations. The job shall also include provisions for electrical, computer & telephone wiring conduits, switch boxes etc. All materials should be approved by the Bank. Executed plan and elevation area of the surface work shall be measured for finished work. The edges of the SWO counters to be finished properly after the work as per the Engineer in charge	15	Sq.M		
3	Supplying and fixing 1 mm thick laminate of approved make and shade by removing / scratching (to make impressions) the existing laminate as per the direction of Engineer in charge.	200.00	Sq.M		
4	Providing and fixing 12 mm Glass partition with Stainless Steel D Brackets of approved make in the sides of SWO Counters The edges of the glass shall be polished and the shape of the glass hall be made as per the requirement of the Bank. The measurement will be for the actual area executed at site.	5.00	Sq.M		
5	Providing and fixing front Modesty with 8 mm thick Aqua blue shade of Saint Gobain glass front vertical with silicon / any other approved adhesive. The measurement will be for the actual area executed at site.	10.00	Sq.M		
6	Painting the false ceiling with one coats of plastic emulsion paint of approved color. The electrical, fire, Air conditioning fixtures shall be properly covered during the painting work.	210.00	Sq.M		
7	Painting banking hall using approved quality 'Asian paint or equivalent two coats without putty finish above textured painted surface. The electrical, fire, Air conditioning fixtures shall be properly covered during the painting work.	200.00	Sq.M		
8	Providing and fixing Godrej auto lock for drawers of existing SWO Counters	11.00	Nos.		
	TOTAL				
	GST @ %				