

Name of work		Page 1 of 3		INTERIOR RENOVATION WORK OF SBI RBO 1 ERNAKULAM (EXISTING PREMISES)	
Name and Address of Contractor					
SCHEDULE OF ITEMS FOR RENOVATION OF RBO 1, ERNAKULAM					
Sl No.	Description of work	Unit	Quantity	Rate	Amount
1	<u>AGM Table</u> Providing and fixing AGM table of size 180 X 90 X75 cm which is made of postform finish at top and 19mm thick plywood (IS 303) finished with 1.0mm thick laminate on outer sides. The table top is provided with 12mm thick glass with edge rounded. The 3 nos. Of Drawer units has to be provided are to be made of 12mm thick plywood (IS 303). Metal Keyboard tray, CPU stand and provisions of wire manager are to be given. Footrest with countrywood 7.5cm X 2.5cm should be provided. The edges should be provided with necessary lippings. Necessary fittings such as multi purpose locks for drawers, metal Keyboard & drawer slides , handles, wire manager etc. are to be provided. The inner portion of the table to be painted with enamel paint of 2 coats over one coat of wood primer. Front side of the table is finished with 12mm thick plywood over the 19mm thick plywood with necessary beadings .	No	1		
2	<u>TABLE</u> Providing and fixing tables which is made of 25 mm postform finish at top and 19mm thick plywood (IS 303) finished with 1.0mm thick laminate on outer sides. The table top is provided with 12mm thick glass. The 3 nos. Of Drawer units has to be provided are to be made of 12mm thick plywood (IS 303). Metal Keyboard tray, CPU stand and provisions of wire manager are to be given. Footrest with countrywood 7.5cm X 2.5cm should be provided. The edges should be provided with necessary lippings. Necessary fittings such as multi purpose locks for drawers, metal Keyboard & drawer slides , handles, wire manager etc. are to be provided. The inner portion of the table to be painted with enamel paint of 2 coats over one coat of wood primer. Front side of the table is finished with 12mm thick plywood over the 19mm thick plywood with necessary beadings .				
a)	150 x 75 x 75 cms	No	12		
b)	120 x 60x 75 cms	No	13		
3	<u>Side Table</u> The table is made of 19mm thick plywood (IS 303) finished with 1mm thick laminate on the other exposed faces as shown. 25 mm thick postformed / edgebanded top is to be provided . File racks should be provided with 19mm thick plywood door shutters and necessary lippings . CPU stand is provided in the side table. The inner sides are painted with 2 coats of enamel paint over a coat of wood primer.				
a)	Size 120 X 45	No.	1.00		
b)	Size 100 X 45	No.	6.00		
c	size 90 x 75 cms	No	6.00		

For Contractor

4	<p>Low level Storage</p> <p>Page 2 of 3</p> <p>Free standing storage with shutters in 19mm thick marine ply in postformed laminate finish. 19Mm thick marine ply for verticals and base & back 9mm thick Marine ply. Back to be flush with external surface of the storage unit, with beech wood lipping on all exposed edges, 25mm thk top postformed laminate adjustable shelves at approximately 40C/C with 19mm Marine ply and all necessary fittings like brush finished adjustable handles, aluminium channels, rollers Godrej/Hafle/ebco make locks , melamine coated beech wood skirting 10cm X 1cm etc. Rate to be inclusive of cost of materials, labour, wastage, transportation, necessary scaffolding, etc complete. Cabinets inside to have 2 coats of enamel paint over 1 coat of primer base.</p>	M ²	10.00		
5	<p>Fully Glazed - Fixed Glass Partition - Patch Fitting</p> <p>Providing and fixing of fixed glass partitions with 12mm thick toughened glass using PT Standard fittings like PT 90/PT 92 of Dorma make / enox at the top and bottom including cutting, making holes in glass and fixing the fittings in floors, ceilings etc and making the same good with necessary screws and pattern, sealants etc.complete.</p>	Sq.M	25.00		
6	<p>Fully glazed Door</p> <p>Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings (Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.(DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 32mm dia X 600mm length) / enox fittings</p>	M2	3.00		
7	<p>False Ceiling</p> <p>Supplying and fixing suspended false ceiling with 12.5mm thick gypsum board over standard 18g GI sections @ 60cm c/c, including perimeter channels strictly as per the specifications of 'India Gypsum' to correct lines and levels finished with two coats of plastic emulsion paint of approved make and shade with roller application including providing necessary openings for electrical fittings, security device etc.</p>	M2	150.00		
8	<p>Column Panelling</p> <p>The frame work of column panelling should be of country wood (Thambakam, Chadachi) 5cm X 5cm both horizontally and vertically at 600mm c/c. 9mm thick plywood with 1mm thick laminate is then screwed to the 6mm thick plywood and design work to be done .Teak / Beech wood polished beadings are to be provided. Skirting for a height of 10cm with 12mm thick teak wood planks with melamine matt finish should be provided.</p>	M2	30.00		

For Contractor

9	Painting Applying two coats of good quality plastic emulsion paint over one coat of putty for the walls	Page 3 of 3 M2	150.00		
10	Applying two coats of good quality plastic emulsion paint for the walls	M2	150.00		
11	Laminated Partition Providing and fixing partition made of 2" X 2" good quality wood frame at 2'-0" c/c both ways. Alternate vertical member above the false ceiling shall continue upto the RCC ceiling. Bottom member shall be 4" X 2" for skirting. The skirting shall be 3" high and provided with 10mm commercial board / ply, finished with 1mm thick laminate of approved shade on both sides. The Teak wood frame shall be fixed rigidly at floor level as well as RCC ceiling bottom. The frame shall be provided with 6mm thick commercial ply with 1.0mm thick approved shade laminate on both sides of the frame. All wood shall be coated with fire resistant paint. The item includes 1 1/4 " thick door shutter in partition made of 3" X 1" good quality wood frame at 1'-0" c/c both ways, 6mm thick commercial ply with laminate shall be fixed on both sides of frame with teak wood edging out of 1 1/4" X 3/4" all around the shutter. The rate includes necessary hardwares such as hinges, tower bolt, 6 lever locks (Godrej) etc. All exposed Teak wood shall be stained to approved colour and finished with melamine (2 or more coats of APCOLITE). The rate includes making provision for electric conduits and switch boxes.	M2	40.00		
12	Semi Partitions – The partitions are made of 12mm thick glass to be fixed firmly to the beech / teak wood frame of size 5X5 cm polished with melamine matt finish for a height of 75cm above the solid partition. The bottom portion of the counter partition is of double skin type for a height of 75cm (as per Bank's instruction) from the finished floor level. In the frame work, verticals and horizontals are made of country wood 5cm X 5cm to a maximum distance of 60cm and two verticals at edges with 5cm X 5cm teak wood. Frame work is covered with 6mm thick plywood (IS 303) on both sides and finished with 1mm thick laminate of approved make. The partition is firmly fixed to the floor. Necessary wicket doors with locking arrangement are to be provided (Godrej / Ebco). Necessary hinges, handles and tower bolts etc. are to be provided for the wicket door. Teak / beech wood polished beadings / grooves in laminate etc. to be provided. Skirting for a height of 10cm with 12mm thick planks of teak wood finished with melamine matt polish to be provided. The edges of the glass to be polished.	M2	40.00		
13	Vertical Blinds Providing and fixing vertical blinds of Parytex/Window Fashion of aproved shade as required at site	M2	15.00		
	TOTAL				
	GST	18%			
	GRAND TOTAL				

For Contractor