

**STATE BANK OF INDIA**

**AO ERNAKULAM  
(EXISTING PREMISES)**

NAME OF WORK	ALTERATION WORK TO STAFF CANTEEN AT PANAMPILLY NAGAR				
NAME AND ADDRESS OF THE CONTRACTOR					
<b>SCHEDULE OF ITEMS FOR ALTERATION WORK TO STAFF CANTEEN AT PANAMPILLY NAGAR</b>					
SL.NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
1	Earthwork excavation for foundation trenches including dressing of sides and ramming of bottom and disposal of debris away from site	22	M3		
2	Plain cement concrete 1:5:10 with 40 mm aggregate for levelling course under foundation including curing	6	M3		
3	Solid block work in cement mortar 1:5 for foundation	10	M3		
4	Cement Concrete 1:2:4 for belt beam and lintels etc including shuttering, curing etc. but excluding cost of reinforcement as directed	5	M3		
5	Providing steel reinforcement for RCC works including bending, tying and placing in position	500	Kg		
6	Solid block Brick work in cement mortar 1:5 for walls/ pillars at all levels	30	Cu.M		
7	Plastering with cement mortar 1:5, 12 mm thick 2 coats	250	Sq.M		
8	Providing and fixing 60 x 60 cm vitrified ceramic tiles Johnson & Johnson "Marbonite" make by using cm 1:3 on to existing flooring for flooring and skirting. Basic price of tiles to be taken as Rs.60 per square foot (Tiles will be selected by the Bank).	125	Sq.M		

9	Providing and fixing in position corrugated aluminium sheets of 24 guage using necessary 'J' bolts (minimum 4 bolts to each sheet) including cost of all fixtures such as bitumen rubber washer, covering the holes with WP compound etc. Measurement shall be for the covered area inclusive of overlaps	150	Sq.m		
10	Finishing the walls of kitchen with 30 x 20 cm (or nearest size) ceramic tiles fixing on to existing surface with cm 1:3 adhesive (Basic price of tiles - Rs.30/- per sq.ft)	6	Sq.m		
11	Provide/fix 20 mm thick jet black granite (with polished / rounded edges) over a bed of cement mortar 1:3, 12 mm thick for the slab at kitchen and work area	6	Sq.M		
12	Providing and fixing 55x40 cm wash hand basin ivory colour with all fittings including 15 mm cp pillar tap, brackets, PVC connection, 15 mm cp stop cock etc.	4	Nos.		
13	Providing and fixing stainless steel sink with drain board of size about 36" x 18" including all connection/ fittings	1	No.		
14	Provide/ fix the following with all required fixtures and ancilliary works				
a	25 mm PVC pipe (4Kg/ Cm2 grade, pasting type) for water lines	25	RM		
b	20 mm PVC pipe for water lines	50	RM		
c	75 mm 4kg/cm2 grade PVC waste water pipe	20	RM		
15	Painting the newly plastered walls with 2 coats of oil bound distemper over a coat of primer	350	Sq.M		
16	Providing and fixing door with anodized aluminium frame of size 63.5 x 38.1 x 1.2 mm around and for intermediate frame infil with 9 mm Bison board, painting, all fittings, locks etc complete.	1	No		
17	Providing/ fixing window of size 120 x 135 cms with 63.5x38.1 x1.2 mm anodised alumium frame around openable/ sliding shutters with 4 mm plain glass, all fittings etc. complete	6	No		

18	Providing and fixing in position welded truss of 20 cm overall depth made out of 32x32x1.6 mm square pipe (TATA Structura make) at top, bottom and interconnecting members welded to the pipes as directed with necessary plates to fix the rafters/ purlins including painting with 2 coats of enamel paint over a coat of zinc chromite primer	25	RM		
19	Providing and fixing PVC gutter of size 8"	40	RM		
20	Providing and fixing in position PVC down water pipes 8"dia (4 Kg) (with necessary drop, clamps bottom seat etc. complete	15	RM		
	TOTAL				
	GST				
	GRAND TOTAL				