

**Renovation of Jalukbari Chariali Branch, Guwahati**  
**BOQ for Electrical Installation Works**

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Exclusive of GST on work contract)	Amount (Rs.) (Exclusive of GST on work contract)
1	<b>Sub-main line:-</b> Wiring in MS conduit of IS specification of Proper size with core PVC insulated stranded copper wire 11KV grade (Finolex/Havells/Polycab/ RR Kabel/ Richa/KEI or equivalent) and with supply ,installation, commissioning of all the materials required including proper termination, connection in complete as required from main DB to various DBs:-				
i)	with 3nos 4sq.mm (1ECC)	RM	30		
2	Computer/Raw Power point wiring in MS conduit of IS specification of proper size with 3nos 2.5sq.mm single core PVC insulated stranded copper wire 1.1KV grade(Finolex/Havells/Polycab/ RR Kabel/ Richa/KEI or equivalent) and with all material supply installation and commissioning complete from CDB/PDB(Raw) .The wiring shall be carried out on surface above false ceiling by chiseling the existing surface and plastering the same with cement etc. after fixing the MS conduit with all accessories like saddles screws, bends T-joint etc. 2 coats of painting Matching to the surface including supply installing, testing, commissioning of modular plate type switch and socket (Legrands / MK or equivalent) for computer terminal on sheet steel enclosure (cadmium plated),duly fitted with screw to the steel conduit and fixed to the wall partition furniture with all interconnection and proper earthing .All the opening shall be covered with blank plate and be sealed to make the box vermin proof.B48(maximum three points in single circuit)				
i)	With 3nos 6A socket with single 16A switch.	No.s	8		
ii)	With 2nos 16A socket with individual switch.	No.s	8		

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Exclusive of GST on work contract)	Amount (Rs.) (Exclusive of GST on work contract)
3	Supply, installation testing and commissioning of recessed type LED luminaire with complete PMMA Difuser with 35W LED lamp (size 2"X 2"). Make :- Bajaj/Havels/Phillips/Wipro/Crompton or equivalent	Nos	34		
5	Supply and installation of Wall Mounted fan 400 mm Metallic body and metallic Blade ,1400 rpm Havels / Crompton/bajaj/usha/orient make	No.s	10		
6	Supply and installation of 5 Meter roll 55W, IP20 Flexible LED Strip surface mounted alongwith required LED Driver as back lighting. Havells or equivalent make.Wall Mounted fan 400 mm Metallic body and metallic Blade ,1400 rpm Havels / Crompton/bajaj/usha/orient make	No.s	55		
7	Wiring for light/fan/exhaust fan points using 3 X 1.5 1.1 kV grade PVC insulated stranded copper conductor wire(Finolex/Havell's/Richa/RR kebel/KEI or equivalent) for phase, neutral and earth in 25 mm dia heavy duty MS conduit along with associated accessories like MS junction boxes, bends, saddles, screws et. concealed in wall, floor, under flooring, below false ceiling or on surface as well as suspended from ceiling with 25mm X 3 mm MS flat suspenders duly painted above false ceiling from individual light/Fan/Exhaust Fan point outlet. etc. to individual modular type switch boards, 10 Amp modular plate type switches etc.(MK/Legrand's/Havell's or equivalent), as required complete including circuit wiring with 3 X 2.5 sqmm. 1.1 kV grade PVC insulated stranded copper conductor wire and as per site requirement and as instructed by SBIIMS Engineer.				
i)	one light/fan controlled by one switch	No.s	15		
				Grand Total	

GST on work contract will be extra as applicable.



