



SBI OLD TOWN BRANCH

INTERIOR FURNISHIN WORKS PRICE BID

Tender ID: BHU201909012

Date: 18.09.2019

SI No	Item Description	Unit	Qty	Rate	Amount
1	Single Window Counter				
	<p>Providing and fixing in position 750 mm high single widnow counter with side credenza.The rate quoted for SWC shall consist of: a) Basic Structure: 19mm thick BWR/BWP ply for Top (1500 x 825 mm), Front (1500x750 mm), Two sides and one middle member (each 825x750 mm).Design and detail of the counters shall be as per Bank's new uniform colour, layout & elevation policy, with curvature on front made of flexi ply.</p> <p>b) One drawer unit (at every 1500-1800 mm length of counter) of 400mm wide (clear internal size). The chest of Drawer units shall have two smaller draw of equal size on top and one bigger vertical filling drawer at bottom with autolocking push type locks (Godrej/Link) and "C" type SS finish handles. The drawers to be made out of 12mm thick BWR/BWP ply at sides, bottom and rear, 19mm thick BWR/BWP plywood at front side.</p> <p>c) One Side Table (Credenza) of size 1000x450x750)mm with shutter unit of 600mm, with 1 drawer unit of 1 sliding draw and one openable shutter made with 19mm BWP/BWR ply Board with necessary hardware viz., 'W' hinges, handles, locks, tower bolts, etc. Ebco/Godrej make telescopic sliding key board tray and a mobile CPU stand.</p> <p>d) The table and credenza top- exposed surfaces shall be claddd with 1 mm thick laminate or equivalent make and shade as approved by EIC in the pattern as directed by the Engineer-in-charge with 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and other exposed surface to be finished with 1 mm thk laminate of approved make and shade as directed by EIC.</p> <p>e) All un-exposed surfaces shall be claddd with 0.8 mm thick laminate of approved make and shade.</p> <p>f) Rates are inclusive of : Ebco/Godrej make telescopic sliding key board tray and a mobile CPU stand and one godrej make night latch per counter.</p>	Nos	4		
2	Work-station for Officer/staff with side credenza				
a	Branch Manager				
	<p>Providing executive type manager table of 1800x900x750 mm and side credenza 1050x700x400 mm with table top of 25mm th. ply and a front drawer unit consisting 3 Nos of drawer units slides on telescopic slider made up of 19mm thk ply with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm thk laminates as per design of approved shade and the inner surface is finished with 0.8 mm thk laminate .The side credenza will have two drawer unit slides on telescopic slider and two cupboard unit. Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in duplicate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers , foot rest etc. of approved quality. It also include readymade keyboard of engineering plastic .The keyboard is a pullout type, fixed to channels and screwed to below table top . The CPU stand is made up with 19 mm ply with laminate finish as per design. The work should be mpleted including all labour and material.</p>	Nos	1		
b	Repair of BM/Officer table including side credenza irrespective of dimension				
	<p>Providing and fixing necessary hardwares such as channels, locks, handles, hinges, keyboard trays, sliding channels etc, as per the site condition. Remodeling the table as per Bank's new uniform colour, layout & elevation policy. Scrapping or making the existing surfce rough. Providing and fixing 4mm thick MDF board on the existing partition/door/table top or side etc., with necessary adhesive and nails/screws, hardwares etc. Thereafter, providing and fixing 1mm thick laminate of approved shade & colour, complete in all respect as per the direction of EIC. Polishing the beading etc, as per the site condition to match with the new ambience policy of the Bank. All unexposed surfaces of the table/ counters/ shelves to be painted with synthetic enamel paint/ fixing 0.8 mm thick laminate, as per the site condition.</p>	Nos	12		

3	Partition work (Semi Glazed/Solid- Full/Low Height)				
a	Providing and Erecting in position low/ full height (upto ceiling) partitions to be made out of 50 mm X 50 mm X 1.5mm thick Aluminum Tubular section frame work 600 mm c/c bothways (Vertical & Horizontal) fixed with 50 mm X 50 mm X 2.5mm thick Aluminum Angle Cleats with Pan Headed Screws covered with 9mm thick BWR/BWP PLY on both sides and ply fixed with Flat Headed Metal Screws. The aluminum members of partition shall rigidly fixed to the existing Ceiling /Floors / Beams & Side Walls, whichever is applicable & as directed, the alternate members and corner members fixed upto existing Slab, Beams, whichever applicable. The glass panel shall be 8mm thick (saint gobin or eqv.) duly supported by teak wood lipping and melamine polished. All exposed surfaces of the partition shall have approved brand and shade 1.0mm thick laminate from both sides as directed complete. The necessary openings in the partitions shall be provided for A.C. Grill, Electrical Conduits, Electrical Switches, A.C. Opening, Electric Fixtures and Fittings etc. complete as per requirements/instructions of the Architect / Engineer.	Sqm	36		
b	Scrapping or making the existing surface rough. Providing and fixing 4mm thick MDF board on the existing partition/door/table top or side etc., with necessary adhesive and nails/screws, hardwares etc. Thereafter, providing and fixing 1mm thick laminate of approved shade & colour, complete in all respect as per the direction of EIC. Polishing the beading etc, as per the site condition to match with the new ambience policy of the Bank.	sqm	38		
c	Removing and resizing the 12mm glass of low height partition or counters and fixing the same with S.S D bracket of size 32mm etc, as per the site condition.	Sqm	3		
4	Putty Finish				
	Applying and finishing wall surface with putty (Birla / equivalent) of required thickness to get smooth surface.	Sqm	50		
5	Doors				
a	Flap doors: Providing and fixing flap door shutter made out of 50mm x 75mm wood sections for frame work 6mm ply fixed on both sides with 1mm laminate including all hardware fittings of S.S. finish, door stopper, door buffer, auto locking SS Knob , 2 Nos. SS 2 ball-bearing hinges, slide bolt all complete as per drawing, design, specification & direction of Engineer-in-charge. The rate shall include cost of all materials, labour, taxes, T&P, transportation, royalties etc.	Sqm	1.5		
b	Flush doors: Size 3'x7' .Providing and fixing 30mm thickness flush door of Sylvam/ Globe/ century finished with teak wood lipping on all edges , three Stainless steel hinges for each door, one door stopper,, one one mortise lock of godrej make per door finished with 1mm thickness laminates of approved shade and colour (solid and glazed with 5mm thickness glass.Cost is incl. of SS door handles bothside 16" long (H - type), one Mortise lock of godrej make. Cost of Door closer shall be paid separately.	Nos	3		
6	Fixing of solid acrylic surface				
	Supplying, Fabrication and Installation of Dupont-Corian/Merino solid surface of 6 mm thk of approved shade. Applied on table Top, Sides and any where wall, Logo etc in place of 1mm thick laminate. The edges to be joined should be straight, smooth and clean. Joints should only be made with joint Adhesive for Dupont Corian. All corners of a cutout must be rounded to 5mm radius and the edges smoothed, both on top & bottom, all around a cutout. "L" & "U" shaped corners need smooth 5mm radius inside corner. All works done to the satisfaction of the Architect/Engineer. Note:- Work done including labour, material wastage, time limits, required hardware etc.	Sqm	9		
7	Entrance Door (Glazed)				
	Providing, fixing in position glazed entrance Double door OR Single door with patch fitting of approved make using 12mm thk toughened glass edge polished. The Door to consist of Heavy Duty Floor spring (paid extra), Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Corner Lock and the side fixed glass to have 2 Nos. Bottom Patch and 2 Nos. Upper Patch for each door to a neat finish etc., complete as per drawing	Sqm	2.6		
8	Storage Cabinet				
a	Providing and fixing 750mm high and depth of 450 storage cabinet having minimum 2 filing cabinets made out of 19 mm thk. BWP block board. All exposed surfaces shall be clad with 1 mm thick s laminates of approved make and shade except edges . Edges which shall be covered with 1mm thk PVC lipping as directed by the Engineer-in-charge and Cabinet Top is to be provided with 1mm thick laminate. All un-exposed surfaces shall be clad with 0.7 mm thick laminate of approved make and shade storage cabinet should be complete in all respect as per the drawing and direction of Engineer-in-charge including all hardware and locking arrangements. The rate shall include cost of all materials, labour, taxes, T&P, transportation, royalties etc.	Sqm	2.5		
b	Scrapping or making the existing surface rough. Providing and fixing 4mm thick MDF board on the existing storage unit top or side etc (exposed surface)., with necessary adhesive and nails/screws, hardwares etc. Thereafter, providing and fixing 1mm thick laminate of approved shade & colour, complete in all respect as per the direction of EIC. Polishing the beading etc, as per the site condition to match with the new ambience policy of the Bank.	Sqm	11.5		

9	Vertical Blinds				
	Providing & fixing vertical blinds of approve pattern and shade of Vista Leveller / Mac/equivalent as approved of 100 mm size including nylon twisted cords, ladder cords, powder coated aluminium top & bottom rail to windows/ partitions etc. cost includes all materials, labour, tax, lead, T&P etc. complete in all respects as per the direction of Bank's Engineer.	Sqm	11.5		
10	False Ceiling Gypsum				
	Providing & fixing at site plain gypsum board stepped/ flush false ceiling as per pattern & design made from 12.5mm thk paper reinforced gypboard sheets fixed with mainframe channels 80mm x 26mm x 0.5mm, every 450mm c/c or as mentioned in drawing intermediate channels 15mm x 45mm x 0.9mm at every 1220mm c/c with perimeter channel 20mm x 26mm x 0.5mm all along the wall shall be provided. The whole system to be suspended with strap bolts as recommended using rawl plugs 12.5mm dia. x 35mm long, with 6mm dia bolt & soffit cleat 27mm x 37mm x 25mm x 1.6mm thk. Gypboards to be screw fixed to the above framework using 25 mm dry wall screws. Provisions of melamine polished white beach wood moulding at wall / partition joints. Arrangements are to be made to accommodate light fixtures by forming recessed channels etc., wherever directed. Depressions, nails & screws, jointing & finishing etc., shall be done with jointing compound & paper tape. Ceiling to be leveled & free from cracks including fixing GI perimeter to hold light fittings. Item to be completed in all respect to the Architect's approval. Provision of Opening (openable) min 4 nos(for maintenance purpose) in ceiling as per site conditions are to be done with necessary timber frame work tied with perimeter channel properly such as to match the remaining area of ceiling by leveling perfectly complete in all respect. This rate includes cost of all materials, labours, royalty,taxes, lead & lift to the place of work& also the cost of all fittings, (Measurements shall be taken for flat surface)	Sqm	32		
11	Floor Spring				
	Providing and fixing floor spring of Godrej/ Dorma two speed in floors for fixing flush doors. Necessary pivot shall be provided at bottom and top so that the flush door shall be operated. The cost includes cutting and making the good of the floor etc complete as directed.	Nos	1.00		
12	Providing and fixing door closure two speed of Godrej/Dorma/Ebco as approved with all accessories to the doors.	Nos	2.00		
13	Emulsion Paint : Applying Roller Finishing the wall surafce with two or more coat of wall primer followed by two or more coats of plastic emulsion paints of asian or equiv of berger/ ICI/ with approved shade and colour. Cost also include touch up finishing to the wall surface with putty of Birla/ Asian/Berger to make the surface in line and level.	Sqm	750.00		
14	Vitrified Tile				
	Chipping and removing the existing tiles/PVC flooring from the site and disposing the desbris to the unobjectionable area of the Municipal corporation(as per the site condition and direted by the EIC). Providing and laying premium quality vitrified tile of size approx 600x600mm with thickness as specified by manufacturer as per sample approved by engineer in charge/ architect laid in backing cement mortar bed (1:6) of 15 to 20mm thick and neat cement slurry in proper line and level and in pattern as per drawing including surface preparation, neat cement, cleaning the joints etc cocomplete. The surafce shall be cured sufficiently. Work shall be executed at any level and height.. Rate includes P&L PCC 1:2:4 wherver required to make the surface in line and level. (make: Kajaria/ RAK/Johnson as per sample approved by engineer -in charge. (Basic price ranges from Rs.500 to 580 per sqm).	sqm	320.00		
15	Miscellaneous Work				
a	The contractor to quote for repair work as required to the cabinets/storage units as per site condition scope of work includes: replacement/ refixing of channels, locks handles and shifting of Counters/Tables/Work Stations/and Other movale furniture items as directed by EIC within branch premises labour charges.	Job	1.00		
b	Contractor to quote rate for catering away debris or any unused/ unnecessary furniture items from Bank's premises to outside muncipal dumping yard , including cost for the buy back items	Job	1.00		
TOTAL AMOUNT					
Note: GST shall be paid extra as per prevailing market rates					

Recommended Materials:	
1. Ply / Block board: Century/ Green / Sylvam BWP grade.	
2. Laminate: Century/ Marino/ Green lam (Unicore, texture, soild, wood shade, glossy etc as aproved),	
3. MDF Board: Century/ Green/ Action tesa/ Kit ply	
4. hardwares: Godrej/ ebco/hettich/ Dorma/Haffles	
5. Glas: Modi/TATA. Saingobain, (6). Upvc: Prominance/ fenesta/ rehau as approved, (7): Flush door: Century/ Sylvam, Green, Duro, (8): veneer: duro/ or equiv as aproved (9) Solid Surface: DuPoint/Merino or eqv.	