

#REF!

**ESTIMATE FOR AIR CONDITIONING WORKS**

Sl.No.	Description	UOM	Qty.	Rate (Rs.)	Amount (Rs.)
<b>Part A:</b>					
1	Supply of inverter type hi wall mounted split type air conditioner units indoor & outdoor complete with cordless remote control, of required capacity. Minimum 3 star rating 1.5 TR capacity (Banking hall)	Set	3		
2	Supply of inverter type hi wall mounted split type air conditioner units indoor & outdoor complete with cordless remote control, of required capacity. Minimum 3 star rating 1.0 TR capacity ( BM – 2, CO, ATM – 2)	Set	5		
Sub Total Part A					
<b>Part B:</b>					
1	Installation, testing and commissioning of hi wall mounted split type air conditioner units indoor & outdoor complete with in all aspects of required capacity. Rates should be inclusive of MS stand for mounting outdoor units, suitable electrical control cabling from indoor to outdoor units and end terminations also. 1.5 TR capacity	Set	3		
2	Installation, testing and commissioning of hi wall mounted split type air conditioner units indoor & outdoor complete with in all aspects of required capacity. Rates should be inclusive of MS stand for mounting outdoor units, suitable electrical control cabling from indoor to outdoor units and end terminations also. 1.0 TR capacity	Set	5		
3	Supply , installation ,testing and commissioning of Soft drawn copper piping with 9 mm thick Nitrile rubber insulation including all necessary fittings between indoor and out door air cooled condensers of the following sizes Suction line	RM	60		
4	Supply , installation ,testing and commissioning of Soft drawn copper piping with 9 mm thick Nitrile rubber insulation including all necessary fittings between indoor and out door air cooled condensers of the following sizes Liquid line	RM	60		
5	Drain line from indoor to outdoor machines as per standards	RM	50		
6	24 hours duty timer for alternative operation of 2 no.s of 1.5 TR capacity Acs fixed at BM chamber & ATM	Set	2		
7	Supply, installation, testing & commissioning of Stabilizer of 4kVA capacity	Nos.	8		
Sub Total Part B					
<b>Grand Total (Part A + Part B)</b>					