

		<b>SBI JHARPADA BRANCH</b>			
		<b>INTERIOR FURNISHIN WORKS PRICE BID</b>			
		<b>Tender ID: BHU201909019</b>		<b>Date: 20.09.2019</b>	
<b>1</b>	<b>Single Window Counter</b>				
	<p>Providing and fixing in position 750 mm high single widnow counter with side credenza. The rate quoted for SWC shall consist of: a) Basic Structure: 19mm thick BWR/BWP ply for Top (1500 x 825 mm), Front (1500x750 mm), Two sides and one middle member (each 825x750 mm). Design and detail of the counters shall be as per Bank's new uniform colour, layout &amp; elevation policy, with curvature on front made of flexi ply.</p> <p>b) One drawer unit ( at every 1500-1800 mm length of counter ) of 400mm wide (clear internal size). The chest of Drawer units shall have two smaller draw of equal size on top and one bigger vertical filling drawer at bottom with autolocking push type locks (Godrej/Link) and "C" type SS finish handles. The drawers to be made out of 12mm thick BWR/BWP ply at sides, bottom and rear, 19mm thick BWR/BWP plywood at front side.</p> <p>c) One Side Table (Credenza) of size 1000x450x750)mm with shutter unit of 600mm, with 1 drawer unit of 1 sliding draw and one openable shutter made with 19mm BWP/BWR ply Board with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc. Ebco/Godrej make telescopic sliding key board tray and a mobile CPU stand.</p> <p>d) The table and credenza top- exposed surfaces shall be clad with 1 mm thick laminate or equivalent make and shade as approved by EIC in the pattern as directed by the Engineer-in-charge with 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and other exposed surface to be finished with 1 mm thk laminate of approved make and shade as directed by EIC.</p> <p>e) All un-exposed surfaces shall be clad with 0.8 mm thick laminate of approved make and shade. f ) Rates are inclusive of : Ebco/Godrej make telescopic sliding key board tray and a mobile CPU stand and one godrej make night latch per counter.</p>	Nos	3		
<b>2</b>	<b>Work-station for Officer/staff with side credenza</b>				
<b>b</b>	<b>Repair of BM/Officer table including side credenza irrespective of dimension</b>				
	<p>Providing and fixing necessary hardwares such as channels, locks, handles, hinges, keyboard trays, sliding channels etc., as per the site condition. Remodeling the table as per Bank's new uniform colour, layout &amp; elevation policy. Scrapping or making the existing surfce rough. Providing and fixing 4mm thick MDF board on the existing partition/door/table top or side etc., with necessary adhesive and nails/screws, hardwares etc. Thereafter, providing and fixing 1mm thick laminate of approved shade &amp; colour, complete in all respect as per the direction of EIC. Polishing the beading etc, as per the site condition to match with the new ambience policy of the Bank. All unexposed surfaces of the table/ counters/ shelves to be painted with synthetic enamel paint/ fixing 0.8 mm thick laminate, as per the site condition.</p>	Nos	7		
<b>3</b>	<b>Partition work ( Semi Glazed/Solid- Full/Low Height)</b>				
<b>a</b>	<p>Providing and Erecting in position low/ full height (upto ceiling) partitions to be made out of 50 mm X 50 mm X 1.5mm thick Aluminum Tubular section frame work 600 mm c/c bothways (Vertical &amp; Horizontal) fixed with 50 mm X 50 mm X 2.5mm thick Aluminum Angle Cleats with Pan Headed Screws covered with 9mm thick BWR/BWP PLY on both sides and ply fixed with Flat Headed Metal Screws .The aluminum members of partition shall rigidly fixed to the existing Ceiling /Floors / Beams &amp; Side Walls, whichever is applicable &amp; as directed, the alternate members and corner members fixed upto existing Slab, Beams, whichever applicable. The glass panel shall be 8mm thick (saint gobin or eqv.) duly supported by teak wood lipping and melamine polished. All exposed surfaces of the partition shall have approved brand and shade 1.0mm thick laminate from both sides as directed complete. The necessary openings in the partitions shall be provided for A.C. Grill, Electrical Conduits, Electrical Switches, A.C. Opening, Electric Fixtures and Fittings etc. complete as per requirements/instructions of the Architect / Engineer.</p>	Sqm	27		
<b>b</b>	<p>Scrapping or making the existing surfce rough. Providing and fixing 4mm thick MDF board on the existing partition/door/table top or side etc., with necessary adhesive and nails/screws, hardwares etc. Thereafter, providing and fixing 1mm thick laminate of approved shade &amp; colour, complete in all respect as per the direction of EIC. Polishing the beading etc, as per the site condition to match with the new ambience policy of the Bank.</p>	sqm	40		
<b>c</b>	<p>Removing and resizing the 12mm glass of low height partition or counters and fixing the same with S.S D bracket of size 32mm etc, as per the site condition.</p>	Sqm	24		
<b>d</b>	<p>Providing, making and fixing in position new 12mm thick toughened clear float glass in the front side/ transcaction side of half height partitions of Single Window Counters of appropriate size . All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, fixing etching film and cut outs etc., for a neat finished job as per drawings and diretions etc., complete.</p>	Sqm	4		

4	<b>Putty Finish</b>				
	Applying and finishing wall surface with putty ( Birla / equivalent) of required thickness to get smooth surface.	Sqm	50		
5	<b>Doors</b>				
a	Flap doors: Providing and fixing flap door shutter made out of 50mm x 75mm wood sections for frame work 6mm ply fixed on both sides with 1mm laminate including all hardware fittings of S.S. finish, door stopper, door buffer, auto locking SS Knob , 2 Nos. SS 2 ball-bearing hinges, slide bolt all complete as per drawing, design, specification & direction of Engineer-in-charge. The rate shall include cost of all materials, labour, taxes, T&P, transportation, royalties etc.	Sqm	1.5		
6	<b>Fixing of solid acrylic surface</b>				
	Supplying, Fabrication and Installation of Dupont-Corlan/Merino solid surface of 6 mm thk of approved shade. Applied on table Top, Sides and any where wall, Logo etc in place of 1mm thick laminate. The edges to be joined should be straight, smooth and clean. Joints should only be made with joint Adhesive for Dupont Corlan. All corners of a cutout must be rounded to 5mm radius and the edges smoothed, both on top & bottom, all around a cutout. "L" & "U" shaped corners need smooth 5mm radius inside corner. All works done to the satisfaction of the Architect/Engineer. Note:- Work done including labour, material wastage, time limits, required hardware etc.	Sqm	7		
7	<b>Storage Cabinet</b>				
a	Providing and fixing 750mm high and depth of 450 storage cabinet having minimum 2 filing cabinets made out of 19 mm thk. BWP block board. All exposed surfaces shall be clad with 1 mm thick s laminates of approved make and shade except edges . Edges which shall be covered with 1mm thk PVC lipping as directed by the Engineer-in-charge and Cabinet Top is to be provided with 1mm thick laminate. All un-exposed surfaces shall be clad with 0.7 mm thick laminate of approved make and shade storage cabinet should be complete in all respect as per the drawing and direction of Engineer-in-charge including all hardware and locking arrangements. The rate shall include cost of all materials, labour, taxes, T&P, transportation, royalties etc.	Sqm	2		
b	Scrapping or making the existing surfe rough. Providing and fixing 4mm thick MDF board on the existing storage unit top or side etc ( exposed surface)., with necessary adhesive and nails/screws, hardwares etc. Thereafter, providing and fixing 1mm thick laminate of approved shade & colour, complete in all respect as per the direction of EIC. Polishing the beading etc, as per the site condition to match with the new ambience policy of the Bank.	Sqm	5		
8	<b>Wall panelling</b> with BWP Ply board: Providing and fixing aluminum frame 25mmx50mmx1.20mm with a grid of 600mmx600mm duly fixed with screws to the walls and finished with 6mm thick thick ply BWP grade and and finished with 1mm thick laminate of approved colour and shade.	sqm	26		
9	<b>False Ceiling Grid type</b>				
	Providing and fixing modular grid ceiling with armstrong make Rh-95 anf tegular edge 600x600 x15mm as specified by manufacturer.Cost is also inclusive of repair of existing grid false ceiling channels and other accessories by providing all necessary materials as required at the site, complete in all respect as per the direction of EIC.	Sqm	10		
10	<b>Floor Spring</b>				
	Providing and fixing floor spring of Godrej/ Dorma two speed in floors for fixing flush doors. Necessary pivot shall be provided at bottom and top so that the flush door shall be operated. The cost includes cutting and making the good of the floor etc complete as directed.	Nos	1.00		
11	Providing and fixing door closure two speed of Godrej/Dorma/Ebco as approved with all accessories to the doors.	Nos	1.00		
12	<b>Emulsion Paint</b> : Applying Roller Finishing the wall surafce with two or more coat of wall primer followed by two or more coats of plastic emulsion paints of asian or equiv of berger/ ICI/ with approved shade and colour. Cost also include touch up finishing to the wall surface with putty of Birla/ Asian/Berger to make the surface in line and level.	Sqm	320.00		
13	<b>Miscellaneous Work</b>				
a	The contractor to quote for repair work as required to the cabinets/storage units as per site condition scope of work includes: replacement/ refixing of channels, locks handles and shifting of Counters/Tables/Work Stations/and Other moveable furniture items as directed by EIC within branch premises labour charges.	Job	1.00		
b	Contractor to quote rate for catering away debris or any unused/ unnecessary furniture items from Bank's premises to outside muncipal dumping yard , including cost for the buy back items & deep cleaning of branch premises : flooring tiles, furnitures,glass etc.	Job	1.00		
<b>TOTAL AMOUNT</b>					
Note: GST shall be paid extra as per prevailing market rates					

<b>Recommended Materials:</b>				
1. Ply / Block board: Century/ Green / Sylvam BWP grade,				
2. Laminate: Century/ Marino/ Green lam (Unicore, texture, soild, wood shade, glossy etc as aproved),				
3. MDF Board: Century/ Green/ Action tesa/ Kit ply				
4. hardwares: Godrej/ ebco/hettich/ Dorma/Haffles				
5. Glas: Modi/TATA. Saingobain, (6). Upvc: Prominace/ fenesta/ rehau as approved, (7): Flush door: Century/ Sylvam, Green, Duro, (8): veneer: duro/ or equiv as approved				