

AIR CONDITIONING WORKS AT BILGRAM BRANCH, A.O. KANPUR

| S.No. | Item Description | Unit | Qty | Rate | Amount |
|-------|--|------|-----|------|--------|
| 1 | Supply, installation, testing and commissioning (SITC) of air cooling type, 2.0 Tr, Cassette type split air conditioner in recessed manner in grid type false ceiling with full function wireless remote and auto restart feature, complete in all respects with indoor/outdoor unit, gas charge etc. Item should also include 5 KVA hi/lo cut off, TDR relay start stabilizer. (BRANCH GROUND FLOOR HALL AREA):Acceptable makes AC: Daikin/Hitachi/Carrier/ Blue Star/Voltas/Toshiba Make of Stabilizer: Servel/V Guard/Stambh/Inmag | Set | 3 | | |
| 2 | Supply, installation, testing & commissioning(SITC) of 1.5TR high wall/split type, 3 star (highest star rating), BEE rated, mounted type air conditioner, wireless remote controlled with auto restart feature complete in all respect with indoor, outdoor unit, <u>copper condenser & copper cooling coil</u> interconnecting piping, wiring/ installation / drain pipe etc. (Upto 3 meters length). Item should also include 4 KVA hi/lo cut off, TDR relay start stabilizer. Acceptable Makes of AC: Daikin/Hitachi/Carrier/ Blue Star/Voltas/Toshiba Make of Stabilizer: Servel/V Guard/Stambh/Inmag | Set | 1 | | |
| 3 | a) Supply and installation of robust MS angle for 2.0 tr Cassette AC , two MS flat fabricated floor/wall mounting stand suitable for outdoor units , painted with one coat of primer and two coats of synthetic enamel outdoor type paint including it's grouting and making good of damages, complete in all respects. | set | 3 | | |
| 4 | b) Supply and installation of robust MS angle for 1.5 tr Cassette AC , two MS flat fabricated floor/wall mounting stand suitable for outdoor units , painted with one coat of primer and two coats of synthetic enamel outdoor type paint including it's grouting and making good of damages, complete in all respects. | Set | 1 | | |
| 5 | a) Copper pipe for refrigerant piping for 2.0Tr cassette AC set as per company specs and discharge to be measured as one composite run and not separately) with insulation, drainage pipe, etc | Mtr | 45 | | |
| 6 | b) Copper pipe for refrigerant piping for 1.5 Tr split air conditioner as per company specs and discharge to be measured as one composite run and not separately) with insulation, drainage pipe, etc. | Mtr | 15 | | |
| 7 | a) 4 Core Interconnecting standard wire/cable between indoor and outdoor units for 2.0 tr | Mtr | 50 | | |
| 8 | b) 4 core Interconnecting standard wire/cable between indoor and outdoor units for 1.5 tr | Mtr | 20 | | |
| 9 | PVC drain pipe . | Mtr | 65 | | |
| | TOTAL | | | | |