

SBI- SAMBALPUR BAZAR, CIVIL WORKS BILL OF QUANTITIES (RATE NOT TO BE FILLED)			
S.No	ITEM SPECIFICATION	UNIT	QTY
1	Flooring		
a	Vitrified Tiles Flooring		
	Providing and laying 600mm x 600mm nano polished double charged vitrified shine tiles of Jonson/ Nitco/ Kajaria/RAK or equivalent make with water absorption less than 0.08% and confirming to IS: 15622 of approved make, in all colours and shades, laid on 20 mm thk. cement mortar 1;4 (1 Cement : 4 Coarse Sand), including grouting the joints with white cement and matching pigment etc. all complete, including cost of all materials, labour, T&P etc. required for the work.	SQM	180
2	Painting Works		
A	Internal Wall Painting		
	Providing and applying two or more coats of Acrylic Emlusion paint to internal walls, columns, beams ceiling etc. Over a coat of primer as per manufacturer's specification including all labour and materials complete in all floors of approved make and shade.	SQM	800
B	Wall Putty on Internal Surfaces Only		
	Providing 2.0 mm thick of Birla white wall care putty (Water resistant white cement based putty for concrete mortar walls and ceiling) after removing all loosely adhering material from the wall surface of 1 mm thickness.	SQM	400
C	Providing and applying two or more coats enamel paint to door and windows, MS works of approved shade and make	SQM	100
3	Brick Masonry work in cement mortar (1:6) in full Brick thick walls using K.B. Bricks having minimum crushing strength of 50 kg/ cm ² after immersing the bricks for 24 hours in water before use with all necessary projections, as per design chamfering, watering and curing etc. including cost, conveyance, royalties and taxes of all material and cost of etc. complete.	CUM	2
4	Providing and laying 16 mm thick cement plaster in proportion 1:6 to all levels to external/internal surface of the wall with sand cement mortar including racking out joints roughning the concrete surface rounding off chamfering & filling of the porturated surface of the brick where necessary as per direction including working in narrow width with cost of all labour, materials scaffolding etc complete in all floors in all respect as required for the completion of the work	SQM	100