

SBI- KHETRAJPUR, CIVIL WORKS			
BILL OF QUANTITIES			
(RATE NOT TO BE FILLED)			
S.No	ITEM SPECIFICATION	UNIT	QTY
1	Flooring Works in Banking Hall Only		
	Providing and laying 600mm x 600mm nano polished double charged vitrified shine tiles of Jonson/ Nitco/ Kajaria/RAK or equivalent make with water absorption less than 0.08% and confirming to IS: 15622 of approved make, in all colours and shades, laid on 20 mm thk. cement mortar 1:4 (1 Cement : 4 Coarse Sand), including grouting the joints with white cement and matching pigment etc. all complete, including cost of all materials, labour, T&P etc. required for the work. Tiles flooring is proposed for ground floor Banking Hall only	Sqm	250.00
2	Painting Works		
a	Providing and applying two or more coats of Acrylic Emlusion paint to internal walls, columns, beams ceiling etc. Over a coat of primer as per manufacturer's specification including all labour and materials complete in all floors of approved make and shade.	Sqm	800.00
b	Providing 2.0 mm thick of Birla white wall care putty (Water resistant white cement based putty for concrete mortar walls and ceiling) after removing all loosely adhering material from the wall surface of 1 mm thickness.	Sqm	600.00
c	Providing and applying two or more coats enamel paint to door and windows, MS works of approved shade and make	Sqm	200.00