



SBI INFRA MANAGEMENT SOLUTIONS PVT.LTD.

CIRCLE OFFICE, THIRD FLOOR, STATE BANK OF INDIA, SYNERGY BUILDING, C-6, G-BLOCK, BANDRA KURLA COMPLEX, BANDRA EAST, MUMBAI-400051

PART – B: FINANCIAL BID

TENDER ID MUM201909011

DATE: 17.09.2019

TENDER FOR:

INTERIOR REPAIR AND REARRANGEMENT WORK OF UDAYNAGAR BRANCH

TENDER SUBMITTED BY:

NAME : _____

ADDRESS : _____

DATE : _____

TENDER INVITED BY:

Vice President & Circle Head,

SBI Infra Management Solutions Pvt. Ltd; 3rd floor, Circle Office, State Bank of India, Synergy building, C-6, G-Block, Bandra -Kurla complex, Bandra East, Mumbai-400051.

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
1	Single window counter: Remodification of existing single window counters with 6 mm thick MR grade ply structure and glass (height 750 mm) as per design, All exposed external surface finished with 1 mm laminate with new CPU stand of 19mm thick MR grade ply including cable manager, a key board tray with telescopic arrangement.	7.2	Rmt		
2	Glass partition: Providing and fixing 10 mm thick glass with etching as per design for low height partitions held with SS clits (D brackets). All exposed glass edges with rounded moulding and crystal polish. All exposed woodwork to be finished in 3 coats of French polish/ melamine polish.	4	Sqm		
3	Providing & fixing in position floor spring for receiving glass door of approved make. (DORMA / HETTICH or equivalent)	1	No.		
4	Providing and fixing in position door closer of approved make (Hyper / Godrej or equivalent).	3	No		
5	Tables: Providing & fixing in position tables made of 18 mm MR grade Ply at top, side and front, support along with drawer unit & Key board tray with telescopic arrangement & CPU base resting on foot rest. 18 mm th MR grade ply modesty panel. All external surfaces to be finished with 1 mm thick laminate and internal surface finished with 0.8 mm of approved shade and make. Including powder coated fittings like sliding channels, for key board & drawers, medium duty hinges for shutter, cable manager. S.S. handles in approved design and size and locks wherever directed in approved make. All exposed plywood edges to be finished with 6mm th. Teak wood beading with french polish in approved shade and necessary locks to shutters etc. complete in all respects.				
a	Grahak Mitra table 1350 mm*750mm*675mm	1	No.		
6	Low height & Full height storage: Providing & fixing in position 400mm deep low/full height storage made of 19mm MR grade ply at top, front and side with 12 mm MR grade ply at back, all external faces including back to be finished with 1 mm thick multi-colour laminate at outside and inside finished with 0.8 mm laminate with locking and SS handle arrangement of approved make complete with openable type shutter, beading patti etc. All exposed plywood edges to be finished with 6mm th. Teak wood beading with french polish in approved shade complete in all respect.	2	Sqm		
10	Vertical blinds : Providing & fixing in position 3" / 4" wide vertical blinds of approved make (Vista / Aerolux) and shade with all accessories and necessary fittings etc.	15	Sq M		
11	Providing & fixing Panelling out of 6 mm thick ply and 1.0 mm thick laminate of approved shade and make to existing columns , tables , partitions, doors along with necessary accessories required if any etc. complete	280	sq m		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
12	Providing and fixing panelling on External walls and for External Rolling Shutters boxing. Framing shall consist of Both ways horizontally and vertically on the wall/column with Aluminium Sections of 2"x1" as directed by Bank /Architect. This framing would be covered with 6mm thk. Comm. Ply (In case of wooden frames), finished with 3mm thick exterior grade multi-coloured "Aluminium Composite Panel". The rate shall be inclusive of necessary scaffolding, cut-outs, fixtures and fittings, sealant etc. complete.	5	Sqm		
13	Providing and applying acrylic emulsion paint of approved quality, shade and colour in 2 or more coats to achieve desired result including applying one coat of primer of cement paint, preparing the surface by cleaning the dust/dirt by watering/brushing the surfaces, filling in cracks/crevices ,scaffolding at all levels, necessary lead, lifts etc. complete	50	sq m		
14	Providing and Laying vitrified tiles of approved make and quality of required size for flooring and skirting in required position laid on bed of C.M.1:4 including cement float, filling joint with white / colour cement slurry, cleaning, curing, complete. 600 mm x 600 mm. size (Basic rate = Rs. 70/- per Sqft) The item rate shall be inclusive of removing the existing flooring & skirting.	10	sq m		
15	Providing and fixing in position 12mm thick toughened glass door including fixed side panel. The door to be fixed with heavy duty Dorma make floor spring, providing 300mm long 30mm dia SS pipe handle and door lock of Ozone/Dorma or equivalent make with necessary cutting chases in floor and restoring the same to its original position complete. Rate to include providing suitable wooden Top and bottom rail, frosted film as per detailed Engineering drawing complete. The item includes removal of existing door and buyback.	10	Sqm		
16	Full height glazed/Partly glazed / partly panelled partition : Providing and fixing in position partly glazed & partly panelled partition made of 50 mm x 50mm x 1.2mm medium duty aluminium hollow square pipes framed at 0.60 m. to 0.45 m c/c both ways covered with 6 mm MR grade ply and 1mm multi-colour laminate of approved shade and make with 6 mm thick glass panel with etching as per design and / or necessary beading patti including 3 coats of french polishing including door shutters as per architectural design with heavy duty hinges handles / handles / locks etc. of approved make.	5	Sqm		
17	Providing & fixing Panelling out of 6 mm thick ply and finished in 4mm thk approved veneer finished with melamine polish existing to columns , tables , partitions, doors along with necessary accessories required if any etc. complete	40	sq m		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
18	Providing & fixing Panelling in out of 12 mm thick ply and 1.0 mm thick laminate with aluminium frame 50mmx25mmx1.2 mm in walls with screws and finished with approved shade and make to column with accessories and as per Bank engineer's instructions etc. complete	5	sq m		
19	Providing and fixing granite stone to treads and risers of staircase and entrance including all necessary material and labour.	5	Sq MTR		

S U M M A R Y :			
	Total of Interior Work	Rs.	
	Less discount (if any)	Rs.	
	Total cost of work Tendered	Rs.	
	Add SGST @ 9%	Rs.	
	Add CGST @ 9%	Rs.	
	FINAL AMOUNT INCLUDING GST	Rs.	

Total Amount
Rupees in words: _____

Signature & Seal of Contractor

Date: _____