

BOQ OF AIR-CONDITIONING WORK FOR SBI CHANSAD BRANCH

Preamble : The vendor shall work in coordination & cooperation with other execution agencies. Variation in quantity in addition to the tender quantity shall be got approved before execution. Since the Premises is not vacant, the work may be carried out by contractor from evening till late night and on holidays, for which no extra payment shall be made. Time is essence of the contract.

No	Description	Qty.	Unit	Rate	Amount
<u>(Make : CARRIER (NO MIDEA) / VOLTAS / DAIKIN / HITACHI / TOSHIBA / TRANE / MISTUBISHI Heavy Industries)</u>					
<u>PART-I : SUPPLY OF MACHINES</u>					
1	Supply of 2.0TR Hi-wall(Copper Condenser) split unit (3 STAR, BEE rating WEF 1-1-18)(including 4 mtr. Copper pipe and interconnecting cable)	1	No.		
2	Supply of 1.5TR Hi-wall(Copper Condenser) split unit (3 STAR, BEE rating WEF 1-1-18)(including 4 mtr. Copper pipe and interconnecting cable)	4	No.		
3	Supply of 1.0TR Hi-wall(Copper Condenser) split unit (3 STAR, BEE rating WEF 1-1-18)(including 4 mtr. Copper pipe and interconnecting cable)	2	No.		
Total for Part -I (machine part)					
<u>PART-II : LOW SIDE WORK</u>					
1	Installation of IDU & ODU of 2.0 / 1.5 / 1.0 TR Hi-wall (Copper Condenser) split unit with first oil & gas charge & commissioning etc. (Include Supply of 4mtr free insulated (6mm Nitrile Rubber with sleeve) copper tube electrical cable for indoor to Out door unit & mounting stand for ODU)	7	Nos.		
2	Referigerant piping 0.8 mm thickness (Make : Mandav / Totaline) insulated (6mm Nitrile Rubber with sleeve) copper tube between indoor to out door unit of 1.0 / 1.5 / 2.0 TR Hi-wall split unit. (Only single distance will be considered irrespective of number of circuits/compressors)	70	Mtr		
3	Electrical control Cabling in ISI PVC Pipe between indoor to out door unit beyond 4 Rmt dist. of 1 / 1.5 / 2.0 TR/ 3.0 TR Hi-wall split unit.(2.5 sqmm , 3 core RR Kable/ Finolex/ Havells)(Only single distance will be considered irrespective of number of circuits/compressors)	75	Mtr		

BOQ OF AIR-CONDITIONING WORK FOR SBI CHANSAD BRANCH

No	Description	Qty.	Unit	Rate	Amount
4	25/32mm Dia UPVC drain pipe with insulation of Dutron / Supreme / Astral make - schedule 40 pipe, white in colour, joint properly glued with UPVC adhesive for water outlet from indoor unit.	90	Mtr		
6	Misc civil work like wall opening to pass ducts & pipes, plastering and refinishing of the same to the original finish as per the site requirements	1	LOT		
	Total for Part -II (low side work)				
	Total for Part -I & Part -II				
	<u>Note:-</u>				
*	Only 1 single order will be placed for both supply & installation work.				
*	ALL RATES SHOULD BE INCLUSIVE OF ALL TAXES EXCLUDING GST WHATEVER IS APPLICABLE.				
*	Rates quoted in the tender should be for 5 star rating machines for 1 , 1.5 & 2.0 tonnes (As per BEE star rating wef 01-01-2018)				
*	Machine Model Number should be mentioned of the Machines for which the rates are quoted. Only one make for AC shall be quoted for the entire project. AC units shall be with				
*	All payments shall be recommended by the architect as per actual quantity of items executed at site.				
*	All chipping/zari/finishing in wall, beam, Floor(if required) etc. is to be carried out by the AC contractor , no extra payment shall be made for the said work.				
*	The rate quoted by the contractor in the column where quantity and unit rate are not required as per tender the contractor rate quoted for such items are not necessary been accepted by the bank if required the item in future use.				