

**BILLS OF QUANTITIES FOR FURNISHING WORK OF STATE BANK OF INDIA OF CURRENCY CHEST
THARAD (0560) BRANCH, AT THARAD, DIST. BANASKANTHA**

BILLS OF QUANTITIES

(NOT TO BE FILLED BY THE BIDDERS)

Sr. No.	Description	Quantity	Unit
---------	-------------	----------	------

Note : Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris ,cleaning cutting wastage etc. all taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills

[A] FURNISHING WORK

1	SINGLE WINDOW COUNTER STRAIGHT SIZE 5'-0" X 2'-9" WITH Front side Toughend Glass Partition above Transaction Top (2'-6" Height) and	6	NO
---	--	---	----

Side Credenza Size 3'-0" x 1'-4" x 2'-6" Height

Supplying, fixing and keeping in position single window counter complete as per design, and drawing made out of 18mm thick commercial ply wood of approved make, complete with 19 mm. C.P. Teak wood lipping on all edges wherever required.

The cost shall be inclusive of S & F of a drawer and shelf unit with 18mm thick commercial plywood and with approved make multipurpose Auto Lock in drawer and shelf unit. The cost shall also be inclusive of the following.

[a] size :

Description:	L	B	Ht.
Writing Top	5'-0"	2'-9"	2'-6"
Transaction Top	5'-0"		2'-6"
4 Drawers with pegon hole	2'-0"	1'-3"	2'-0"

Computer key Board

Supplying and fixing metal key Board of approved make in counter as per design and instructions.

- [b] Working table top and edges shall be finished with **6mm thick white corian** of approved make, as per drawing and direction with all labour and materials all edges should be finished with corian
- [c] Transaction Top :3x6 mm thick flexy ply wood round shape with **6mm thick white corian** shall be provided at front as per design, all edges should be finished with corian
- [d] Front pannel (Front Apron) shall be finished with 6mm thick 18" high, glass blue lacquered glass of approved make and fixed on 18mm thick commercial ply wood with Natural Silicon gum as per manufacturers specification of approved make All complete as per drawing
- [e] Foot rest of 3" x 1.5" in C.P. Teak wood. and CPU stand 16" x 24"
- [f] All wood work shall be laquer polished to a smooth and uniform finish of choice colour and shade.
- [g] All fittings like S.S. handle/ approved make **Auto Lock** to each drawer and cabinet doors, piano hinges, ball catcher stopper, metal cable manager etc. approved make heavy duty full extension channel in drawers.
- [h] Heavy duty telescope full extension sliding channel of approved make shall be used in all drawers.
- [i] **All the surface without lamination shall be Synthetic enamel paint/polishing of approved shade etc complte**
- [j] Counter shall be made independent in Length of 5'-0" and properly placed between two partition.Counter measured between two partition and paid (**FOR DETAILS REFER DRG. NO- 3**)

(NOT TO BE FILLED BY THE BIDDERS)

Sr. No.	Description	Quantity	Unit
[k]	<p>Providing and fixing 12 mm thick Toughened Glass partition on counter front side top as follows. Providing and fixing 12 mm thick Toughened float glass with polished edges shall be fixed with necessary S.S Brush finish brackets support on wooden partition as directed. Making necessary cut out in glass all edges of glass shall be Diamond cut polished edges as directed complete.</p>		
[l]	<p>Side Credenza For S.W Countwer Size 3'-0"x1'-4" x 2'-6" ht. With openable shutter Side Table top and edges shall be finished with 6 mmThick White Corian on Top and Edges. All other visible surface shall be finished with 1.00 mm th laminate Supplying and providing side cabinet for keeping computer and printer size 1'-4" width 2'-6" height and 3'-0" length. Openable shutters as directed. Cabinet shall be made from 18mm thick commercial ply wood &. Back shall be made from 6mm th commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with 1.0mm th laminate and approved group lock, handle, hinges, magnet catch. Edges to be finished with teak wood lipping etc. including all internal surface to be polished/ Synthetic enamel paint etc. As per drawing and instruction of Architect/Bank Complete FINISHING DETAILS IN NUTSHELL: 1) Table Top : 6mm thick white corian 2) Front Apron: Round corian and 6 mm thick lacquered blue glass fixed with Natural Silicon 3) Facing of Drawers: 1.00 mm thick laminate finish 4) Front Side Glass Partition : 12 mm thick Toughened glass Partition 750mm Height 5) Side Credenza- Top: 6mm thick White Corian Finish and Shutter : 1.00 mm thick Laminate</p>		
1[A]	<p>Same as above Item No-1 but without Front side Glass Partition SINGLE WINDOW COUNTER STRAIGHT For Service Manager SIZE 5'-0" X 2'-9" WITH Without Front side Glass Partition above Transaction Top (2'-6" Height) and Side Credenza Size 3'-0" x 1'-4" x 2'-6" Height</p>	1	NO
1[B]	<p>Providing and fixing curved shape 12mm thick Toughened float Glass partition between Single Window counter partition front side as follows. 12 mm thick Toughened clear float glass with polished edges shall be fixed with silicon and T.W beading support on wooden partition as directed. All edges of glass shall be Diamond cut polished edges as directed complete. (Glass for Measurement outer longer width and height shall be measured and paid)</p>	3	SQMT
3	<p>TABLES</p>		
3[A]	<p>MANAGER TABLE SIZE: 6'-0" X 2'-9" X2'-6" HT..with Teak veneer with PU coating finish on Table Top ,sides & Edges and all other visible surfaces etc complete as follows With Side Credenza Size 3'-0" x 1'-4" x 2'-6" Height Supplying and providing Table as per the following description Size 6'-0" x 2'-9". Table top shall be made from 18mm thick commercial ply wood with 3.50 mm thick Teak veneer with PU Coating with necessary intermediates support. Table top shall be supported by 18mm thick commercial ply wood with wooden framing. Storage cabinet of 1'-3" x 2'-0" x 2'-6" shall be provided using 18mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make , grouplock / S.S. Handle. Computer Key board of metal of approved make shall be provided. Exposed surfaces of the cabinete shall have Teak veneer with PU polish . Foot rest of 1 1/2" x 3" T.W members shall be provided. All the surface without veneer shall be polished/painting.</p>	1	NO

(NOT TO BE FILLED BY THE BIDDERS)

Sr. No.	Description	Quantity	Unit
	<p>Apron (Modesty Panel) made from 18mm thick ply wood with teak veneer PU Finish & groove pattern as per drawing Table side made from 18mm thick ply wood with 3.50 mm thick teak veneer with PU coating finish shall be provided in a pattern as per drawing directed. Veneer to be provided only on visible surface Table shall have stand for keeping CPU and metallic cable Manager shall be provided in table top. All exposed edges of plywood shall have veneer with smooth edges & corners Exposed edges of Table Top, Leg panel & Side Shelf shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width. All the surface without teak veneer shall be synthetic enamel paint /polished of approved shade As per drawing and instruction of Architect/Bank Complete (FOR DETAILS REFER DRG. NO- 4) FINISHING DETAILS IN NUTSHELL: 1) Table Top : Teak Veneer with PU Coating & Burma Teak beading on Edges with PU Coating 2) Front Apron & Sides: Teak Veneer with PU Coating 3) Facing of Drawers: Teak Veneer with PU Coating</p>		
[i]	<p>SIDE CREDENZA (SIDE TABLE) Side Credenza Size 3'-3"x1'-4" x 2'-3" Openable shutter with 3.50mm thick Teak veneer with PU Coating finish on Top , front side shutter and 35 mmx6mm thick Burma Teak beading on Top Edges with PU Coating. Veneer to be provided only on visible surface etc complete as follows Supplying and providing side cabinet for keeping computer and printer size 1'-4" width 2'-6" height and 3'-6" length. Having openable shutters as directed. Cabinet shall be made from 18mm thick commercial ply wood with 3.50mm thick veneer with PU Finish. back shall be made from 6mm th commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with veneer finished and approved make group lock, handle, hinges, magnet catch. , Rate includes all necessary provisions for installing computers.All the surface without veneer shall be polished/synthetic enamel paint Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width. As per drawing and instruction of Architect/Bank Complete (FOR DETAILS REFER DRG. NO- 4)</p>		
3[B]	<p>OFFICER TABLE FOR CASH OFFICER AND OTHER TABLE With Side Credenza Size 3'-0" x 1'-4" x 2'-6" Height Same as above but Item No 3[A] size 5'-0" x 2'-6" with storage unit 4 Nos Drawer in table Finishing as follows Table Top finished with 3.50mm thick Teak veneer with PU Coating including edges covering Apron (Modesty Panel) made from 18mm thick ply wood with 1 mm thick frosty white laminate of approved make shall be provided in a pattern as per drawing /directed. Table side made from 18mm thick ply wood with 1mm thick frosty white laminate shall be provided in a pattern as per drawing/ directed. All the surface without lamination shall have polished/ synthetic enamel paint of approved shade As per drawing and instruction of Architect/Bank Complete (FOR DETAILS REFER DRG. NO- 5)</p>	8	NO

(NOT TO BE FILLED BY THE BIDDERS)

Sr. No.	Description	Quantity	Unit
	<p>FINISHING DETAILS IN NUTSHELL: For Item No 3[A]</p> <p>1) Table Top : Teak Veneer with PU Coating & Burma Teak beading on Edges with PU Coating</p> <p>2) Front Apron & Sides: Frosty white Laminate</p> <p>3) Facing of Drawers: 1.0 mm thick Laminate Finish</p> <p>SIDE CREDENZA (SIDE TABLE) for Sales officer and Service Manager and Other Officer</p> <p>Same as above Item No 3[A] but Teak veneer with PU Finish on Top & Burma T.W Edges. Other surfaces finished with laminate finished Size shall be 3'-3" x 1'-4" x 2'-6" ht. with openable shutters as directed.</p> <p>As per drawing and instruction of Architect/Bank Complete (FOR DETAILS REFER DRG. NO- 5)</p>		
3[C]	<p>CASH COUNTING TABLE (Laminate Finish on Table Top and Drawer shutter finish)</p> <p>Providing and fixing Cash Counting Table having width of 2'-0" using 18mm thick Commercial plywood for Top and verticale support, Providing storage cabinet one drawer and shutter (2Nos Unit),Group lock, SS handle in counter as directed complete. 1.0 mm thick Laminate finish on table Top and shutter front side of the counter shall have 1.0 mm thick laminate. Providing Foot rest of 3" x 1.5" in C.P. Teak wood,All the surface not laminated shall be polished/ synthetic enamel paint complete as directed.</p>	2.50	RMT
3[D]	<p>GRAHAK MITRA TABLE</p> <p>Same as above item no 3[a] but Approx Size 5'-6"x 2'-3" wide with storage unit in Table with 4mm thick MDF board + Blue and white PU Coating finishing on all exposed visible surface As per drawing and instruction of Architect/Bank Complete For Grahak Mitra/Tech Mitra (Help Desk Table)</p> <p>Table top made from 18mm thick ply wood + 4mm thick MDF board with PU coating finish</p> <p>Apron (Front side) made from 18mm thick ply wood + 4mm MDF board with PU Coating finish</p> <p>Both sides made from 18mm thick ply wood + 4mm MDF board with PU Coating finish</p> <p>3" thick Partition above working table top made from 18mm thick+6mm thick ply wood with necessary framing with 4mm thick MDF board + PU Coating finish.</p> <p>Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.</p> <p>Drawer Storage Unit- 1'-4" W x 2'-0" D, 2 Nos Drawer on top and rest 1 No shutter-</p> <p>As per drawing and instruction of Architect/Bank Complete (FOR DETAILS REFER DRG. NO-6)</p> <p>FINISHING DETAILS IN NUTSHELL:</p> <p>1) Table Top : 18mm Thick Plywood with 4mm thick MDF with High gloss white PU Coating</p> <p>2) Front Apron & Sides: 4mm thick MDF with High gloss white/blue PU Coating</p> <p>3) Facing of Drawers: 1.0 mm thick Laminate finish</p>	1	NO

(NOT TO BE FILLED BY THE BIDDERS)

Sr. No.	Description	Quantity	Unit
3[E]	SERVER ROOM TABLE Providing and fixing Server Room Table having width of 2'-3" using 18mm thick Commercial plywood for Top and verticle support, Providing storage cabinet 1Nos drawer+1 Shutter,,key board,Group lock, SS handle in counter as directed complete. 1 mm thick laminate finish on table Top and front sides of the counter shall have 1.0 mm thick laminate on visible surface.. Providing Foot rest of 3" x 1.5" in C.P. Teak wood,All the surface not laminated shall be polished/synthetic enamel paint complete as directed.	1.80	RMT
3[F]	DINING TABLE Approx Size 5'-0"x 2'-6" Supplying and Providing Dining Table of 6'-0" x 3'-0" x 2'-6" height 1" x 1.5 ht." T.W beading shall be fixed on border .Top shall be made of 18 mm thick commercial plywood with additional 18mm thick Ply wood patta of required width on edges with 1.0 mm thick laminate on top of approved shade brand and. supports of the Table shall be made of 2" x 2" T.W. members in a Design as directed. All surfaces not laminated shall be lacquer polished. Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.	1	NO
4	SIDE STORAGE CABINATE Supplying and providing storage cabinete with Teak Veneer with PU Coating on Top,Front Shutter & 35 mmx6mm thick Burma Teak beading on Edges with PU Coating. Veneer to be provided only on visible surfaces Size : Depth 1'-4" ,. 2'-6" ht. having openable shutter as directed. storage Cabinet shall be made from 18mm thick commercial ply wood for Top with Teak veneer with PU Coating finish and 18mm thick ply wood for verticle, shelves, shutters and 6mm commercial plywood for backing with 3.5 mm thick Teak Veneer with PU coating on all exposed surface. with verticle (at 3'-0" c/c) shelves at 1'-3" c/c Openable shutters in 18mm thick commercial ply wood with all S.S hinges, towers bolts, powder coated handle, ball catches, S.S approved make (group lock) multi purpose lock complte. Edges to be finished with teak wood lipping etc. including all internal surface to be polished/painted etc. complte. Veneer to be provided only on over visible surface All the surface without veneer shall be Polished/ synthetic enamel paint of approved shed Front surface area shall be measured for payment purpose.	3	SQMT
4[A]	Same as above item No 4 but Supplying and providing storage cabinet with Teak Veneer with PU Coating on Top & 35 mmx6mm thick Burma Teak beading on Edges with PU Coating. and 1.00 mm thick frosty white laminate on Front shutter. Laminate to be provided only on front,side visible surfaces	13	SQMT
5	P/F ELECTRIC CUB BOARD Providing and fixing Electric cup board using 18mm thick bision panel for verticale and shelves and aluminium framing of 50x25x1.20mm thick with 6mm thick bision panel on both side for shutter with 1.0 mm thick laminate on all exposed surface and polishing/ synthetic enamel paint on all internal surface. shutter with approved make lock handle, hinges,ball catches P&fixing S.S Perforated jali shall be provided in shutter etc.complete as directed, depth of cup board 1'-3".Shutter height up to 7'-0" and above fixed Type up to false ceiling bottom	4	SQMT

(NOT TO BE FILLED BY THE BIDDERS)

Sr. No.	Description	Quantity	Unit
5[A]	P/F PANTRY PLATFORM CUB BOARD SHUTTER Providing and fixing cupboard shutters below pantry platform using 1 1/2" x 2 1/2" T.W members for frame, 18mm Tk plywood with 1.0mm laminate for shutters. Providing 1/2" th T.W beading all around shutter. Providing S.S hinges, Handles, stoppers and magnetic catch as directed. All the surface shall be polished/ synthetic enamel paint as directed complete. Providing and fixing 0.60mm thick balancing laminate on internal shutter surface	2	SQMT
6	P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION FOR S.W COUNTER AND CASH CABIN Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 6 mm thick commercial plywood of approved brand on both side of aluminium skeleton and fixing 1.0 mm thick laminate of approved brand on both sides. Fixing 1.0 laminate in a shape as directed shall be fixed on all exposed edges. Fixing 12 mm transparent toughened glass as directed. Applying polish on exposed steam beach members with lacquer polished edges as directed complete. Laminate to be provided only on visible surface [FOR DETAILS REFER DRG. NO 5] For Low height Single window and Cash cabin partition, Average height of partition shall be measured and paid.	22	SQMT
6[A]	PROVIDING AND FIXING WICKET GATE WITH BOTH SIDE LAMINATE Same as item no 7 but P/F 30 mm thick flush shutter with both side laminate including SS hinges with countersunk SS screws, Approved make Night latch Lock, S.S Handles, Door stoppers, doorstop etc complete as directed.	3	SQMT
6[B]	P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 6 mm thick commercial plywood of approved brand on both side of aluminium skeleton and fixing 1.0 mm thick laminate of approved brand on both sides. Fixing 1.0 laminate in a shape as directed shall be fixed on all exposed edges. Fixing 12mm th free clear float glass as directed. Applying polish on exposed steam beach members with lacquer polished edges as directed complete. Laminate to be provided only on visible surface	9	SQMT
6[C]	P/F BOTH SIDE LAMINATE SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION Providing and fixing both sides laminate full height partly glazed partition using 50mm x25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 6mm th commercial plywood on both sides, 1.0mm laminate of approved brand shall be fixed on plywood, Providing 5.0/8.0 mm th float glass as directed in the partition. Providing door shutter using 30mm thick flush shutter with both side laminate and fixing 6 mm thick glass shall be provided in door shutter providing 5" Long 3 Nos stainless steel hinges/doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter Steam beach Beading shall be provided for fixing glass. All visible members if not laminated shall have lacquer polished as directed.	27	SQMT

(NOT TO BE FILLED BY THE BIDDERS)

Sr. No.	Description	Quantity	Unit
7	Providing and fixing Isolated flush door shutter (Partly Glazed and Partly Laminate) with frame as follows. Providing and fixing 4"x2" steam beach member for frame and Flush door shutter made out of 31 mm thick flush door with 6 mm thick clear float glass vision panel secured with 12 mm thick steam beach beading, 31x 12 mm thick steam beach periphery patti around shutter edges, 1 mm thick laminate on both sides, 35x12mm thick steam beach stopper patti on frame including 3 Nos 5" long SS hinges with countersunk SS screws, Approved make Ded Lock, S.S Handles, 150 mm long Door stoppers, doorstop of approved make etc. all exposed surface /edges not laminated be provided with lacquer polish complete as per drawing & instructions	8	SQMT
7[a]	Providing and fixing Isolated solid flush door shutter with Aluminium Frame and both side Bison panel for UPS Room Providing and fixing aluminium frame of 65mm x 38mm x 1.5 mm thick and door shutter made out of 50x25x1.5mm thick framing at maximum 1'-6" C/C both way with 6 mm thick Bison Panel on both side with painting. Providing 6 mm thick clear float glass vision panel secured with 12 mm thick steam beach beading, 31x 12 mm thick steam beach periphery patti around shutter edges, aluminium stopper patti on frame including 3 Nos 5" long SS hinges with countersunk SS screws, Approved make Ded Lock, S.S Handles, Door stoppers, doorstop of approved make etc. complete as per drawing & instructions	2	SQMT
8	GLASS DOORS AND PARTITIONS		
8[A]	P & F FULLY GLAZED DOOR WITH PATCH FITTINGS for Main Entrance Door For Branch and E-Lobby Providing & Fixing fully glazed main door at the main entrance and ATM. The Item includes fixing of 12 mm th. Toughened glass with the help of top patch & bottom patch fittings . The door will have patch lock, pti pivot, floor spring & 400 mm long handles both sides, (Approved Make) , fixed with the glass by making necessary cutouts & holes. The glass edges shall be polish on all sides. The entire door shall be erected in complete line & level. The door will have S.S brush finish Signage for pull & push. The patch fittings (Approved make) shall be of aluminium with s,s, matt finish coating & signage shall be of kich make. The entire door, complete in all respect should be installed in positions as req.	6	SQMT
8[B]	Same as above item but P & F FULLY GLAZED PARTATION With Patch Fitting for front side Main Entrance [FIXED PORTION] For Branch and E-Lobby	18	SQMT
8[C]	PROVIDING AND FIXING 12 MM THICK TOUGHENED GLASS DIAPHARM FOR SEPARATING TWO M/C FOR E-LOOBY P /F 12mm th Toughened glass Diapharm for Separating of between two M/C with etching and frosting Films complete as directed. Glass edges shall be round moulded and polish as per direction complete. Glass shall be fixed in wall and floor with necessary suitable patch fittings as directed. (Area based on outer diameters shall be measured and paid).	6	SQMT
9	Wall panelling with laminate finishing for wall and Piller etc Providing and laying panelling on walls & pillars having 6mm th commercial plywood and 1.0mm th laminate fixed on wall & pillars with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways or 18 mm thick plywood with laminate panelling on wall and pillar etc complete as directed. panelling as per design and instruction of Architect. .	33	SQMT

(NOT TO BE FILLED BY THE BIDDERS)

Sr. No.	Description	Quantity	Unit
9[A]	Providing and fixing 8mm thick MDF Board exterior grade with jali work with high gloss PU coating paint over central column having 6mm thick commercial plywood fixed on pillar with aluminium framing of 25mm x25mm x1.20 mm thick at maximum 2'-0" c/c bothway as per drawing and direction with all labour and material etc complete (Rate shall be including CNC cutting jali work and 1mm thick blue gloss laminate behind design jali work as directed)	13	SQMT
9[B]	Panelling for Display wall with 3M Vinyl Films with printed design and lamination finishing Providing and laying panelling on wall having 8mm th MDF Board exterior grade with 3M vinyl films with printed design and lamination fixed on wall with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways etc. complete as directed. panelling as per design and instruction of Architect. Only Finished visible surface area shall be measured for payment (MDF board with 0.60 mm thick laminate) Front surface area shall be measured for payment purpose.	4	SQMT
9[C]	Panelling for Digital wall with Blue/white high gloss PU Coating finishing Providing and laying pannelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20mm thick at maximum 2'-0" c/c bothways etc. complete as directed. pannelling as per design and instruction of Architect. . Only Finished visible surface area shall be measured for payment	5	SQMT
9[D]	P/A WALL PAPERS on Digital wall Providing and applying Wall paper approved by Architect / Bank's Engineer, wall paper basic price of Rs 100=00 Per Sq.Ft	6	SQMT
10	SOFT BOARD Providing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6mm thick commercial plywood on back side and 12mm th soft board on front. Fixing cloth of selected design of Basic rate of Rs. 150 per mt.steam beach member shall have lacquer polish as directed complete.	1	SQMT
11	CUSTOMER WRITING DESK WITH STORAGE Writing Desk Size 3'-0" x 1'-3" x 0'-6"+3'-0" ht. Verticle Sides and bottom shall be made out of 36 mm (2X18) thick Commercial plywood and back side 12mm thick ply wood with Laminate on Top and Edges on all sides including inside divisions. Top shall be made from 12mm th glass with bevelled and polished edges making diff divisions by 12mm th glass for slips or forms as per detail drawing and inststruction complete.P &F Storage below with providing self etc including all accessories etc complete (Drawing as enclosed herewith) Laminate to be provided on all visible surface	1	NO
12	Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shed. (Basic Price of Rs 135=00 Per Sq.Ft)	24	SQMT
13	Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surfaces as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification.	15	SQMT

(NOT TO BE FILLED BY THE BIDDERS)

Sr. No.	Description	Quantity	Unit
14	<p>ALUMINUM COMPOSITE PANEL FOR FRONT SIDE ELEVATION for BRANCH AND ATM ROOM IN SIDE WALL AND OUT SIDE</p> <p>Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond with 0.25 mm foil with 2" x 1" x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building This item will be carried out as per manufacturer specifications. Rate also including trap door shutter including hinges stopers etc complete as directed. Design as per Bank standered Drawing and Architects instruction etc complete.</p>	63	SQMT
15	<p>FALSE CEILING WORK</p> <p>P/F GYPSUM BOARD FALSE CEILING</p> <p>Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA (Gypsteel Ultra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. After completion of work to certificate from Saint Gobin Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification</p> <p>Note : (1) Rate includes making necessary cutouts for lighting fixtures (2) Pattas of Less than 1'-0" shall be measured in Sqft and not in Rft and paid in Sqft. (3) Only finished visible surface area shall be measured for payment.</p>	255	SMT
15[A]	<p>Extra for Providing and Fixing of 8 mm thick MDF board strip with Blue shade high gloss PU Coatings instead of Gypsum Board for Item No-1 over Transaction Area etc complete as per design and instruction Only finished surface area shall be measured for payment.</p>	5	SMT
16	<p>Providing and Fixing of Armstrong Mineral Fibre Acoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid</p> <p>Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be dducted for payment purpose</p> <p>After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications</p>	102	SMT
17	<p>Supplying and providing Dressing Table with Puffy as follows.</p> <p>Dressing Table shall have 1'-6" x 4'-0" 5mm thick mirror with 1 1/2" x 3" T.W frame and 6mm thick BWR plywood 2'-0" x 6" size having polished edges supported by brass bracket 2 Nos. as directed.</p> <p>Puffy shall be made of using TW member size 2"x2" and 18mm th.plywood for seat support. Seat shall be padded with 4" foam covered with hession cloth and upholstered with Approved shade and quantity fabric. Basic price of fabric shall be Rs.400 per Rmt. Visible wooden support shall be polished,Size of Puffy shall be 1'6"x1'6".</p>	1	NO
18	<p>Providing and applying Texture paint of Heritage/Berger brand on internal walls. Rate includes surfaces preparation, applying necessary coats of paint to obtain Uniform and even finish. Rate also includes applying paint of approved shed etc. complete.</p>	10	SMT

(NOT TO BE FILLED BY THE BIDDERS)

Sr. No.	Description	Quantity	Unit
19	Providing and fixing "EG/Godrej /Dorma/Ozone" or equivalent make door closure. etc complete	5	NO
20	Supplying and providing 3'-0" x 1'-9"x 1'-3" height Center Tepoy as follows. Providing and making open box structure type Teapoy made out of 36 mm (2X18) thick plywood with all over 1.0 mm thick laminate finish provided with bevelled & diamond polished edges 12mm thick glass top supported on SS studs with complete as directed.	1	NO
20[A]	Same as above but size 1'-9" x 1'-9" x 1'-3" height for Corner Tepoy	3	NO
21	Providing and Fixing Mirror using 5mm thick mirror with 1 1/2" x 2 1/2" T.W. frame and 6mm thick Commercial plywood on back side having polished edges etc. complete as directed.[For petrolling passage]	5	SMT