

BOQ & SPECIFICATIONS FOR RENOVATION OF TOILETS AT ADMINISTRATIVE OFFICE, GWALIOR					
S.NO	ITEM AND SPECIFICATION	QTY	UNIT	RATE	AMOUNT
A	GROUND FLOOR TOILET WORK'S				
1	WALL TILES				
	Providing & Fixing at site 1st quality 6.0-8.0mm thick Glazed ceramic DIGITAL pattern colored tiles of size 450 x 600mm to be fixed on walls of toilet with 1:3 cement mortar/ tile adhesive the cost shall include all materials, labour, materials, etc complete.	102.00	SQM		
2	FLOOR TILES				
	Providing & Fixing at site approved color and shade, group-3 Antiskid 16" x 16" x 8.0mm ceramic floor tiles to be fixed over the floor surface after removing of existing floor in 1:3 cement mortar including all labour, materials, etc complete.	25.00	SQM		
3	EUROPEAN W.C WALL HUNG WITH CONCEALED WATER TANK FOR TOILETS				
	Providing and fixing at site wall hung European WC with Concealed Water tank of Hindware, Parry / Kohlar, jacquar make, including all the necessary work to conceal the water tank, including flushing buttons, erection of Brick wall to conceal the tank all materials, labour necessary accessories etc complete.	4.00	NOS		
4	HEALTH FAUCET				
	Providing & Fixing at site Toilet Health Fauce with wall hook , 8mm diameter and 1.2 meter flexible pipe including all fittings, material , labour etc complete. Plumber, jacquar make as per the site requirement etc complete.	4.00	NOS		
5	WASH BASIN COUNTER TYPE				
	Providing & Fixing at site Under Table Counter type Wash basin of oval or approved shape size, to be fixed in Black coloured Granite Platform with push button type Long body Bib cocks off Parko, Plumber, Jacquar make including CP heavy duty fittings all accessories such as PVC connection, Angle cock all materials, labour, 'materials, etc complete Excluding cost of Black granite counter top to be paid seperatly.	8.00	NOS		
6	CPVC PIPE				
	Providing & fixing at site CPVC pipe of 2.0mm wall thickness Class to be fixed in walls including all accessories after making Necessary chases in the existing Brick Work, fixing of pipe and making chases good including all accessories labour, materials, etc complete.				
	20 mm nominal outer dia Pipes	30.00	MTR		
	25 mm nominal outer dia Pipes	50.00	MTR		
7	BIB COCK & ANGLE COCK				
	Providing & Fixing at site heavy duty Quarter turn foam flow Bib cocks, with ceramic disc angle cock & other taps of Parko, Plumber, jacquar make as per the site requirement etc complete.	14.00	NOS		
8	MIRROR				

	Providing and fixing at site 5.0mm thick plain reflective mirror mirror of given size to be fixed at site with 12.0mm BWP ply backing and to 25 x 50mm teak wood frame duly finish with melamine polish to match the tile color including all materials, labour etc complete	3.00	SQM		
9	URINAL WITH ELECTRONIC SENSOR				
	Providing & Fixing at site white Flat full back Urinal pot with electronic sensor of Standard size (580 x 380 x 350) or as per approved make to be fixed at site including waste coupling, necessary PVC waste pipe, all fittings accessories, labour etc complete. Of Hindware, parry, Kohlar, Jacuzzi or EQ make	2.00	NOS		
10	C.I WASTE PIPE				
	Providing and laying S&S centrifugally cast (spun) iron pipes (Class LA) conforming to IS - 1536 :including lead caulked joints to spun iron or C.I. pipes and specials,including testing of joints , all fitting , material , labour etc comple				
	100 mm dia pipe	20.00	RM		
11	TOWEL RING				
	Providing and fixing at site towel ring Stainless Steel heavy duty to be fixed at site with metallic Anchor fasteners etc complete.	4.00	NOS		
12	NAHANI TRAP				
	Providing and fixing at site 100mm inlet/75mm outlet nahani trap heavy duty PVC of approved make including stainless steel jali, including all materials, labour etc complete.	5.00	NOS		
13	Dismantling of existing plaster, floor , wall tiles of the toilets and toilet seats, throwing away all the waste materials, away from the existing site including transporting the same if required all labour etc complete.	126.00	SQM		
14	ALUMINUM PANEL Powder coated DOOR with Aluminium Frame FOR W.C & BATH				
	Providing and fixing Powder coated Aluminum door with Aluminium Frame, The door shutter is of aluminium door section frame with 12.0mm HDF(water proof board) as panel having laminated finish on both the sides with approved pattern and design including all fittings, accessories labour etc complete	12.00	SQM		
15	FLUSH DOOR				
	Providing and fixing at site flush doors 30mm thick BWP grade flush doors to be fixed at site with SS Finished 100mm heavy duty hinges and door closers, with 1.0mm thick approved shade of textured laminated finish on both the sides, in the given pattern, with cylindrical mortice lock SS finished/ anodised shall include all the labour, materilas, etc complete.	12.00	SQM		
16	GRANITE WORK FOR WASH BASIN & Urinal partitions				
	Providing and fixing at site Black coloured 25mm thick Granite stone with edge moulding, including fixing of wash basin over platform & Urinal partitions including all base support fixed including all materials, labour etc complete	8.00	SQM		
17	UPVC VENTILATION				

	Providing and fixing Finesta or Equivalent Make sliding/Louvers type U.P.V.C. Ventilation Including frame, and 38mm thick shutter frame with 6.0mm thick Glass panes, with provision of Exhaust fan per the given design & drawing, including cost of materials, all accessories, locking arrangement labour etc complete.	3.00	SQM		
18	POP PUNNING				
	Scraping of old paint/ distemper wherever necessary from the existing walls, and applying of 4.0 to 8.0 mm thick lime punning over it to give a smooth leveled finish, the final coat of punning to have one coat of oil based Cement primer the cost shall include all labor , materials, etc complete.	30.00	SQM		
19	ACRYLIC EMULSION PAINT				
	Applying one coat of cement premier and applying two or more coats of Acrylic emulsion Royale/ Velvet touche to be applied over the punning area with roller to give desired smooth finish, including one coat of Birla Putty properly sand papered to give a neat smooth & silky finish, the cost shall include all materials, labour etc complete.	30.00	SQM		
20	SYNTHETIC ENAMEL PAINT				
	Two or more coats of approved shade synthetic enamel including one base coat of steel/ wooden primer over the existing wooden/ steel surfaces, with brush after cleaning & scrapping by wire brushing. Including all materials, labour etc complete.	10.00	SQM		
21	OIL BOND DISTEMPER				
	Two or more coats of Acrylic oil bond distemper with brush over the existing wall surfaces, after scrapping the existing finish, applying one coat of cement premier and one coat of putty to repair the wall as per the site condition including all materials, labour etc complete.	25.00	SQM		
22	Dismantling & excavation of existing duct filling of the toilets and throwing away all the waste materials, away from the existing site including transporting the same if required all labour etc complete.	12.00	CUM		
23	WATER PROOFING FOR TOILET DUCT				
	Providing and laying water proofing treatment to vertical and horizontal surfaces of depressed portions of W.C.,and toilet the like consisting of :				
	(i) Ist course of applying cement slurry @ 4.4 kg/sqm mixed with water proofing compound conforming to IS 2645 in recommended proportions including rounding off junction of vertical and horizontal surface. (ii) IInd course of 20 mm cement plaster 1:3 (1 cement : 3 coarse sand) mixed with water proofing compound in recommended proportion including rounding off junction of vertical and horizontal surface. (iii) IIIrd course of applying blown or residual bitumen applied hot at 1.7 kg. per sqm of area. (iv) IVth course of 400 micron thick PVC sheet. (Overlaps at joints of PVC sheet should be 100 mm wide and pasted to each other with bitumen @ 1.7 kg/sqm).	25.00	SQM		
24	FILLING WITH BRICK BATS				

	Filling & Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs and finishing top with water proofing compound including all material, labour etc complete.	12.00	CUM		
	TOTAL AMOUNT FOR GROUND FLOOR (A)				
B	FIRST FLOOR TOILET WORK'S				
1	<u>WALL TILES</u>				
	Providing & Fixing at site 1st quality 6.0-8.0mm thick Glazed ceramic DIGITAL pattern colored tiles of size 450 x 600mm to be fixed on walls of toilet with 1:3 cement mortar/ tile adhesive the cost shall include all materials, labour, materials, etc complete.	185.00	SQM		
2	<u>FLOOR TILES</u>				
	Providing & Fixing at site colored 16" x 16" x 8.0mm anti skid ceramic floor tiles to be fixed over the floor surface after removing of existing floor in 1:3 cement mortar including all labour, materials, etc complete.	44.00	SQM		
3	<u>EUROPEAN W.C WALL HUNG WITH CONCEALED WATER TANK FOR TOILETS</u>				
	Providing and fixing at site wall hung European WC with Concealed Water tank of Hindware, Parry / Kohlar, jacquar make, including all the necessary work to conceal the water tank, including flushing buttons, erection of Brick wall to conceal the tank all materials, labour necessary accessories etc complete.	6.00	NOS		
4	<u>HEALTH FAUCET</u>				
	Providing & Fixing at site Toilet Health Fauce with wall hook , 8mm diameter and 1.2 meter flexible pipe including all fittings, material , labour etc complete. Plumber, jacquar make as per the site requirement etc complete.	6.00	NOS		
5	<u>INDIAN W.C</u>				
	Providing & fixing at site Light colored 1st quality Indian orrissa pan of Standard size (580 x 440) Indian WC including Light colored and matching pvc low level water tank (10 Lt,) of Hindware/ Parryware/ RAK make 1st quality, including fixing at site with all necessary accessories, all materials, labour etc complete.	2.00	NOS		
6	<u>WASH BASIN under counter type</u>				

	Providing & Fixing at site Under Table Counter type Wash basin of oval or approved shape size, to be fixed in Black coloured Granite Platform with push button type Long body Bib cocks off Parko, Plumber, Jacuzzi make including CP heavy duty fittings all accessories such as PVC connection, Angle cock all materials, labour, 'materials, etc complete Excluding cost of Black granite counter top to be paid separately.	9.00	NOS		
7	CPVC PIPE				
	Providing & fixing at site CPVC pipe of 2.0mm wall thickness Class to be fixed in walls including all accessories after making Necessary chases in the existing Brick Work, fixing of pipe and making chases good including all accessories labour, materials, etc complete.				
	20 mm nominal outer dia Pipes	30.00	MTR		
	25 mm nominal outer dia Pipes	40.00	MTR		
8	BIB COCK & ANGLE COCK				
	Providing & Fixing at site heavy duty Quarter turn foam flow Bib cocks, with ceramic disc angle cock & other taps of Parko, Plumber, jacquar make as per the site requirement etc complete.	25.00	NOS		
9	MIRROR				
	Providing and fixing at site 5.0mm thick plain reflective mirror mirror of given size to be fixed at site with 12.0mm BWP ply backing and to 25 x 50mm teak wood frame duly finish with melamine polish to match the tile color including all materials, labour etc complete	3.00	SQM		
10	URINAL with electronic sensor				
	Providing & Fixing at site white Flat full back Urinal pot with electronic sensor of Standard size (580 x 380 x 350) or as per approved make to be fixed at site including waste coupling, necessary PVC waste pipe, all fittings accessories, labour etc complete. Of Hindware, parry, Kohlar, Jacuzzi or EQ make	6.00	NOS		
11	C.I WASTE PIPE				
	Providing and laying S&S centrifugally cast (spun) iron pipes (Class LA) conforming to IS - 1536 :including lead caulked joints to spun iron or C.I. pipes and specials,including testing of joints , all fitting , material , labour etc comple				
	100 mm dia pipe	50.00	RM		
12	TOWEL RING				
	Providing and fixing at site towel ring Stainless Steel heavy duty to be fixed at site with metallic Anchor fasteners etc complete.	7.00	NOS		
13	NAHANI TRAP				
	Providing and fixing at site 100mm inlet/75mm outlet nahani trap heavy duty PVC of approved make including stainless steel jali, including all materials, labour etc complete.	10.00	NOS		
14	Dismantling of existing plaster, floor , wall tiles of the toilets and toilet seats, throwing away all the waste materials, away from the existing site including transporting the same if required all labour etc complete.	225.00	SQM		

15	ALUMINUM PANEL Powder coated DOOR with Aluminium Frame FOR W.C & BATH				
	Providing and fixing Powder coated Aluminum door with Aluminium Frame, The door shutter is of aluminium door section frame with 12.0mm HDF(water proof board) as panel having laminated finish on both the sides with approved pattern and design including all fittings, accessories labour etc complete	14.00	SQM		
16	FLUSH DOOR				
	Providing and fixing at site flush doors 30mm thick BWP grade flush doors to be fixed at site with SS Finished 100mm heavy duty hinges and door closers, with 1.0mm thick approved shade of textured laminated finish on both the sides, in the given pattern, with cylindrical mortice lock SS finished/ anodised shall include all the labour, materials, etc complete.	10.00	SQM		
17	GRANITE WORK FOR WASH BASIN & Urinal partitions				
	Providing and fixing at site Black coloured 25mm thick Granite stone with edge moulding, including fixing of wash basin over platform & Urinal partitions including all base support fixed including all materials, labour etc complete	15.00	SQM		
18	UPVC VENTILATION				
	Providing and fixing Finesta or Equivalent Make sliding/Luvers type U.P.V.C. Ventilation Including frame, and 38mm thick shutter frame with 6.0mm thick Glass panes, with provision of Exhaust fan per the given design & drawing, including cost of materials, all accessories, locking arrangement labour etc complete.	3.00	SQM		
19	POP PUNNING				
	Scraping of old paint/ distemper wherever necessary from the existing walls, and applying of 4.0 to 8.0 mm thick lime punning over it to give a smooth leveled finish, the final coat of punning to have one coat of oil based Cement primer the cost shall include all labor , materials, etc complete.	55.00	SQM		
20	ACRYLIC EMULSION PAINT				
	Applying one coat of cement premier and applying two or more coats of Acrylic emulsion Royale/ Velvet touche to be applied over the punning area with roller to give desired smooth finish, including one coat of Birla Putty properly sand papered to give a neat smooth & silky finish, the cost shall include all materials, labour etc complete.	55.00	SQM		
21	SYNTHETIC ENAMEL PAINT				
	Two or more coats of approved shade synthetic enamel including one base coat of steel/ wooden primer over the existing wooden/ steel surfaces, with brush after cleaning & scrapping by wire brushing. Including all materials, labour etc complete.	17.00	SQM		
22	OIL BOND DISTEMPER				
	Two or more coats of Acrylic oil bond distemper with brush over the existing wall surfaces, after scrapping the existing finish, applying one coat of cement premier and one coat of putty to repair the wall as per the site condition including all materials, labour etc complete.	50.00	SQM		

23	Dismantling & excavation of existing duct filling of the toilets and throwing away all the waste materials, away from the existing site including transporting the same if required all labour etc complete.	20.00	CUM		
24	WATER PROOFING FOR TOILET DUCT				
	Providing and laying water proofing treatment to vertical and horizontal surfaces of depressed portions of W.C.,and toilet the like consisting of :				
	(i) Ist course of applying cement slurry @ 4.4 kg/sqm mixed with water proofing compound conforming to IS 2645 in recommended proportions including rounding off junction of vertical and horizontal surface. (ii) IInd course of 20 mm cement plaster 1:3 (1 cement : 3 coarse sand) mixed with water proofing compound in recommended proportion including rounding off junction of vertical and horizontal surface. (iii) IIIrd course of applying blown or residual bitumen applied hot at 1.7 kg. per sqm of area. (iv) IVth course of 400 micron thick PVC sheet. (Overlaps at joints of PVC sheet should be 100 mm wide and pasted to each other with bitumen @ 1.7 kg/sqm).	45.00	SQM		
25	FILLING WITH BRICK BATS				
	Filling & Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs and finishing top with water proofing compound including all material, labour etc complete.	20.00	CUM		
	TOTAL AMOUNT FOR FIRST FLOOR (B)				
C	<u>SECOND FLOOR TOILET WORK'S</u>				
1	<u>WALL TILES</u>				
	Providing & Fixing at site 1 st quality 6.0-8.0mm thick Glazed ceramic DIGITAL pattern colored tiles of size 450 x 600mm to be fixed on walls of toilet with 1:3 cement mortar/ tile adhesive the cost shall include all materials, labour, materials, etc complete.	165.00	SQM		
2	<u>FLOOR TILES</u>				
	Providing & Fixing at site colored 16" x 16" x 8.0mm anti skid ceramic floor tiles to be fixed over the floor surface after removing of existing floor in 1:3 cement mortar including all labour, materials, etc complete.	40.00	SQM		
3	<u>EUROPEAN W.C WALL HUNG WITH CONCEALED WATER TANK FOR TOILETS</u>				
	Providing and fixing at site wall hung European WC with Concealed Water tank of Hindware, Parry / Kohlar, jacquar make, including all the necessary work to conceal the water tank, including flushing buttons, erection of Brick wall to conceal the tank all materials, labour necessary accessories etc complete.	6.00	NOS		
4	<u>HEALTH FAUCET</u>				

	Providing & Fixing at site Toilet Health Fauce with wall hook , 8mm diameter and 1.2 meter flexible pipe including all fittings, material , labour etc complete. Plumber, jacquar make as per the site requirement etc complete.	6.00	NOS		
5	INDIAN W.C				
	Providing & fixing at site Light colored 1st quality Indian orrissa pan of Standard size (580 x 440) Indian WC including Light colored and matching pvc low level water tank (10 Lt ,) of Hindware/ Parryware/ RAK make 1st quality, including fixing at site with all necessary accessories, all materials, labour etc complete.	2.00	NOS		
6	WASH BASIN under counter type				
	Providing & Fixing at site Under Table Counter type Wash basin of oval or approved shape size, to be fixed in Black coloured Granite Platform with push button type Long body Bib cocks off Parko, Plumber, Jacquar make including CP heavy duty fittings all accessories such as PVC connection, Angle cock all materials, labour, 'materials, etc complete Excluding cost of Black granite counter top to be paid seperatly.	7.00	NOS		
7	CPVC PIPE				
	Providing & fixing at site CPVC pipe of 2.0mm wall thickness Class to be fixed in walls including all accessories after making Necessary chases in the existing Brick Work, fixing of pipe and making chases good including all accessories labour, materials, etc complete.				
	20 mm nominal outer dia Pipes	30.00	MTR		
	25 mm nominal outer dia Pipes	40.00	MTR		
8	BIB COCK & ANGLE COCK				
	Providing & Fixing at site heavy duty Quarter turn foam flow Bib cocks, with ceramic disc angle cock & other taps of Parko, Plumber, jacquar make as per the site requirement etc complete.	25.00	NOS		
9	MIRROR				
	Providing and fixing at site 5.0mm mirror to be fixed at site with 12.0mm BWP ply backing and to 25 x 50mm teak wood frame duly painted to match the tile color including all materials, labour etc complete.	3.00	SQM		
10	URINAL with electronic sensor				
	Providing & Fixing at site white Colored Flat full back Urinal pot with electronic sensor of Standard size (580 x 380 x 350) including fixing of quarter turn heavy duty stopcock of Parko or equivalent make over each urinal for flushing purposes to be fixed at site including waste coupling, necessary PVC waste pipe, all fittings accessories, labour etc complete. Of hindusthan, parry, Kohlar or EQ make	6.00	NOS		
11	C.I WASTE PIPE				
	Providing and laying S&S centrifugally cast (spun) iron pipes (Class LA) conforming to IS - 1536 :including lead caulked joints to spun iron or C.I. pipes and specials,including testing of joints , all fitting , material , labour etc comple				
	100 mm dia pipe	60.00	RM		
12	TOWEL RING				

	Providing and fixing at site towel ring Stainless Steel heavy duty to be fixed at site with metallic Anchor fasteners etc complete.	7.00	NOS		
13	NAHANI TRAP				
	Providing and fixing at site 100mm inlet/75mm outlet nahani trap heavy duty PVC of approved make including stainless steel jali, including all materials, labour etc complete.	10.00	NOS		
14	Dismantling of existing plaster, floor , wall tiles of the toilets and toilet seats, throwing away all the waste materials, away from the existing site including transporting the same if required all labour etc complete.	200.00	SQM		
15	ALUMINUM PANEL Powder coated DOOR with Aluminium Frame FOR W.C & BATH				
	Providing and fixing Powder coated Aluminum door with Aluminium Frame, The door shutter is again of aluminium door section frame with 12.0mm HDF(water proof board) as panel having laminated finish on both the sides with approved pattern and design including all fittings, accessories labour etc complete	14.00	SQM		
16	FLUSH DOOR				
	Providing and fixing at site flush doors 30mm thick BWP grade flush doors to be fixed at site with SS Finished 100mm heavy duty hinges and door closers, with 1.0mm thick approved shade of textured laminated finish on both the sides, in the given pattern, with cylindrical mortice lock SS finished/ anodised shall include all the labour, materilas, etc complete.	8.00	SQM		
17	GRANITE WORK FOR WASH BASIN & Urinal partitions				
	Providing and fixing at site Black coloured 25mm thick Granite stone with edge moulding, including fixing of wash basin over platform & Urinal partitions including all base support fixed including all materials, labour etc complete	15.00	SQM		
18	UPVC VENTILATION				
	Providing and fixing Finesta or Equivalent Make sliding/Luvers type U.P.V.C. Ventilation Including frame, and 38mm thick shutter frame with 6.0mm thick Glass panes, with provision of Exhust fan per the given design & drawing, including cost of materials, all accessories, locking arrangement labour etc complete.	3.00	SQM		
19	POP PUNNING				
	Scrapping of old paint/ distemper wherever necessary from the existing walls, and applying of 4.0 to 8.0 mm thick lime punning over it to give a smooth leveled finish, the final coat of punning to have one coat of oil based Cement primer the cost shall include all labor , materials, etc complete.	50.00	SQM		
20	ACRYLIC EMULSION PAINT				
	Applying one coat of cement premier and applying two or more coats of Acrylic emulsion Royale/ Velvet touche to be applied over the punning area with roller to give desired smooth finish, including one coat of Birla Putty properly sand papered to give a neat smooth & silky finish, the cost shall include all materials, labour etc complete.	50.00	SQM		

21	SYNTHETIC ENAMEL PAINT				
	Two or more coats of approved shade synthetic enamel including one base coat of steel/ wooden primer over the existing wooden/ steel surfaces, with brush after cleaning & scrapping by wire brushing. Including all materials, labour etc complete.	20.00	SQM		
22	OIL BOND DISTEMPER				
	Two or more coats of Acrylic oil bond distemper with brush over the existing wall surfaces, after scrapping the existing finish, applying one coat of cement premier and one coat of putty to repair the wall as per the site condition including all materials, labour etc complete.	40.00	SQM		
23	Dismantling & excavation of existing duct filling of the toilets and throwing away all the waste materials, away from the existing site including transporting the same if required all labour etc complete.	18.00	CUM		
24	WATER PROOFING FOR TOILET DUCT				
	Providing and laying water proofing treatment to vertical and horizontal surfaces of depressed portions of W.C.,and toilet the like consisting of :				
	(i) Ist course of applying cement slurry @ 4.4 kg/sqm mixed with water proofing compound conforming to IS 2645 in recommended proportions including rounding off junction of vertical and horizontal surface. (ii) IInd course of 20 mm cement plaster 1:3 (1 cement : 3 coarse sand) mixed with water proofing compound in recommended proportion including rounding off junction of vertical and horizontal surface. (iii) IIIrd course of applying blown or residual bitumen applied hot at 1.7 kg. per sqm of area. (iv) IVth course of 400 micron thick PVC sheet. (Overlaps at joints of PVC sheet should be 100 mm wide and pasted to each other with bitumen @ 1.7 kg/sqm).	40.00	SQM		
25	FILLING WITH BRICK BATS				
	Filling & Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs and finishing top with water proofing compound including all material, labour etc complete.	18.00	CUM		
	TOTAL AMOUNT FOR SECOND FLOOR (C)				
	GRAND TOTAL (A+B+C) EXCL. GST*				

* GSAT SHALL BE PAID EXTRA AS APPLICABLE.

SEAL/SIGN OF THE FIRM