

**ESTIMATE FOR Air-Conditioning WORK FOR STATE BANK OF INDIA
SHAHJAHANPUR MAIN BRANCH(TOWN HALL)**

S.N.	DESCRIPTION (rate must be quoted excluding GST)	UNIT	QTY	RATE	AMOUNT
1	Supply, installation, testing and commissioning (SITC) of air cooling type, 2.0 Tr, Cassette type split air conditioner in recessed manner in grid type false ceiling with full function wireless remote and auto restart feature, complete in all respects with indoor/outdoor unit, gas charge etc. (100% copper coil condenser) Daikin/Hitachi/Carrier/ Blue Star/Voltas/Toshiba/Godrej.	No	6.00		
4	Dismantling of the existing split A.C from the branch and re-fixing the same after paneling at advised location	No	12.00		
5	Providing & Installation of 5 KVA voltage Stabilizers with range of 130 - 280V of standard make as per the approval of the Architect of (Inmag, Serval, Stambh)	No	8.00		
6	PVC Drain Water Piping	RM	150.00		
7	Copper Piping Refrigerant along with insulator Piping for Hi Wall 1.5 ton and 1 ton Ac 1/2 and 1/4 Soft Copper Refrigerant piping with complete fitting, elbows bends supporting arrangements Nissan, Merchant, MET tube, Totaline tube, pressure tested tube .	Rm	150.00		
8	S.I.T.C. of 4 core Copper conductor flexible cable between Indoor & Outdoor Unit through holes made as above	Rm	150.00		
9	S.I.T.C. of L shape / suitable shape M.S. Frame and stand for mounting Outdoor Units on wall / On floor with all fixing hardwares. Within above Catwalk for cassette & split A.c.'s.	No	6.00		
	TOTAL (excluding GST)				

