

Page 1 of 2  
STATE BANK OF INDIA  
RBO 1 ERNAKULAM

Name of work		Providing corean top and laminate change of sbi Jews Street, Lissie Hospital and Metro Station Branches			
Name and Address of Contractor					
<b>SCHEDULE OF ITEMS FOR PROVIDING CORIAN TOP/ LAMINATE CHAGE FO MAKING UNIFORM LAYOUT FOR JEWS STREET, LISSIE HOSPITAL AND METROSTATION BRANCHES</b>					
SI No.	Description of work	Quantity	Unit	Rate	Amount
1	Providing and fixing 6 mm marine flexy plywood of approved make with curved bend in front modesty to the existing surface of counters using necessary frames.	50	Sq.M		
2	CORIAN TOP:- Providing, fitting and fixing flexible solid surface material (Corian solid surface- 6 mm thick)of approved shade and make as per drawing and design. Solid surface material is to be fixed with acrylic epoxy adhesive compound including surface and edge finishing and moulds. The fixing is to be done on exposed surface of counters, tables or any other surface as directed. The work is to be completed with all materials, accessories, labour, tools and tackles and in strict conformity with manufacturer's specification and recommendations. The job shall also include provisions for electrical, computer & telephone wiring conduits, switch boxes etc. All materials should be approved by the Bank. Executed plan and elevation area of the surface work shall be measured for finished work.	50	Sq.M		
3	Providing and fixing 6 mm ply wood finished with 1 mm laminate of approved make and shade to the existing table top finishing with necessary beedings etc complete.	25	Sq.M		
4	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing partition/ panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings etc. complete	450	Sq.M		
5	Remove the existing laminate and fix with new 1 mm laminate of approved make and shade	15.00	Sq.M		

For Contractor

6	Providing and fixing side portion glazing with "Blue Laminated / Lacquered transperated glass of 12mm thick of approved brand and shall be fixed with 'Doma' (or) equivalent brand 'SS' 'D' brackets. The curved 12mm thick lacquered transperant toughened glass shall be fixed at front size in between counters as per drawing and shall be fixed suitably with 'SS' brackets.	20.00	Sq.M		
7	Providing and fixing front Modesty with 8 mm thick Aqua blue shade of Saint Gobain glass or equivalent fixed 3M stickering suitable at front vertical finished with 1 mm laminate.	45.00	Sq.M		
8	Painting the false ceiling with 1 coats of plastic emulsion paint of approved color	450.00	Sq.M		
9	Painting banking hall using approved quality ' Asian paint or equivalent two coats without putty finish	650.00	Sq.M		
10	Providing PVC telescopic key boad tray with channel	10.00	Nos.		
11	Removing the existing drawer channel and fixing new telescopic channel of approved make	18.00	set		
12	Providing and fixing Godrej auto lock	18.00	Nos.		
	TOTAL				
	GST				
	GRAND TOTAL				