

**BOQ FOR INTERIOR FURNISHING WORK**

**FANCY BRANCH TRADERS BRANCH(RENOVATION)**

Sl.No	Description of items	Unit	Qty	Rate(Rs.)	Amount(Rs.)
1	<p>Supplying and installing <b>Tables</b> of Overall size - 5'6"x5'6" including cost of side credenza (3'x1'6'') with top made up of 19 mm thick ply finished with 6.0 mm thick <b>FROSTY WHITE QUARTZ CORAIAN</b> only on top and other surface finished with 1mm thick laminate as approved by the Bank and wooden beading / moulding all round melamine polished. The cost to include two drawers of 100 mm deep &amp; a file shutter of 450mm, a keyboard tray 250 mm wide with CPU stand, foot rest. The works to include all hardware like castors, brass hinges, ball catchers, fully extendable drawer slides, locks, handles etc. of approved make. Locks to be of single control type. All exposed edges to have wooden lipping stained to match the desk and melamine finished. Rate to include cost of Studds. Design and detail of the counters shall be as per Bank's new uniform colour, layout &amp; elevation policy 2016 available with Bank's engineer. Counter &amp; Credenza top to be provided with 8mm thick glass duly finished on edges and necessary cut to accommodate wires, edges to be m/c polished, with ms powder coated wire manager, complete as directed by EIC and placement as per layout given Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalent</p>	nos	7		
2	<p>Fabricating and fixing <b>full height semi glazed partition</b>, made of 6 mm ply of approved brand in both side and to be finished with 1.5 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm ( thickness not less than 1.5 mm) alluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. Middle portion at 900 mm to 2100 mm height shall have 5 mm thick plain float glass (Make: Saintgobin/Modigurd) fixed with 10 mm thick teak wood moulding duly polished. All exposed edge shall be covered with teakwood lipping with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalent</p>	sqm	90		

3	<p>Fabricating and fixing <b>full height solid partition</b>, made of 6 mm ply of approved brand in both side and to be finished with 1 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm ( thickness not less than 1.5 mm) alluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. Middle portion at 900 mm to 2100 mm height shall have 5 mm thick plain float glass (Make: Saintgobin/Modigurd) fixed with 10 mm thick teak wood moulding duly polished. All exposed edge shall be covered with teakwood lipping with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalent</p>	sqm	15		
4	<p>Providing and fixing <b>full hieght storage units</b> 1'-6" wide &amp; hieght as per site condition(avg hieght 8'). The storage units shall have shutters made in 19mm thick plwood and finished in <b>1 mm thick mat finished laminate</b> of approved shade including top. The storage units shall have intermediate shelves made in 19mm thick plywood with matching wood lipping. The storage shall have wood edge moulding as per the diretion of EIC. This also includes providing necessary hardware like handles, hinges, locks, tower bolts etc of approved make. All exposed wooden surfaces shall be stained to shade as directed by the EIC and polished melamine</p>	m	25		
5	<p>Providing and fixing <b>storage units</b> 1'-6" wide &amp; 2'6" high. The storage units shall have shutters made in 19mm thick plwood and finished in <b>1.5 mm thick mat finished laminate</b> of approved shade including top. The storage units shall have intermediate shelves made in 19mm thick plywood with matching wood lipping. The storage shall have wood edge moulding as per the diretion of EIC. This also includes providing necessary hardware like handles, hinges, locks, tower bolts etc of approved make. All exposed wooden surfaces shall be stained to shade as directed by the EIC and polished melamine</p>	m	15		
6	<p>Fabricating and fixing <b>wall paneling/column paneling</b>, consisting of 25 mm x 35 mm (thickness not less than 1.5 mm) alluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical.) Panelling framework to be secured to wall surface / column surface and to be finished with <b>1.5 mm thick mat finished laminate</b> of approved colour, brand and shade over 12 mm thick ply. Design and detail shall be as per direction of EIC and Bank's new uniform colour, layout &amp; elevation policy. Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalen</p>	sqm	93		

7	<p>Fabricating and fixing <b>column paneling</b> after dismantling existing ACP/laminate and fixing 1mm thick laminate of blue shade as per uniform colour scheme. The rate also includes fixing of MDF jali of size 12mm of white shade of length (4' X 2') for each face of the column with proper support. Design and detail shall be as per direction of EIC.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green or equivalent.</p> <p>Laminate Make: Greenlam/Centurylam or equivalent</p>	sqm	8		
8	<p>Providing &amp; fixing in position Aluminium Composite Panel (ACP) <b>Shutter Boxing</b> with framing of Aluminium Tube section of min 1.5"x1" and 20 gauge 2'-0" C/C both ways. ACP to be in 2' width panels or distributed equally. The Panels to be fixed to the frame with 3M or equivalent adhesive and mirror screws. Joints to be finished with Silicon based sealant. ACP thickness of 3 mm minimum. Aluminium foil thickness to be min 0.20 mm. Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used. Shades to be as per Bank's approval. ACP Trap door will be 12 mm marine ply finished with ACP.</p>	sqm	8		
9	<p>Providing &amp; fixing in position Aluminium Composite Panel (ACP) with framing of Aluminium Tube section of min 1.5"x1" and 20 gauge 2'-0" C/C both ways. ACP to be in 2' width panels or distributed equally. The Panels to be fixed to the frame with 3M or equivalent adhesive and mirror screws. Joints to be finished with Silicon based sealant. ACP thickness of 3 mm minimum. Aluminium foil thickness to be min 0.20 mm. Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used. Shades to be as per Bank's approval. ACP Trap door will be 12 mm marine ply finished with ACP.</p>	sqm	8		
10	<p>Providing and fixing suspended <b>false ceiling</b> with 600x600 mm size Fine Fisher tiles/Gypboard/Minwool/Armstrong and suspenders, frame work as per manufacturer's specifications. With Tagular edges Prima dune plus. The item to include cost of making necessary cut-outs for lights/air-conditioning grills as per design directed</p>	sqm	50		
11	<p>Providing and fixing suspended 12mm thick <b>Gypsum board false ceiling</b> with GI framework of standard gauge and as per the specifications of India Gypsum Co. The rate to include painting with lustre paint and making necessary design, pattern &amp; cut outs for light fittings etc. complete as per direction of EIC</p>	sqm	70		
12	<p>Providing and fixing <b>Vertical Blinds</b> of approved shade, design and texture Vista Levelor/Mac/Eqvt</p>	sqm	15		

13	<p>Providing and <b>fixing glazed doors</b> at Main entrance of average size of 2'6"X7'-0" made of top, bottom, middle and side wooden framework of teak wood of size 5"x11/2" and finished with 1.0 mm thick laminate &amp; 8 mm thick float glass with frost film to be provided between the framework. Glass to have acid etched design pattern with logo as directed. Doors to be mounted on heavy duty floor spring. 1"dia and 15" long brush S.S. finish handle of approved make to be provided. All complete including locks and necessary hardwares such as hinge, stopper, tower bolt etc. Door should include 1st class local wood door frames of size 3"x2.5'" and cover all exposed edge with bidding as directed by EIC. (doors of other sizes will be paid on pro rata basis.)</p>	each	1		
14	<p>Providing, fitting and fixing anodised aluminium sliding windows of standard sections of approved brand without horizontal glazing bars, joints mitred and welded (manufactured to relevant IS specifications) and providing and fixing handles, angle cleat, rubber gasket, roller, bolting device, locking arrangements, screws etc as required complete as specified and directed for all levels.</p>				
<b>2 Track sliding window</b>					
(i) 6mm clear glass		Sqm	9		
<b>Total Cost</b>					

**Note : Design and Detail of the counters shall be as per Bank's engineer at LHO and A.O**  
**Rates are exclusive of GST**



