## Page 1 of 1

## STATE BANK OF INDIA RBO 2 ERNAKULAM

RBO 2 ERNAKULAM					
	Name of work	Providing corean top and laminate change of SBI			
		Ernakulam South, Pravasi Seva and Valanjambalam			
				<u>branches</u>	
Name and Address of Contractor					
L		<u></u>			
SCUE	DILLE OF ITEMS FOR DROVIDING CORRANTOR/LANGUAGES CO.	CE EOD MANUS	IC LINUTO	DM I AVOUT	OB EDNAVIU ASA
SCHEDULE OF ITEMS FOR PROVIDING CORIAN TOP/ LAMINATE CHAGE FOR MAKING UNIFORM LAYOUT FOR ERNAKULAM SOUTH, PRAVASI SEVA AND VALANJAMBALAM BRANCHES					
John J. H. W. S. L. C. L					
SI No.	Description of work	Quantity	Unit	Rate	Amount
1	Providing and fixing 6 mm marine flexy plywood of approved	44	Sq.M		
	make with curved bend in front modesty to the existing				
	surface of counters using necessary frames.				
2	CORIAN TOP:- Providing, fitting and fixing flexible solid surface	44	Sq.M		İ
	material (Corian solid surface- 6 mm thick)of approved shade				
	and make as per drawing and design. Solid surface material is				
	to be fixed with acrylic epoxy adhesive compound including				
	surface and edge finishing and moulds. The fixing is to be				
	done on exposed surface of counters, tables or any other surface as directed. The work is to be completed with all				
	materials, accessories, labour, tools and tackles and in strict				
	conformity with manufacturer's specification and				
	recommendations. The job shall also include provisions for				
	electrical, computer & telephone wiring conduits, switch boxes				
	etc. All materials should be approved by the Bank. Executed plan and elevation area of the surface work shall be measured				
	for finished work.				
3	Providing and fixing 6 mm ply wood finished with 1 mm	20	Sq.M		1
	laminate of approved make and shade to the existing table top				
	finishing with necessary beedings etc complete.				
4	Providing and fixing 6 mm plywood with 1 mm laminate of	400	Sq.M		
	approved make and shade to the existing partition/ panelling/				
	counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and				
	refixing existing glass /beedings etc. complete				
	5 55, 5- <del></del>				
5	Remove the existing laminate and fix with new 1 mm	15.00	Sq.M		1
	laminate of approved make and shade	15.00	54.1 <b>*</b> 1		
6	Providing and fixing side portion glazing with "Blue Laminated	18.00	Sq.M		<u> </u>
U	/ Lacquered transperated glass of 12mm thick of approved	10.00	3q.IVI		
	brand and shall be fixed with 'Doma' (or) equivalent brand 'SS '				
	'D' brackets. The curved 12mm thick lacquered transperant				
	toughened glass shall be fixed at front size in between counters				
	as per drawing and shall be fixed suitably with 'SS' brackets.				
<u></u>					<u> </u>
7	Providing and fixing front Modesty with 8 mm thick Aqua	40.00	Sq.M		
	blue shade of Saint Gobain glass or equivalent fixed 3M stickering suitable at front vertical finished with 1 mm				
	laminate.				
8	Painting the false ceiling with 1 coats of plastic emulsion paint	425.00	Sq.M		1
	of approved color	.23.00			
9	Painting banking hall using approved quality ' Asian paint or	650.00	Sq.M		
	equivalent two coats without putty finish				
10	Providing PVC telescopic key boad tray with channel	8.00	Nos.		
11	Removing the existing drawer channel and fixing new	17.00	set		
	telescopic channel of approved make				
12	Providing and fixing Godrej auto lock	18.00	Nos.		
	TOTAL				
	GST				
-					<del> </del>
<u> </u>	GRAND TOTAL				