



REFURBISHMENT OF PANDUPOORT BRANCH

**BOQ for Supply, Installation and Annual Maintenance Contract for 5 years of Air-conditioners**

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Exclusive of GST)	Amount (Rs.) (Exclusive of GST)
1	Supply of 1.5 TR Capacity Hi Wall mounting 5-star rated Inverter Split AC with cordless remote and Copper Condensor Coil. <b>AC Make, Voltas/Bluestar /Carrier/Daikin /LG/Godrej</b>	No.	3		
2	Supply of 2.0 TR Cassette type split air conditioners with Copper Condensor Coil and refrigerant (R32 or R 410A) <b>Indoor unit</b> ceiling hung comprising cooling coil, evaporator fan with motor, filters, insulated drain pan, drain pump, expansion valve, refrigerant filter drier with cordless remote control unit, etc. <b>Outdoor unit</b> comprising single phase hermetically sealed scroll / rotary compressors, condenser coil with fan & motor, starters / controls / cutouts / relays etc., mounted inside a powder coated sheet metal cabinet of 2mm thick, duly treated for corrosion protection complete, mounted on ribbed rubber pads. <b>AC Make, Voltas/Blue Star/Carrier/Daikin /LG</b>	No.	6		
3	Installation charges of the <b>1.0/1.5 TR</b> Hi-Wall Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	3		
4	Installation charges of the <b>2.0 TR</b> Cassette Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	6		
5	<b>For 2.0 TR Copper Cassette type split air conditioners:</b> Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessities and making good all the damages.	RM	80		
6	<b>For 1.0 TR/1.5 TR Hi-Wall type split air conditioners:</b> Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessities and making good all the damages.	RM	15		
7	Supply and Installation of 4 KVA Stabilizer for 1.0 TR/1.5 TR Split Acs	Nos.	3		
8	Supply and Installation of 5 KVA Stabilizer for 2.0 TR Cassette type Acs	Nos.	6		
9	Comprehensive Annual Maintenance Contract of above mentioned <b>3 No.</b> of 1.5 TR Hi-Wall type split air conditioners after expiry of defect liability period of 1 year from the date of installation.	year	5		
10	Comprehensive Annual Maintenance Contract of above mentioned <b>6 Nos.</b> of 2.0 TR Copper Cassette type split air conditioners after expiry of defect liability period of 1 year from the date of installation.	year	5		
	<b>Total(In Rupees)</b>				