

**INTERIOR AND FURNISHING WORK OF  
JAWAHAR CHOWK BRANCH**

S.N	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
A	INTERIOR WORK				
1	"FALSE CELING : Suspended Ceiling System Slotted Grid/False Ceiling"	Sqm	70		
	Providing and fixing at all heights. Suspended false ceiling in sprit level as per design of, PVC coated Gypsum board/ mineral fibre board or equivalent A coustical Consisting of 600x600x7.5mm thick ceiling tiles of type on slotted stitched. True lock 24 TL exposed grid systems with 24 mm wide T-section flanges color white, the frame work will comprised of hot dipped galvanized steel sections consisting of main runner TEE 3600 mm long of size 24x43 mm (with single stitching) spaced at 1200 mm centers secretly fixed to the structural suffix by approved hangers at 1200 mm maximum centre. Hanger striper rod connector Clip ACE 7898 or AQ 35& ATW 15 to be fixed by approved roof plug, level adjusters and screws etc. the last hanger a the end of each main runner should not be greater than 450mm from the adjacent wall. Flush fitting 1200 mm long prelude 24XL cross tees of size 24x30 mm ( with double stitching) to be interlocked between main runners at 600 mm center to center form 1200x600 mm modules.				
	Cut cross lees longer than 600 mm to be supported independently 600x600 mm modules to be formed by fitting 600 mm long flush fitting prelude 24 XL cross tees of size 24x30 mm centrally between the 1200 mm cross tees. Perimeter trim to be 3000 mm long, colour white Armstrong wall angle of size 19x24 mm secured to walls at 450 mm maximum centre.				
	Note : Provision for light fittings. AC grills and diffusers have to be made at no extra cost supported with tees Angles suitably fixed all complete as per drawing and direction. The area of these cutouts which is less than 0.5 sqmt for one unit will not be deducted while measuring the ceiling area.				
2	MOULDINGS/CORNICES : Providing and fixing decorative mouldings/cornices of P.O.P at approved desing etc. complete incl. painting two or more coats of O.B.D. etc. complete				
a	100 mm wide	R.M.	0		
b	75 mm wide	R.M.	0		
3	GYP BOARD FALSE CEILING	SQM	65		
	Providing and fixing at all height false ceiling with 0.55 mm thk., perimeter channel having flange of 20 mm & another flange of 30 mm & web of 27mm fixed at 610 mm c/c and connected to suspended GL intermediate channel (15x45)x0.9 mm) at 1220 mm centers with ceiling angles of size 25 x 10 x 0.55 mm thk fixed to soffit with GI cleat & steel expansion fasteners. Ceiling section of 0.55 mm thk. Having knurled web of 51.5 mm & two flanges of 26mm each				

	With lips of 10.5 mm are to be fixed to the intermediate channel with the help of connecting clip and in direction perpendicular to intermediate channel at 475 mm centers including fixing of 12.5 mm thick tapered edge gypsum board (conforming to IS : 2095-1982 & 2542-1981) with drywall screws at 230mm c/c, to have a flash finish of tapered and square edges of the gypsum board with recommended filler, paper tapes, finisher, all as per manufactures specification.				
	Including two coats of primer suitable for gypsum board two or more coats of O.B.D. of approved shade and also including making necessary openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitable fixed all complete as per drawing and specification and direction.				
	False ceiling will be provided in approved design and shape such as Oval/Arch or any other design as per instruction etc. complete.				
4	a. FULL HT. PARTLY GLAZED PARTLY WOODEN DOUBLE SKIN PLY WOOD PARTITIONS.	Sqm	42		
	Providing and fixing full height partly wooden, partly glazed double skin partition 60mm thick with following specifications (Measurement shall be taken up to false ceiling ht but sal wood member shall go up to slab/beam soffit)				
	Frame work of sal wood sect. 50x35mm part thereof both ways, including one additional horizontal member of sal wood of size 50x35 mm fixed at 600x600 mm grid fixed firmly to floors/walls etc. treated with antitermite chemicals. The wooden frame structure with vertical & horizontal members to go upto slab/beam soffit for fixity at no extra cost.				
	Providing bottom panel of 6 mm thk approved make stamped with ISI mark, with 1 mm thick lamination of approved make.				
	The partition will be provided with 5 mm thick float glass fixed at 900 mm above the floor level with teak wood beading fixed on both sides of the glass finished with polishing as directed. The float glass to be etched as per approved design. The beading for fixing glass to be fixed on both sides of the partition in such a way that it would be projected from the partition.				
	b. FULL HT. CEMENT BOARD DOUBLE SKIN PARTITION	SqM	10		
	Providing and Fixing full height cement board double skin partition made ouof 65X65X3 mm thick aliuminium section and 10 mmthick cement board of Bison or equivalent make of 2'X 2' centre to centre for verticle members and at 0', 3', 7' and ceiling levels for horizontal member fixed with wooden screws, Painting will be paid seperately.				
5	LOW HEIGHT PARTITION WITH GLASS	Sq.M	18		
	P/F 60 mm thick low ht. double skin glazed wooden partition approx. 1120mm to 1200mm. high, with following specifications:				
	Frame work of sal wood sect. 46 x 46 mm comprising of verticals 750mm c/c & horizontals @600/- mm c/c or part thereof both ways, fixed firmly to floors / walls etc. One additional Sal wood section 46 x 46 mm shall be placed at 700 mm level from floor to fix the table wood shall be treated with antitermite chemicals.				

	6mm th. BWR plywood fixed on both sides of framework, finished with 1.0mm th. Lamination of approved shade and make.				
	P&F 12 mm thick (approx) etched glass as per design and shape fixed with stainless steel glass fixing brackets/crews etc. of length varying from 750 to 1550 mm and height appx. 300 mm. including etching etc. complete as directed.				
6	SAL WOOD DOOR FRAME : p/F Salwood or other soft wood door frame work of 65mm x 125 mm section incl. fixing the frame to ceiling, walls etc incl. a coat of antitermite chemical and painting polishing as directed	Rm	15		
7	12mm toughened glass partition panel to be fixed at top and bottoms with stainless steel standard approved fittings, complete in all respects.	Rm	8		
8	FLUSH DOOR SHUTTER : P/F 30 mm thick Solid core flush door shutter with 1.0mm thick Laminates of approved shade on both side lamination incl. 4 Nos. 100m long brass butt hinges, one brass AL drop. 150mm brass tower bolt, brass handles, door stopper etc and 30x6 mm teak wood lipping at edges.	Sq.M	7		
9	MAIN ENTRANCE GLASS DOOR	Sq.M	0		
	Providing and fixing shutter to be made of 5.5 mm thick float glass with TW top, bottom rail and styles of section 125x48 mm ( finished size) including TW beading for fixing glass. All teak wood to be finished with melamine polish. The float glass to be etched as per approved design including etching colouring State Bank of India (SBI) logo as directed the rate to including necessary hardware fixtures like heavy duly floor spring with stainless steel cover plate and one pivot at top, 2 Nos. 300 mm long decorative stainless steel handles for each shutter. The teak wood surface will be melamine polished to the satisfaction of engineer – in – charge.				
10	Glazed Door Providing and fixing 12 mm thick toughened glass door panel to be fixed at top and bottoms with stainless steel standard approved patch fittings, handles lock, etc. complete in all respects.	Sqm	5		
11	FLUSH DOOR SHUTTER : Providing and fixing 32 mm thick flush door shutter shall have partly glazed portion of required size with 5.5 mm thick glass or without glazed both side laminated with 1 mm lamination of approved colour & make including fitting & fixtures like brass hinges, tower bolts, and handles, as of approved brand and design as per the direction of the engineer-in-charge.	Sqm	6		
		<b>TOTAL (A)</b>			

B	FURNITURE				
	Note : All tables and side storage units to be made out of a combination of 19mm, 12mm, 9mm and 6mm thick BWR plywood of approved make as mentioned in respective items. The top and exposed sides of the tables as well as storage units to be finished with 1 mm thick laminate on external surfaces and 0.7 mm thick lamination on internal surfaces of approved make and shade. All table tops to be provided with 12x20mm teakwood/Rubber wood beading on edges duly melamine polished, unless otherwise mentioned in the respective items. For all exposed edges of the plywood, teak, wood lipping of size 20 x 6 mm to be provided finished with polish. No vertical edge of the table & storage units should be left sharp. All drawers in tables shall be provided with single multidrawer lock of Ebco or Godrej made and storage units to be provided with individual "Godrej" make multipurpose lock. All the edges of the BWR plywood in contact with the floor also to be provided with teak wood lipping of size 20 x 6 mm. Nylon Buffers of suitable size to be provided under the tables and storage units fixed with screws. Wherever required.				
1	SINGLE WINDOW COUNTER AND TABLE	RM	4.6		
	Providing and fixing single window counter of overall width 900 (approx.) mm and working top height 750mm (approx) made out of BWR ply 19mm th. With T.W. lipping at edges incl. T.W. decorative mouldings at front counter all as per drawing and direction of Engineer –in -charge consisting of the following.				
	The working table top of width 900 mm made of 19mm thk. BWR plywood finished with 1 mm thick laminate on external surfaces and 0.7 mm thick lamination on internal surfaces of approved make and shade incl half round TW beading of sect. 20x 12 mm duly polished. The front side of the working top will be provided with 12 mm thick etched /frosted/plain ( as per design) float glass of height about 450mm including etching as per design and necessary exposed edges rounded smooth and polished etc. complete as per drawing or as directed by Bank's Engineer. The working platform to have provision of cable manager and cap.				
	One drawer unit ( at every 1500-1700 mm length of counter ) of 400mm wide (clear internal size) drawer unit having three drawers below to be made out of 12mm thick BWR ply at sides, 6mm thick BWR ply at bottom, 19mm thick BWR plywood at fron and rear including cash separation arrangement in top drawer only with 6mm BWR ply sliding on heavy duty telescopic drawer slide (HTDS 50 of ebco Make). Front surface finished with 1.0 mm thick laminates and internal surface with 0.7mm thick laminate. The drawer shall be provided auto locks of approved manufacturer.				
	On the left side platform at bottom for CPU.The bottom compartment made up of 19mm thick. BWR plywood. The exposed edges of the plywood to be provided with TW lipping of size 20x6 mm duly polished.				
	One M S powder coated keyboard tray with mouse tray as manufactured by ebco ( KBTM 45 ) or EGL ( KBT-M-001) including sliding channel as per manufacturers specification to be provided below the working platform.				

	1 mm thick lamination of approved shade and make to be provide on top of working plate form, on face of each of the 3 drawers, side hung shutter and on the vertical sides of the 19 mm thk. BWR ply wood to be provided with TW lipping of size 20 x 6 mm duly polished. All the inner sides of the counter not exposed from customer side including the bottom of table top as well as the insides of the drawers to be painted / polished with synthetic enamel paint of apprd. Shade and make incl. a coat of primer putty all complete.				
	Foot rest of ply wood with support of section 70x 35 mm to be provided finished with painting.				
2	BACK CREDENZA (Width = 460 mm, Ht. = 750mm, Length as reqd. with Side Hung Shutters)	Sqm	7		
	Providing and making 460mm deep side storage unit of required length having overall height 750m made out of 19mm thk. BWP block board for top, bottom, sides shelf and shutters having 20 x 6 mm teak wood lipping on all exposed edges duly polished and as detailed below				
	Storage unit top of width 460 mm made of 19mm thk. BWP block board finished with 1 mm thick laminate on external surfaces and 0.7 mm thick lamination on internal surfaces of approved made and shade including providing teakwood beading of sect. 20 x 12 mm duly polished on all edges.				
	Providing 19mm thk. BWP block board in verticals at sides 900 mm c/c so as to form storage units attached together, each of width 900 mm overall depth 460 mm and height 750 mm				
	Providing two nos. shelves, one at 75mm above floor level and one intermediate in middle made of 19mm BWP block board with TW lipping on exposed edges duly polished.				
	The outermost sides of the storage unit to be finished with 1mm thick laminate on outer surface incl providing teakwood beading of sect 20 x 6 mm duly polished on vertical edges.				
	Two equal side hung shutters of 19mm thck. BWP block board with teak wood lipping of size 20 x 6 mm on all edges for each compartment of 700 mm approx finished with 1mm thick lamination on outer surface and painted on inner surface.				
	The back of the side credensa to be made with 6 mm thk. BWR plywood finished with 0.7 mm thick lamination of approved made and shade complete.				
	The rate to include for necessary hardware fittings like 2 Nos 75 mm brass hinges of approved quality, one no. handle, one no. brass magnetic ball catcher, for each shutter, one no. 75 mm long brass tower bolt to relevant shutter and one "Godrej" made lock for each compartment consisting of one or two shutters.				
3	OFFICER'S TABLE				
a)	B.M Table : 1800x900x750	Nos.	1		
b)	Officer Table : 1500x750x750	Nos.	2		
c)	Clerical Table : 1350x750x750	Nos.	0		
	Providing and supplying Officer's table as detailed below				

	The table shall be of size of 1550 x 750 x 750 mm height having one side drawer Unit, 350 mm wide (clear internal size) one M S powder coated keyboard tray with mouse tray as manufactured by ebco ( KBTM 45) or EGL (KBT-M-001) including sliding channel as per manufactures specification.				
	Table top of size 1500 x 750 mm (exluding beading) made of 19 m,m thick BWR Plywood finished with 1 mm thick laminate on external surfaces and 0.7 mm thick lamination on internal surfaces of approved made and shade incl TW haf round beading of sect 20 x 12 mm duly polished. All vertical supports frontapron and gable ends of the table are to be made out of 19 mm thick BWR plywood finished with 1 mm thick laminate on external surfaces and 0.7 mm thick lamination on internal surfaces of approved made and shade.				
	Drawer unit of with 350mm (clear internal), consisting of set of 3 nos. od drawer. Each drawer to be made of 19 mm thk. Ply wood for the font and rear 12 mm BWR Plywood for sides and 6mm thk BWR ply for the bottom sliding on Quadrail slides as manufactured by heavy duty telescopic drawer slides (HTDS 50 of ebco Make). Incl. eak wood lipping of size 19 x 6 mm on edges for the drawer. The fron face of the drawers to be finished with 1 mm thick laminate of colour matching with table top laminate. All edges of the drawer unit to be provided with eak wood beading of sect. 20 x 6 mm after fising the laminate and duly polished. No vertical edge of the drawer unit should be lef sharp.				
	Providing multidrawer Godrej or Ebco single lock and approved brass handle for each drawer. Providing circular holes in table top for cables with PVC cable managers of 65 mm dia and cap. 1 mm thick laminate on external surfaces and 0.7 mm thick lamination on internal surfaces of approved made and shade to bottom of table top, drawers & inside the drawer unit etc complete. One footrest of salwood of sec. 70 x 35 mm finished with painting.				
	Apron or Modesty panel: made out of 19 mm thick BWR ply. Outer surface finished with 1 mm thick post lamination at site of approved make and shade as per design shown in drawing in colour with 2 nos. 25mm high bands of 1 mm thick lamination colour matching with sirting and 2 nos 50mm high bands of 1 mm thick lamination colour matching with apron lamination. All internal surfaces are to be finished with apron lamination. The bottom of the apron and gable ends are to be provided with PVC/ rubber gasket so the scratches will be avoided.				
4	OFFICERS' SIDE STORAGE UNIT (900x400x750 mm)	Nos.	6		
	Providing and making side storage unit of size 900 mm length, 400 mm overall dept and 750 (approx.) mm height with side hung shutters as detailed below				

	<p>The storage unit's top of size 900 x 400 mm, both sides and two shelves, one at 75 mm from floor level and other in the middle to be made of 19 mm thick BWP block board. The back to be made of 9 mm thk. BWP block board finished with 1mm thick lamination externally and internally by synthetic enamel painting. The top and both sides of the storage unit to be finished with 1 mm thick laminate on external surfaces and 0.7 mm thick lamination on internal surfaces of approved make and shade.</p>				
	<p>One shelf of size 250 mm wide (internal size) fixed at 75mm from floor level for CPU duly painted. A cabinet with two side hung shutters of 19mm thick BWP block board to be provided with teak wood lipping of size 19 x 6 mm on all edges, finished with 1 mm thk laminate on outer face shade matching to the storage top laminate. Providing 2 Nos 75mm brass hinges, one brass magnetic ball catcher, one brass handle to each side hung shutter. One 75 mm long brass tower bolt for each unit of storage. Painting / polishing the internal surfaces incl. shelves with synthetic enamel paint incl. primer, putty etc. all complete ( all as per sketch)</p>				
5	<p><b>CORIAN MARBLE SURFACES ON FURNITURE / PARTITIONS :</b> Supplying, Fabrication and Installation of Dupont/Corian of 6 to 12mm thk. Applied on table Top, Sides and any where wall, Logo etc in place of 1mm thick laminate. To minimise material usage and facilitate installation a corner block of corian should be made square(Butt) rather than mitred. The edges to be joined should be straight, smooth and clean. Joints should only be made with joint Adhesive for Dupont Corian. All corners of a cutout must be rounded to 5mm radius and the edges smoothed, both on top &amp; bottom, all around a cutout. "L" &amp; "U" shaped corners need smooth 5mm radius inside corner. All works done to the satisfaction of the Architect/Project Manager. Note:- Work done including labour, material wastage, time limits, required hardware etc. Note:- Corian Sheet use in - Salt(Translucent series), Azure &amp; Diamond Blue.</p>	Sqm	8		

6	FULL HEIGHT STORAGE UNITS	Sq.m	4		
	P/F 450 mm deep full ht. storage units of reqd. length with overall ht 2100mm approx with 5 equal compartment. Made of 19mm th. BWP block board with TW lipping at edges. 19mm th BWP block board in verticles at every 900mm or part thereof of sides & at top. Back of 6mm thick & shelves of 19mm th BWP block board one at 75mm above floor & 19 mm in BWP block board one at 75mm above floor and 1 intermediates at ht 1200mm to have two compartment. Top compartment will have one intermediate of 19mm thick plywood. Bottom compartment should have 4 19 mm thick ply wood self. 19mm the BWP block board overall shutter ( i.e. set of 4 shutters in (900 x 2100 mm) (one shutter should not be more than 450 mm wide and 1200mm high) provided with 3 nos ( for 1200 door) and 2 nos for 900 mm shutter 75mm long brass hinges for each shutter, two nos of 75mm tower bolt (one top and bottom), magnetic catchers for each shutter and multipurpose Godrej or ebco lock & brass handles all approved made incl. finishing with 1.0 mm th. Lamination of approved shades at fron. Top & sides & painting the internal surfaces with 2 or more coats of synthetic enamel.				
7	Cabinet for Electric Panel	sqm	5		
	Providing cabinet with openable shutter around the electric panel. Cabinet and shutter made of 19 mm thk. BWP bockboard finished with1 mm thick laminate on external surfaces and 0.7 mm thick lamination on internal surfaces of approved made and shade incl providing teakwood lipping of size 20 x 6 mm on edges. Horizontal slots to be dut in the shutter at top & bottom for ventilation. Rate to include for necessary hardware fixture like approved 75mm brass hinges, brass handle, magnetic ball catcher for the shutter all as directed at site ( Note : Measurement to be taken for the fron surface area of the cabinet)				
8	a. PANELLING : Providing and fixing of wall and column paneling with salwood frame of size 38mm x 25 mm fixed vertically and horizontally 600 mm c/c or less as per site condition and 6 mm thick BWP plywood shall be fixed over the frame ( either in one plane or at different levels) finished wht 1mm thick decorative laminate of approved made and shade ( in one or multi colour) shall be fixed with proper adhesive as directed top of the paneling is to be provided with teak wood decorative beeding of 35mm x 20 mm finished with polish/painting. Panelling will be provided with skirting of 6 mm thk. BWR ply wood finished with 1 mm thk. Lamination of approved make and sha	Sqm.	35		
	b. DECORATIVE PANELLING: Providing and fixing decorative panelling made out of teak wood beeding and coloured acrylic/ glass sheet with approved design. Rate should include rubbing poilishing putty etc.complete.	Sqm.	8		
9	WRITING COUNTER	Nos.	1		
	Providing and fixing half round customer voucher holders writing counter of width 900 mm and maximum depth 450 mm fixed to be wall or partition at a height of 1050mm made of 19mm thk. SWP bock board and 12 mm thick glass top as per the drawing and instruction given by the Bank Engineer.				



10	CONTINUOUS TABLE FOR COMPUTER SYSTEM ROOM	RM	0		
	Providing and fixing 600mm wide continuous table platform for computers made out of 19 mm thick block board. The height of the platform shall be 750MM" and vertical supports shall be given at 900MM" intervals with 19 mm thick blackboard. The drawer, key board, CPU platform, cable managers etc. of approved design and specifications as mentioned in cash counter. The 1 mm thick laminate on external surfaces and 0.7 mm thick lamination on internal surfaces of approved made and shade and officers table specifications.				
11	SOFA SETS	Seat	0		
	"Supplying sofa / settee made from best quality badam/hillock wood framework and legs fitted with rubber nylon shoes fixing with 8mm thick commercial ply back side, 150 mm thick high density foam rubber of approved quality to seat of zigzag spring of approved quality over 12 mm thick approved quality commercial ply and 50 mm thick foam rubber of approved quality to back covered with upholstery of rate not less than Rs.400/-per m finish of approved quality materials including polish finish complete of approved quality and make selected by the Engineer in Incharge. Rate inclusive of cost of material, transportation, loading/unloading, labour tools & tackles up to any lead and lift etc. "				
12	"GRAHAK MITRA TABLE Providing and fixing arch shape 1650mm long grahak mitra table with transaction top of 370mm wide and height 150 mm made out of 12mm glass with blue laquered to be fixed with SS studs.. Exposed faces would be finished with 1 mm thick laminate on external surfaces and 0.7 mm thick lamination on internal surfaces of approved made and shades."	Nos.	0		
		<b>TOTAL (B)</b>			
C.	CIVIL RENOVATION				
1	VITRIFIED TILE FLOORING	Sqm.	0		
	Providing and fixing Premium quality double charge Vitrified tiles of size 600x600mm thickness not less than 9mm conforming to IS : 13630 PART-7 1993 & IS 13755, including fixing the same on existing floor fixed on a screed of approved adhesive viz Carebond or Nitobond or Balendura and joints finished neatly with white cement past pigmented to match the colour of the tiles etc. complete.				
2	SKIRTING : Providing and fixing Premium quality is skirting 100mm high by cutting vitrified tiles of thickness not less than 9 mm conforming to IS: 13630 PART-7 1993 & IS 13755 including fixing the same with a screed of approved adhesive viz Carebond or Nitobond or balendura and joints finished neatly with which cement past pigmented to match the colour of the tiles etc. complete	Rm	0		
3	Granite flooring / Top : Providing and fixing 19 mm thick mirror polished granite slab of superior quality, of zade black or other color shade, fixing in entrance, stairs, window sills, platform etc. with cement mortar 1:3 including rounding of edges, mirror polishing, cutting curing etc. complete as per the direction of the engineer-in-charge.	Sqm	2		
4	Dismantling of brick wall and disposing debris out of the premises.	Sqm	0		

5	BRICK WORK : providing and constructing 100 mm thick wall with ash bricks of good quality in cement mortar 1:4. The rate should include cost of bricks, labour, material, scaffolding, curing, taxes etc. complete.	Sqm	0		
6	PLASTER : plastering the brick wall with cement mortar 1:4 complete including cost of material labour, scaffolding, curing etc. complete.	Sqm	0		
7	EUROPEAN WC : Providing and fixing white vitrous pedestal type EWC of Hindware / Parryware make having P / S trap connection including 10 litre capacity PVC ISI approved make low height cistern. The rate should include all fittings jointing material, labour and making connection with the existing line complete.	Nos	0		
8	WASH BASIN : Providing and fixing white vitrous wash basin with pedastal of Hindware / Parryware make with CI brackets, 15 mm heavy pilar cock, 32mm cp brass coupling, waste pipe etc. The rate should include all fittings jointing material, labour and making connection with the existing line complete.	Nos.	0		
9	HALF STALL URINALL: Providing and fixing flat back stall urinal of size 580x380x350mm with half turn flushing valve with standard CP brass fittings etc. complete.	Nos.	0		
10	BIB COCK : Providing and fixing 15 mm CP brass heavy long body bib cock of approved make and quality confirming to IS : 8931 complete.	Nos.	0		
11	STOP COCK : Providing and fixing 15 mm CP brass heavy stop cock of approved make and quality confirming to IS : 8931 complete.	Nos.	0		
12	CPVC PIPE LINE : providing and fixing CPVC pipes complete with fittings including making chases / holes in walls				
	a) 15 mm dia	Rm	0		
	b) 20 mm dia	Rm	0		
13	Providing and laying Vinyl 40C-20 with HP Latex, 3M cobranded ink printing with over laminate: 8520 laying on wood surfaces approved color pattern and make, including any types of shade, required adhesive for pasting on wall panelling, labour, wastages, etc.	Sqm			
14	Providing and applying wooden paint company make:- Sirca Paints, Product:- Paint on Wood, Brand:- Polyurethane Systems Color sirca, Shade:- White 19nc, finishing glossy varnishes(enamel) of series as per the specifications given by the engineer. Including primer coat, putty coat on wall and other locations as desired after making surface good to receive paint on it without spots or colour difference at any place and providing smooth surface.	Sqm			
15	"WEATHER COAT EXTERIOR EMULSION PAINT Providing and applying two coats and final coat of weather proof exterior emulsion paint (Asian / Berger or equivalent) 7 years warranty of premium quality of approved make & manufacturer of required shade after thoroughly brushing the surface free from mortar dropping and other foreign matter, including two coats of primer and two coats of putty(JK, ASIAN or equivalent) and also including preparing the surface even and sand papered smooth etc. all materials and labour complete."	Sqm	0		

16	INTERNAL PANINTING : Preparing the surface by applying Birla white putty and approved primer, to all surfaces, to give uniform leveled surface in proper plumb, line and level ready to receive paint, including scaffolding etc and applying two or more coats of paint of approved made and shade to give uniform smooth surface with roller finish plastic emulsion paint.				
a	Plastic emulsion paint with roller finish	Sqm	250		
b	Acrylic O B D with roller finish on wall	Sqm.	100		
c	Acrylic OBD on ceiling	Sqm	50		
17	SYNTHETIC ENAMEL PAINT TO WOOD & STEEL WORK Providing and applying 2 or more coats of Synthetic enamel paint of approved made and shade including a coat of primer, putty to existing woodwork (item include preparation of surfaces) so as to obtain a uniform shade all complete	" Sqm"	50		
18	CERAMIC TILES IN TOILET FLOORING	Sqm	0		
	Providing and fixing Premium quality ceramic tiles of Group=IV of size not less than 300 x 450 mm and thickness not less than 7 mm conforming to IS 13755/1993 of approved make, design, shade and patters as directed in flooring fixed on sacred of cement mortar 1:4 20mm thick average and floated in a next cement slurry and joints finished neatly with which cement mixed with pigment to match the colour of the tile, curing, washing cleaning etc. complete as per drawing and details, and as directed all complete.				
19	CERAMIC TILES IN DADO	Sqm	0		
	Providing and fixing Premium quality ceramic tiles of size not less than 300 x 300 mm and thickness not less than 7 mm conforming to IS : 13755/1993 of approved make, design, shade as directed in dado fixed on backing of 12 mm thick cement mortar 1:3 including waterproofing compound, jointed with which cement with pigment to match the tiles etc. complete				
20	TEXTURE PAINT	Sq.M	8		
	Textured pain as manufacture by Spectrum, Heritage with roller finish with Preparation the surface by applying approved primer, including Biurla wall care putty to all surfaces, to give uniform leveled surface in proper plumb, line and level ready to receive paid, including scaffolding etc. and applying three or more coats of paint of approved make and shade to give uniform smooth surface with roller finish				
21	VERTICAL BLINDS	Sqm	35		
	Providing & fixing vertical blinds of 100mm width, febri of approved shade, design with top rail, rods for adjustment of blinds, heavy nyulon cord and fixing brackets etc. complete as per condition with Vista / Tac / Mark make				
22	Providing and applying two or more coat of French polish to the wood work in workmen like manner with preparation of surface.	Sq.M			
23	STEEL WORK MS GRILL	KG	0		
	Providing and fixing security grills etc. of approved pattern and design consisting of MS angles/flats and bars securely fixed with angle cleats to the wall, slabs as per site condition and as directed at site including painting the grill with synthetic enamel paint over a coat of primer all complete.				

24	Providing and fixing 4 mm thick plain sheet glass on existing windows/ventilators with putty etc. all complete	Sqm.	0		
25	COLLAPSIBLE STEEL GATE : Providing and fixing in position collapsible steel shutter with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size with top and bottom rails of T-iron 40x40x6mm with 38mm dia, steel pulleys, complete with bolts, nuts, locking arrangements, stoppers handles including painting with two coats of synthetic enamel paint of approved shade over a coat of primer all complete.	Sqm.	8		
26	ROLLING SHUTTER : Providing and fixing manually operated rolling shutter of approved make and type fabricated with 18 gauge section M.S Flats with galvanized pressed steel side guides of one piece construction including providing the grill in the middle of rolling shutter of 0.60m high of approved design and shape pressed steel bottom rail with interlocking arrangement for steel laths, brackets extra strong door suspension pipe shaft with high tension coil type spring made out of spring steel wire, locking arrangement, holdfast, handles, MS cover hood on top necessary accessories and fixing with 1:1:5:3 Cement concrete including painting with synthetic enamel paint three coats over a coat of primer with putty etc. complete in all respect.	Sqm	0		
27	Planters	Nos.	6		
	P & F in position planters of size 15"x15"x15"made out of 18mm block board or 1 ½ " x1 ½ "wooden frame with laminate & duly polished. on all exposed surface including making GI housing for plants made of superior quality Galvanized Sheets18 Gauge with rounded top edges the top and all sides/ bottom to be water tight The job shall include all material, labour, wastages etc. complete				
28	ALUMINIUM WINDOW: Providing and fixing composite windows to upper and lower portion of 500 mm (height) fixed and middle portion of about 1200 mm to be sliding with two track using standard approved section and 4mm float glass. Complete as per design and direction of Engineer – in charge	Sqm	0		
29	Providing and fixing in position 3mm thick aluminium composite Panel (ACP) with framing of M.Stube sections of min. 2" * 1" and 16 gauge 2'-0" C/C both ways. Tray joints panel to be fixed to the frame with 3M or equivalent adhesive.	Sqm	15		
		<b>TOTAL ( C )</b>			

D.	A T M				
1	FULL HEIGHT PARTITION (ONE SIDE ACP LAMINATION): Providing, fabrication and fixing flush type partition made of aluminum framework and 6 mm thick plywood to be fixed on inside of the framed grid. The exposed surface to be laminated with 3 mm thick ACP (aluminum composite panel) in tray jointing. The inside surface of ply should be painted with oil bound distemper.	Sqm	0		
2	FLUSH DOOR SHUTTER : Providing and fixing 30 mm thick flush door shutter one side fixed with 3 mm ACP of approved colour & make and inside painted with oil paint. It should include fitting & fixure like hinges, tower bolts, and handles of approved brand and design as per the direction of the engineer-in-charge.	Sqm	0		
3	FLOOR SPRING Providing & fixing floor spring (heavy duty) ISI make of Hyper/Hardwin/ Everite make.	Nos.	4		
4	ACP Panelling : Providing and fixing 3 mm thick ACP panelling on internal wall with tray jointing and necessary aluminium square pipe frame work. Panelling as per the company specifications. The rate is inclusive of all fixtures and fittings (with sealant) for proper finish.	Sqm	45		
5	Glazed Partition Providing and fixing 12 mm thick toughened glass fixed partition to fixed on black powder coated aluminum jumbo sections at top and bottoms stainless steel standard fittings, etc. complete in all respects.	Sqm	8		
6	Aluminum Glass Door Providing and fixing galzed door of 5.5 mm thick glass in black powder coated standard aluminum section frame with fittings like handles, hinges, tower bolts etc. of approved make.	Sqm	0		
7	False Ceiling: Mineral fiber board ceiling	SQM	0		
		TOTAL (D)			
E.	CHAIRS				
1	High back , revolving executive chair with cushioned seat and back and molded PVC hand rest Godrej PCH/Featherite/Wipro make for RM.	Nos.	1		
2	Medium back, revolving executive chair with cushioned seat and back and molded PVC hand rest Godrej PCH/Featherite/Wipro make for Officer.	Nos.	7		
3	Visitor chairs with cushioned seat and back and molded PVC hand rest Godrej PCH/Featherite/Wipro make for visitors.	Nos.	7		
4	Supplying and fixing three seater S.S frame airport chairs of approved manufacturer as per their specification.	Nos.	0		
		TOTAL (E)			
	TOTAL (A)+(B)+(C)+ (D) +(E)				