

**CORREGENDUM-01**  
**REVISED BOQ FOR AIR CONDITIONING WORKS OF KARIMNAGAR**  
**MAIN BRANCH, KARIMNAGAR, TELANGANA**

S NO	DESCRIPTION OF WORK	UNIT	QTY	RATE	AMOUNT
1	Supply, Installation, testing, commissioning of following <b>Ceiling suspended Duct able Unit (R410-Ozone Friendly and Non CFC Refrigerant)</b> Air conditioners with scroll compressors, copper finned air cooled condensers, condenser fans, expansion valve, Evaporator with cooling coils and blower section. Including proper mounting arrangement and accessories, initial charge of refrigerant, Thermostat, evaporator units and control panels etc complete of the capacities.				
a	11.0 TR	Nos	2		
2	Supply, Installation, Testing and commissioning of the following capacities of <b>Cassette Units (Gas -R 32/ R134A /R407/ R410-Ozone Friendly and Non CFC Refrigerant)</b> with necessary gas Top Up complete with <b>scroll inverter compressor</b> , copper condenser, evaporator, vibration isolators, structural supports with required hard ware, control cable, etc.				
a	3.0 TR including stand	Nos	1		
3	Supply and laying of copper refrigerant piping using <b>Hard drawn copper pipe duly insulated with 9mm thick nitrile rubber tube sections</b> neatly taped at joints and clamped properly with all necessary fixing arrangement. The copper piping shall include suction and liquid lines along with electrical control cable between the indoor and outdoor units				
a	Suction & Liquid line for 11.0 TR	Rmt	25		
4	Soft drawn copper piping with 9 mm thick Nitrile rubber insulation including all necessary fittings between indoor and outdoor air cooled condensers of the following sizes.				
a	Suction & Liquid line for 3TR 4Way Cassette as per Standards	Rmt	10		
5	Supply and Laying of Drain piping using hard drawn <b>PVC pipes covered with 6mm thick Nitrile rubber</b> insulation including PVC fittings etc., complete for the following sizes				

S NO	DESCRIPTION OF WORK	UNIT	QTY	RATE	AMOUNT
a	25 mm dia size	Rmt	50		
b	32mm dia size	Rmt	30		
6	Supply, Fabrication & Erection of factory fabricated GSS Ducting with necessary angle flanges & GI full threaded rods and slotted rail supports as scheduled and as specified.				
a	24Guage GI Ducting	Sqm	85		
b	22Guage GI Ducting	Sqm	45		
7	Supply, fabrication, and erection of fire retardant canvass connection with necessary flanges, nuts and bolts etc	Nos	2		
8	Providing <b>Acoustic Insulation</b> for initial portion of ducting with 12mm thick Rigid board Fiber Glass material finished covered with RP tissue and perforated aluminum sheet fixing it properly with necessary nuts and bolts.	Sqm	25		
9	Supply & fixing of <b>Thermal insulation</b> using 6mm thick Nitrile rubber	Sqm	55		
10	supply and fixing of <b>Volume control dampers</b> made out of 16G GI sheet, low leakage V type opposed blades, gear type, with nylon bushes for free operation	Sqm	1		
11	Supply & erection of <b>Fresh air arrangement</b> including GI Volume control damper, 20 micron filter, GI duct cowl piece for rain protection along with Bird screen.	Lot	1		
12	Supply and Erection of MS Outdoor stands for the condensing units ( <b>Duct able Units</b> )	Nos	2		
13	MS Powder coated collar dampers	Sqm	2.5		
14	Supply and fixing of Aluminum powder coated continuous Grills	Sq.M	7.2		
15	Supply and fixing of electronic timer for alternate running of Split AC units in ATM with connection etc required	Nos	1		

S NO	DESCRIPTION OF WORK	UNIT	QTY	RATE	AMOUNT
16	Electrical cabling Interconnecting between indoor unit and outdoor unit of the following sizes				
a	3C X1.5 sq mm	Rmt	40		
17	Removing, servicing, re installation and commissioning of existing split AC units of 1TR/ 1.5 TR/ 2TR form the existing branch premises to new premises including gas charging if required.	Nos	4		
18	BUY BACK ( amount to be paid to the Bank): Removing and Buy back of old/ beyond repairable AC units as is where is condition form branch after taking the permission and approval of Bank's official of capacities 1TR/1.5 TR/ 2TR	Nos	-3		
19	<b>Comprehensive ANNUAL MAINTENANCE CONTRACT (AMC) For the Air conditioning units after warranty period of One Year. (i.e. 11TR- 2 Nos, 3 TR-1 No) which includes all spares, compressor, replenishing the refrigerant, bimonthly servicing, any number visits if any problem occurs.</b>				
a	Second Year	TR	25		
b	Third Year	TR	25		
c	Fourth Year	TR	25		
d	Fifth Year	TR	25		
	<b>Total AC Works except GST</b>				
	<b>Discount if any</b>				
	<b>Grand Total of Air Conditioning Works except GST</b>				

NOTE:

**PRICE QUOTED SHOULD BE EXCLUSIVE OF GST**

**SIGNATURE WITH SEAL**