

NIT NO: GUW201907033

**RENOVATION WORKS
INTERIOR FURNITURE WORKS
OF SBI POMSHUTIA BRANCH**

PRICE BID

ANNEXURE-III



**SBI INFRA MANAGEMENT SOLUTIONS PVT. LTD., (SBIIMS),
(WHOLLY OWNED SUBSIDIARY OF SBI)
GUWAHATI CIRCLE OFFICE
3rd FLOOR, SBI, LHO, GUWAHATI BUILDING
DISPUR, GUWAHATI-781006**

BOQ FOR INTERIOR & FURNITURE WORKS OF SBI POMSHUTIA BRANCH

S.N.	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
1	<p>Supply and installing new SWO Counters of overall size 1520 mm X 1830 mm X 750 mm, including cost of side credenza (1200mm x 450 mm x 750 mm) made up of 19 mm thick Block board of approved brand all around and finished with laminate of 1.0 mm thick of approve colour, brand and shade. The cost to include three drawers of 375 mm wide made up of 6mm/12mm ply of approved brand on right hand side of the table on telescopic slider with partitions for keeping of notes of different denominations, a keyboard tray 250 mm wide, CPU stand, foot rest as designe and direction by bank. The credenza unit should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All exposed edges to have teak wood bidding/lipping stained to match the desk and melamine finished.</p> <p>All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved make. Locks to be of single control type. Design and detail of the counters shall be as per Bank's new uniform colour, layout & elevation policy, with curvature on front with flexi ply. Counter & Credenza top to be provided with 8mm thick glass duly finished on edges and necessary cut to accommodate wires, edges to be m/c polished, with ms powder coated wire manager, complete as directed by EIC and placement as per layout given.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply or equivalent. Laminate Make: Greenlam/Centurylam/Archidlam or equivalent.</p>	NOS	2		
2	Providing and fixing 12mm thk. Toughened Float Glass in front portion of single window counters with metal clamps including cutouts for passing currency and communication as per details. The edges of the glass to be polished etc. complete to the satisfaction of Architect/ Bank's Engineer.	SQM	2.2		
3	WORK STATIONS WITH SIDE STORAGE				
i	<p>FOR OFFICERS</p> <p>Providing and laying <u>Officer's Workstations</u> of over all size 5'-0" X 6'-0" , of top as mentioned in the attached drawing. It shall consist of 19mm thk. Comm.block board top as per design (double edge on the front and back with) supported on 19mm thk. Comm. blockboard verticals. Suitable (as per Architects design) . A 19mm thk. Comm.block board apron shall be provided as per Architects design with necessary pattern. The Table top and side storage should be finished with 1mm thk Laminate of approved shade and make. The Front Apron/ Wall of the Table (Customer Side) shall be finished with 1mm Laminate of approved shade & make as per design. Each top should be provided with 3" dia PVC wire manager of approved quality near the CPU / Monitor , 1 no Metal Keyboard Tray of Best quality, 1 no Metal CPU Trolley at position as shown in drawing. .Rate to include the cost of locks of M/s Godrej make or, equivalent handles , 8mm glass on the table top polishing , placing, fixing at site , transportation etc. complete.The side Storage shall have openable shutter on hinges with necessary locking arrangements. All exterior parts of the storage, including the shutters shall be finished with 1mm thk laminate of approved shade & make over block board. The Work station shall also consists of a pedestal for the table as per design with central locking system. The external face and sides of the pedestal shall be finished with 1mm thk laminate of approved shade & make over block board. All internal surfaces shall be finished with 0.80mm thk laminate of milky white shade of approved make instead of paint. All locks shall be used of Godrej make.Rates Shall be inclusive of all locks , handles, magnets, Tower bolts etc and other hardware items as may be required and as asked by the architect/ engineer incharge.</p>	NOS	2		

ii.	<p>BM's table: Size 1.67 m X 0.915 m X 0.762 m, Side table 1.143 m X 0.405 m X 0.762 m Or (Size5'-6" X 3'-0" X 2'-6", Sidetable 3'-9" X 1'-4"X2'-6") : Providing, making & placing in position executive table and side table ('L' Shaped) with the following specifications: a) Table top made in 25 mm block board / BWR ply & all other members with18/19 mm BWR plywood with 1 mm laminate, except on top (which has to have good quality decorative laminate of approved shade) all edges to have 20 X 6 mm beech wood lipping. b) One drawer cum shutter unit with necessary hardware viz: drawer channels, handles, locks etc. c) One CPU pedestal. d) One ply wood keyboard tray with channels to be provided e) One footrest f) Side table with shutters to be made with 25mm blockboard / BWR ply with 1 mm laminate or top and other members with 18/19 mm BWR plywood & 1 mm laminate with necessary hardware viz: cabin ethinges , handles, locks, towerbolts, etc. and 25 X 40 mm beech wood beading and 20 X 6mm beechwood lipping etc. g) All the exposed surfaces to have 1mm laminate of approved shad eand brand. All unexposed surfaces to have two coats of enamel paint with putty. All wooden members to have melamine polish.</p>	NOS	1		
4	<p>PARTITIONS WORKS: Note :- The rate shall be include of frame work above false ceiling level. Measurement should be taken up to false ceiling level and visible portion only.</p>				
i	<p>FULL HT GLAZED PARTITIONS Providing & fixing in position as per the layout full metal stud dry wall partition with the following specifications: a) supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick aluminiums tuds@600mmc/cand 51 X 32mm aluminium tracks at floor, middle, door and ceiling level with joints staggered.The verticals should touch the ceiling with horizontal ceiling channel at slab / beam bottom. The rate should include necessary strengthening with studs / tracks or channe at doors and other openings. b) 9mm BWR Plywood fixed on both sides with 25mm dry wall screws. c) 1 mm laminate on both sides (dark for bands, light for body) upto false ceiling level. d) 6 mm thick clear float glass with frosted film design as directed between 1050 X 2000mm level in specified areas fixed with 85 X 15mm beechwood jamband 12 X 12mm beechwood beading. e) All beech wood members to have melamine polish finish.LengthXheight upto false ceiling will measured for payment.</p>	SQM	34		
ii	<p>LOW HT GLAZED PARTITION Providing and fixing GI metal stud low height partitions with the following specifications. a) Supporting system comprising of best locally available make 51 X 35 mm aluminium studs at 600mmc/c and 51 X 32 mm aluminium tracks at floor,middle and at 1200 mm level with joints staggered.The rate should included necessary strengthening with studs /tracks or channels at openings. b) 9 mm plywood with 1mm laminate(dark for band sand light for body) on both sides c) 85 X 15 mm beechwood capping on top and sides of openings. The beechwood members to have melamine polish finish. d) 8 mm glasses with edges polished and with etching design above 3'-0" height at specified areas as directed.</p>	SQM	7.4		

5	PANELLING WORKS				
i	<p>WALL PANELING (ONLY FOR BM ROOM & TRANSANCTION AREA) Providing & fixing GI metal stud wall panelling with the following specification: a) Supporting system comprising of best locally available make 51X35X0.55mm thick aluminium studs @ 600mm/c and 51X32mm aluminium tracks at floor, middle, door level and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. b) 9mm BWR plywood fixed on one side with 25mm dry wall screws for the entire height of panelling. c) 1mm laminate (dark for bands, light for body) upto false ceiling level. e) All beechwood members to have melamine polish finish. length X height up to false ceiling will be measured for payment.</p>	SQM	24		
ii	COLUMN PANELING:- Same as item no. 5 (i) but for columns	SQM	14		
iii	<p>Providing & fixing in position Aluminium Composite Panel (ACP) Panelling with framing of min 20 gauge 35 mm x 25 mm Aluminium Tube section in 600 mm C/C both ways. Minimum 3 mm thick ACP to be fixed over the freamework with 3M or equivalent adhesive and mirror screw in 600 width panels or distributed equally. Joints to be finished with Silicon based sealant. Aluminium foil thickness to be min 0.20 mm on both sides.</p> <p>Make: Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used.</p>	SQM	10		
iv	<p>Shutter Boxing: Providing & fixing in position Aluminium Composite Panel (ACP) with framing of min 20 gauge 35 mm x 25 mm Aluminium Tube section in 600 mm C/C both ways. Minimum 3 mm thick ACP to be fixed over the freamework with 3M or equivalent adhesive and mirror screw in 600 width panels or distributed equally. Joints to be finished with Silicon based sealant. Aluminium foil thickness to be min 0.20 mm on both sides. ACP Trap door will be 12 mm ply finished with 3 mm thick ACP.</p> <p>Make: Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used.</p>	SQM	4.6		
6	DOORS				
i	<p>ENTRANCE DOORS - IN ALLUMINIUM POWDER COATED SECTIONS (HEAVY DUTY-14 GAUGE) Providing and fixing fully glazed alluminium (heavy duty-14 guage) doors at the main entrance as shown in the drg. Door shall consist of approved make heavy duty-14 guage sections 6" x 2" for top & bottom rails, 2" X 2" for vertical styles. 10mm thk. approved make clear float glass shall be provided and fixed in the framing. Rate shall include necessary etching film / Logo, Pad Lock (GODREJ MAKE), 1 pair of 12" long S. S. Handles (Curved shape , C Shape in Elevation), floor springs (MAKE EVERITE / GOLDEN /HARDWIN /EVEREST MAKE), gaskets & any other necessary hardware items. 'BANKING HALL - FULLY GLAZED (10MM THK GLASS)</p>	SQM	3.4		
ii	<p>PARTLY GLAZED FULL HEIGHT DOOR The door frame made of approved quality Beach/Safeliwood. The Shutter to be 35mm thk BWR Block Board with both side finished with 1mm thk laminate with necessary inlay sand grooves as per drawing. The door inlet with 8mm thk glass with etching design as directed. The edges of the door and four side of the glass shall be fixed with beading. The door to be provided with handles, locks of Doorset, doorclosers and stoppers etc. and other necessary hardware. All beading surface to be finished with melamine polish as instructed by Bank's Engineer/architects, all complete as per drawings. All materials to be approved by Bank's Engineer/ architects. With door closure (With all Hardware EVERITE / GOLDEN / HARDWIN / EVEREST MAKE)</p>	SQM	4.8		
iii	<p>SINGLE WINDOW COUNTER DOORS (2' 0 X 4' 0" -IN LAMINATE FINISH) Providing and fixing solid doors of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 1mm thick laminate of approved shade & make on both sides. The edges finished with steam beach lipping. A door frame if required shall be finished with laminate of approved shade. Rate shall include approved make NIGHT LATCH LOCK, door closure, door stopper, a pair of handles 9" SS Brushed finished, 5" hinges 2 Nos., buffers, tower bolts, etc with necessary hardware items.</p>	NOS	2		

iv	Wicket Gate: Providing and fixing Wicket Gate made out of 32 mm flush door finished with 1 mm lamination of approved shade on both sides with all necessary hardware such as hinges, tower bolt etc. Complete. The edges shall be finished with beech wood beading polished.	SQM	2.8		
v	ALUMINIUM HEAVY DUTY FRONT GLAZING Providing and fixing fully glazed heavy duty aluminium sections (14 Gauge) at the main entrance as shown in the drwng. Glazing shall consist of approved make heavy duty 6" x 2" sections for the top & bottom rails and 2" x 2" sections for the vertical styles. 10mm thk. approved make clear float glass shall be provided and fixed in the framing. Rate shall include necessary etching film / LOGO, and any necessary hardware items. (Heavy Duty 6" & 2" thick frames(14 Gauge) - approved make) WITH ANODISED SECTIONS (As per Colour Specified by Bank)	SQM	5.8		
7 i	BACK OFFICE RUNNING COUNTER (2'-0" WIDE)-FOR UPS/SYSTEMS ROOM Providing and laying a Plain running counter with only key board and Pencil Drawers at every 3'-0" length for over all size of top as mentioned bellow. It shall consist of 19mm thk. Comm. block board top as per design (double edge on the front and back with 1mm thk laminate on the edges) supported on 19mm thk. Comm. block board verticals at every 3' length. The top, edges and all other external surfaces of the counter should be finished with 1.0 mm thk Laminate (suede finish)of approved make. Each desk should be provided with a 3" dia PVC wire manager at the given location and a metal CPU Trolley.	RM	3		
ii	Specifications same as above but only the table Top to be finished with approved shade of 1mm thick laminate of approved shade & make.	RM	3		
8	LOW HT RUNNING STORAGE (450mmDX750 HT) (BACK CADENZA) Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 19mm thk block board for all sides and back support of 6mm thk Commercial plywood & also 19mm thk block board shutter with self closing hinges of haffele make(full ovel open) & lipping matching with the approved shade of laminate on all the edges. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make.Divisions of the shutter shall be make equally according to the length of the storage. A 19 mm thk fixed block board shelf on battens shall be provided @16" intervals from the base and edges of the storage top shall be finished with laminate. All inner surfaces including shutters shall be finished with enamel paint.Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make	RM	4		
9	BANK'S LOGO ON ACRYLIC SHEET OF MAXIMUM SIZE 2' X 2' Supplying and Fixing Bank's Logo made of Stainless Steel of 1" thk and 24" overall diameter with polishing etc as per design and direction of Engineer Incharge. Complete in all respects	NOS	1		
10	FALSE CEILING AND P.O.P. WORK				
i	MODULAR FALSE CEILING- ARMSTRONG/ equivalent make Grid type :: Providing suspended ceiling at approx. 2450 mm height from floor with 600x600 mm size Fine Fisher Tiles Armstrong make including aluminum frame work and other fixtures as provided by the manufacturer as per specification and as directed by Engineer In charge for system, printer rooms, B.M.'s chamber and Banking hall .(No false ceiling inside strong room, locker room , toilets , stiarcase , record room, canteen , kitchen , store room etc.)	SQM	53		
11	CUSTOMER WRITING DESK: Supplying & fixing of customer writing table 750 x 450 x 1050(H) mm with 18mm thick/ MDF Board and 1mm thick lamination and necessary timber beading/lapping complete with open slots below for keeping forms / vouchers etc. as per drawing and direction of Engineer in Charge.	NOS	1		
12	VERTICAL BLINDS: Providing and fixing Vertical Blinds (Vista Levelor/ MAC/ DACK) of approved shade, texture and fabric including all associated accesories etc. complete to the satisfaction of Architect/Bank's Engineer. (Base price of the fabric be used Rs. 100/- sq.ft.).	SQM	10.2		
13	Stickering with 3M designer film: For SWO counters,UPS-Server Room, BM Chamber, Toilet(G) & Toilet(Ladies)	Set	1		