



SBI INFRA MANAGEMENT SOLUTIONS PVT.LTD.

CIRCLE OFFICE, THIRD FLOOR, STATE BANK OF INDIA, SYNERGY BUILDING, C-6, G-BLOCK, BANDRA KURLA COMPLEX, BANDRA EAST, MUMBAI-400051

PART – B: FINANCIAL BID

TENDER ID: MUM201909025

DATE : 23.09.2019

TENDER FOR:

CIVIL WORK OF SAINAGAR BRANCH

TENDER SUBMITTED BY:

NAME : _____

ADDRESS : _____

DATE : _____

TENDER INVITED BY:

Vice President & Circle Head,

SBI Infra Management Solutions Pvt. Ltd; 3rd floor, Circle Office, State Bank of India, Synergy building, C-6, G-Block, Bandra -Kurla complex, Bandra East, Mumbai-400051.

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
1	Providing and applying acrylic emulsion paint of approved quality, shade and colour in 2 or more coats to achieve desired result including applying one coat of primer of cement paint, preparing the surface by cleaning the dust/dirt by watering/brushing the surfaces, filling in cracks/crevices ,scaffolding at all levels, necessary lead, lifts etc. complete	310	sq m		
2	Providing and Laying vitrified tiles of approved make and quality of required size for flooring and skirting in required position laid on bed of C.M.1:4 including cement float, filling joint with white / colour cement slurry, cleaning, curing, complete. 600 mm x 600 mm. size (Basic rate = Rs. 70/- per Sqft) The item rate shall be inclusive of removing the existing flooring & skirting.(for repair purpose)	200	sq m		
3	Constructing 9"thk. Brick masonry wall Providing & Constructing 6" thick brick wall masonry in cement Mortar (1:4) including (1:2:4) R.C.C.Patti of size 11cm X 15cm at bottom & 2 Nos. M.S. bars at to properly bend & bound at ends along with form work,scaffolding,racking out joint, both side neeru plaster finish, clean / level the surface, curing carting away debris out of compound, cleaning the site etc. complete as per instructions of Architect. RCC lintels of 100 mm thickness to be provided at each interval of 2.1 m during brickwork.	3	Cu Mtr		
4	Providing general cement plaster 12 mm in cement mortar (1:4) in all positions including curring, scaffolding, cleaning, carting away debris out of the compound, cleaning etc. complete as per the instructions of the architect.	10	Sq mt		
5	Providing and laying Cast in situ/Ready Mix cementPlain Cement Concrete in M-10 of trap/ granite/quartzite/ gneiss metal for foundation and bedding including bailing out water, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic microprocessor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With natural sand/V.S.I. quality Artificial Sand	2	Cu mt		
6	Providing and fixing in position reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams and columns, canopies, staircases, newels, chajjas, lintels, pardis, coping, fins, arches etc. as per detailed design and drawings and schedules including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required completed. (use TMT steel only.)	0.3	M.T.		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
7	Providing & fixing Pantry Platform 750 mm wide out of 20 mm thk. Black granite supported over 12 mm thk. cement board including double moulding on the edges to granite, SS Nirali Sink (550 x 450), with 25 x 50 mm size Aluminium pipes TW inserted for framing below counter, including water supply CPVC pipes & bib-cocks, etc. complete. (Item includes dismantling of existing platform).	1.8	RMT		
8	Providing and fixing heavy duty inter locking concrete coloured paving blocks of 60 mm thickness of having a strength of 300 kg/sq cm of approved quality and shape on a bed of crushed sand of 25 to 30 mm thick including skirting joints and cleaning etc complete.	50	Sq MTR		
9	Providing and fixing granite stone to treads and risers of staircase and entrance including all necessary material and labour.	10	Sq MTR		
10	Providing and fixing panelling on External walls and for External Rolling Shutters boxing. Framing shall consist of Both ways horizontally and vertically on the wall/column with Aluminium Sections of 50mmx25mmx1.2mm as directed by Bank /Architect. This framing would be covered with 6mm thk. Comm. Ply (In case of wooden frames), finished with 3mm thick exterior grade multi-coloured "Aluminium Composite Panel". The rate shall be inclusive of necessary scaffolding, cut-outs, fixtures and fittings, sealant etc. complete.	30	Sq Mtr		
11	Providing and laying Ceramic glazed floor tiles(Antiskid) of any size (9-10mm thickness) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 sand) including pointing the joints with white cementand matching pigment, curing etc., complete.(Basic rate of Tile Rs. 650/Sq.m.)	10	SQ MTR		
12	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (6-7mm thickness) of approved make in all colours, shades except burgundy,bottle green, black of any size as approved by Architect in skirting, risers of stepsand dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 sand) andjointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete (Basic rate of Tile Rs. 550/Sq.m.)	30	SQ MTR		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
13	Providing and applying fibre reinforced elastomeric liquid water-proofing membrane with resilient acrylic polymers having Sun Reflectivity Index (SRI) of 105 on top of concrete roof slab in three coats @10.76 litre/ 10 sqm. One coat of self-priming of elastomeric waterproofing liquid (dilution with water in the ratio of 3:1) and two coats of undiluted elastomeric waterproofing liquid (dry film thickness of complete application/system not less than 500 microns). The operation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as per the direction of Engineer-in-Charge. For horizontal surface one coat @1.85 kg per sqm. Single component UV resistant flexible acrylic coating, vapour permeable membrane(1.0 mm thick) & eco-friendly. Application with brush.Curing must be done by only placing a wet hessian at least upto 72 hrs after drying, and thereafter by proper curing with water(Make- Perma- Eazee Coat/Choksey-Acrylic colour membrane/ROFF-Hyguard EX)	50	SQ MTR		
14	Providing and applying water proofing treatment to vertical surface of brick and R.C.C. wall, elevated and overhead R.C.C./ brick water tanks and sumpwell etc. in all directions by using standard acrylic copolymer coating of Roff Hyguard, Monopol 456, Dr. Fixit Pidilite 2K or equivalent in two coats including cleaning the surface by wire brush, washing and drying i,and as directed by Engineer incharge etc. complete	20	SQ MTR		

S U M M A R Y :			
Total of Interior Work	Rs.		
Less discount (if any)	Rs.		
Total cost of work Tendered	Rs.		
Add SGST @ 9%	Rs.		
Add CGST @ 9%	Rs.		
FINAL AMOUNT INCLUDING GST	Rs.		

Total Amount
Rupees in words: _____

Signature & Seal of Contractor

Date: _____