



**SBI INFRA MANAGEMENT SOLUTIONS PVT.LTD.**

**CIRCLE OFFICE, THIRD FLOOR, STATE BANK OF INDIA, SYNERGY BUILDING, C-6, G-BLOCK, BANDRA KURLA COMPLEX, BANDRA EAST, MUMBAI-400051**

**PART – B: FINANCIAL BID**

<b>TENDER ID: MUM201909026</b>
<b>DATE : 23.09.2019</b>

**TENDER FOR:**

**INTERIOR AND FURNITURE WORK OF GADCHANDUR BRANCH**

**TENDER SUBMITTED BY:**

**NAME :** \_\_\_\_\_

**ADDRESS :** \_\_\_\_\_

\_\_\_\_\_

**DATE :** \_\_\_\_\_

**TENDER INVITED BY:**

**Vice President & Circle Head,**

**SBI Infra Management Solutions Pvt. Ltd; 3<sup>rd</sup> floor, Circle Office, State Bank of India, Synergy building, C-6, G-Block, Bandra -Kurla complex, Bandra East, Mumbai-400051.**

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
1	<b>False Ceiling:</b> Providing & fixing in position 12 mm thick gypsum board false ceiling fixed with 16 gauge galvanized frame supported from and fixed to RCC slab with Anchor bolts. The ceiling should contain approx. 40 % of the ceiling area of 12mm thick Mineral Fibre ceiling Board of Armstrong or equivalent approved make with framework, runners, cross runners & suspenders from the existing ceiling as per the manufacturers details and specification and 600X 600mmX 15mm thick mineral fibre ceiling ( 600*600 mm ) - beuti sky or other approved pattern and stepping. All the joints to be properly sealed with jointing tape and finished with approved jointing material. The item includes making cut-outs and providing necessary frame work for light fitting, grill diffusers and ducts etc. which have to be made with frame of perimeter channels of size 20mm x 30mm x 0.55mm. thick supported suitably and angle bead is to be used at steps to get straight line finish etc. complete. The item rate shall also include preparation of surface with sanding, and 3 coats of Acrylic Emulsion paint in approved shade over a coat of primer / putty including necessary work etc. complete as per Bank Engineer's instruction.	180	Sq M		
2	<b>Single window counter :</b> Providing & fixing in position single window counter as per design, made of 18 mm / 19mm thick MR grade ply structure. The work top is to be made of 18 mm / 19mm thick MR grade ply structure. Thereafter, a double layer of flexi-ply (12 mm + 6 mm thick) ( ( the bottom of this niche to have provision of cove lighting with LED strips) is to be fixed with necessary fittings to the plywood structure and laminated glass in approved shade, . All exposed external surface finished with 1 mm high gloss laminate and internal surfaces finished with 0.8 mm laminate of approved shade. The work is to be completed with providing of foot rest, key board tray with telescopic arrangement. vertical glass of 12 mm to be fixed at the front of SWO with one horizontal glass ( if required) of approx 150mm with itching and crystal finish etc. complete as per instructions of EIC. Design and detail of the counters shall be as per Bank's new uniform colour, layout & elevation policy available with Bank's Engineer.	9	Rmt		
3	Providing and fixing factory made <b>solid core flush door</b> in single leaf 30 mm thick, finished with approved 1mm th. Laminate on both faces with / without glazing and venetians in the positions shown on the drawings or as directed, all necessary beads, moulding and lipping, Stainless Steel fixtures and fastenings with CP / brass mortise lock, Stainless Steel handles on both sides, stoppers and exposed woodwork finished with French-polish complete. (Without door frame).	3	Sqm		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
4	<b>Low / medium height partition:</b> Providing and fixing in position low / medium height partition made of 50 x 50 x 1.2mm medium duty aluminium hollow square pipes framed at 0.6 m to 0.45 m c/c both ways covered with 6 mm MR grade ply and 1mm thick laminate of approved shade & make, both sides including necessary opening / outing for receiving cheques & other papers, and to receive 10 mm th. Float glass including all necessary opening for electric / telephonic conduits etc. as per requirement. (Glass area in the partitions will be deducted in the measurements of partition).	35	Sqm		
5	<b>Glass partition:</b> Providing and fixing 10 mm thick glass with etching as per design for low height partitions held with SS clits (D brackets). All exposed glass edges with rounded moulding and crystal polish. All exposed woodwork to be finished in 3 coats of French polish/ melamine polish.	12	Sqm		
6	<b>Providing and fixing in position 12mm thick toughened glass door</b> including fixed side panel. The door to be fixed with heavy duty Dorma make floor spring, providing 300mm long 30mm dia SS pipe handle and door lock of Ozone/Dorma or equivalent make with necessary cutting chases in floor and restoring the same to its original position complete. Rate to include providing suitable wooden Top and bottom rail, frosted film as per detailed Engineering drawing complete. The item includes removal of existing door and buyback.	8	Sqm		
7	Providing & fixing in position floor spring for receiving glass door of approved make. (DORMA / HETTICH or equivalent)	8	No.		
8	Providing and fixing in position door closer of approved make (Hyper / Godrej or equivalent).	8	No		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
9	<b>Providing and supplying table for the B.M table</b> ( size 1800x750x750 mm) to be made out of 18/19mm thk. IS: 303 Grade BWR Plywood finished with approved 4.0mm thk high end veneer with polycoat polish for the top & 4.0mm thk veneer with melamine polish for all other exposed areas. The top of the table to have t.w. moulding all around. The rate shall be inclusive of providing a keyboard tray on sliding telescopic channels & a pedestal drawer unit made out of 16mm thk IS: 303 BWR Plywood on side with 2 nos of equal sized drawers on sliding channels & openable shutter below. The side credenza shall be on the other side & shall be paid for separately under the relevant item. All internal surfaces to be finished in approved 0.8mm thk laminate. All the external surfaces shall be finished with 4.0mm thk approved high end veneer with melamine polish including the pedestal drawer unit. The table shall have 12 mm thk clear glass on top with bevelled edges and necessary holes and provision of 12 mm glass at front side for Modesty panel. The rate shall also include CPU trolley of reputed manufacturer, keyboard tray as per the approved makes which shall be heavy duty. The necessary hardware such as automatic locking, ball catches, wire managers etc. to be provided as per the instructions of the Engineer. The Elevation of the table shall be as directed by Engineer on site. Design and detail of the table shall be as per Bank's new uniform colour, layout & elevation policy available with Bank's Engineer.	1.00	No		
10	<b>Officer and Staff Tables</b> : Providing & fixing in position tables made of 18/19mm MR grade Ply at top, side and front, support along with drawer unit & Key board tray with telescopic arrangement & CPU base resting on foot rest of teak wood member of 75 x 40 mm. 19mm th MR grade ply modesty panel. All external surfaces to be finished with 1 mm thick laminate and internal surface finished with 0.8 mm of approved shade and make. Including powder coated fittings like sliding channels, for key board & drawers, medium duty hinges for shutter, cable manager. S.S. handles in approved design and size and locks wherever directed in approved make. All exposed plywood edges to be finished with 6mm th. Teak wood beading with French polish in approved shade and necessary locks to shutters etc. complete in all respects. Design and detail of the table shall be as per Bank's new uniform colour, layout & elevation policy available with Bank's Engineer.				
a	<b>Officer's Tables - 1500x750x750 mm</b>	3	No.		
b	<b>Staff Table -1200x750x750 mm</b>	3	No.		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
11	<b>Grahak Mitra Table</b> : Providing & fixing in position Grahak Mitra table of size 1350 mm*750mm*675 mm made of 18 mm MR grade Ply at top, side and front, support along with drawer unit & Key board tray with telescopic arrangement & CPU base resting on foot rest . 18 mm th MR grade ply modesty panel with fixing blue glass. All external surfaces to be finished with 1 mm thick laminate and internal surface finished with 0.8 mm of approved shade and make. including powder coated fittings like sliding channels, for key board & drawers, medium duty hinges for shutter, cable manager. S.S. handles in approved design and size and locks wherever directed in approved make. All exposed plywood edges to be finished with 6mm th. Teak wood beading with french polish in approved shade and necessary locks to shutters etc. complete in all respects.	1	No.		
12	<b>Low height &amp; Full height storage with laminate finish:</b> Providing & fixing in position 400mm deep low/full height storage made of 18/19mm MR grade ply at top, front and side with 12 mm MR grade ply at back, all external faces including back to be finished with 1 mm thick multi-colour laminate at outside and inside finished with 0.8 mm laminate with locking and SS handle arrangement of approved make complete with openable type shutter, beading patti etc. All exposed plywood edges to be finished with 6mm th. Teak wood beading with French polish in approved shade complete in all respect.	17	Sqm		
13	<b>Low height &amp; Full height storage with veneer finish:</b> Providing & fixing in position 400mm deep low/full height storage made of 18/19mm MR grade ply at top, front and side with 12 mm MR grade ply at back, all external faces including back to be finished with 4mm thk approved veneer finished with melamine polish and inside finished with 0.8 mm laminate with locking and SS handle arrangement of approved make complete with openable type shutter, beading patti etc. All exposed plywood edges to be finished with 6mm th. Teak wood beading with French polish in approved shade complete in all respect.	3	Sqm		
14	<b>Full height glazed/Partly glazed / partly panelled partition with plywood and laminate</b> : Providing and fixing in position partly glazed & partly panelled partition made of 50 mm x 50mm x 1.2mm medium duty aluminium hollow square pipes framed at 0.60 m. to 0.45 m c/c both ways covered with 6 mm MR grade ply and 1mm multi-colour laminate of approved shade and make with 6 mm thick glass panel with etching as per design and / or necessary beading patti including 3 coats of french polishing including door shutters as per architectural design with heavy duty hinges handles / handles / locks etc. of approved make.	27	Sqm		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
15	<b>Full height glazed/Partly glazed / partly panelled partition with plywood and one side laminate one side veneer</b> : Providing and fixing in position partly glazed & partly panelled partition made of 50 mm x 50mm x 1.2mm medium duty aluminium hollow square pipes framed at 0.60 m. to 0.45 m c/c both ways covered with 6 mm MR grade ply and 1mm multi-colour laminate of approved shade at one side and finished in 4mm thk approved veneer finished with melamine polish to other side and 8 mm mm thick glass panel with etching as per design and / or necessary beading patti including 3 coats of french polishing including door shutters as per architectural design with heavy duty hinges handles / handles / locks etc. of approved make.	20	Sqm		
16	<b>Providing and fixing side table Size 900x400x750</b> mm made of 18/19 mm thick ply for all top, support and side with 6 mm thick ply at back externally finished with 1.0 mm thick laminate and All internal surfaces to be finished in approved 0.8mm thk laminate , both of approved make including brush finish S S handles, shutters , hinges with necessary teak wood beading including three coats of french polish to teak wood member and necessary locks to shutters etc. all required surface	4	No		
17	<b>Providing and fixing side table Size 1050x400x750</b> mm made of 18/19 mm thick ply for all top, support and side with 6 mm thick ply at back externally finished with 4.0 mm thick veneer and All internal surfaces to be finished in approved 0.8mm thk laminate , both of approved make including brush finish S S handles, shutters , hinges with necessary teak wood beading including three coats of french polish to teak wood member and necessary locks to shutters etc. all required surface	1	No		
19	<b>Cheque Writing desk</b> : Providing & fixing writing desk out of 19mm th.MR grade ply & 1 mm th. Laminate complete. Size 3'-0" x 1'-6"	1	No		
20	<b>Notice board:</b> Providing & fixing notice board with approved upholstery. Size 3'-0" x 1'-6"	1	No		
21	<b>Vertical blinds</b> : Providing & fixing in position 3" / 4" wide vertical blinds of approved make (Vista / Aerolux) and shade with all accessories and necessary fittings etc.	20	Sq M		
22	Providing and fixing <b>counter type desk</b> made of 18/19 mm thick ply for top , sides, with a cabinet with a drawer & shutter finished with 4 mm thick veneer to outer facae and 0.8 mm laminate inside, as per specifications including provision for CPU base and footrest	1.2	Rmt		
23	Providing Chairs of approved quality and make				
a	BM Chair ( basic cost Rs. 5000 )	1	No		

S.NO.	PARTICULARS	QTY	UNIT	RATE	AMOUNT
b	Staff chair ( basic cost Rs. 3500)	12	No		
c	Visitor chair ( basic cost Rs. 3000)	10	No		
24	Providing & fixing Panelling in out of 12 mm thick ply and 1.0 mm thick laminate with aluminium frame 50mmx25mmx1.2 mm in walls with screws and finished with approved shade and make to column with accessories and as per Bank engineer's instructions etc. complete	25	sq m		
25	Providing and fixing MDF jali work on walls/columns of approved design with high gloss paints	6	sq m		
26	Providing and fixing M S Self locking drawer of size 400*700*740 mm with tw self locking drawers etc complete as per specifications.	6	No		
27	Providing and fixing frosted film of 3 M/ LG make of approved design pattern, shade and colour to glass panels.	5	Sqm		
28	Providing and fixing panelling on External walls and for External Rolling Shutters boxing. Framing shall consist of Both ways horizontally and vertically on the wall/column with Aluminium Sections of 50mmx25mmx1.2mm as directed by Bank /Architect. This framing would be covered with 6mm thk. Comm. Ply (In case of wooden frames), finished with 3mm thick exterior grade multi-coloured "Aluminium Composite Panel". The rate shall be inclusive of necessary scaffolding, cut-outs, fixtures and fittings, sealant etc. complete.	10	Sqm		

	<b>S U M M A R Y :</b>		
	<b>Total of Interior Work</b>	<b>Rs.</b>	
	<b>Less discount (if any)</b>	<b>Rs.</b>	
	<b>Total cost of work Tendered</b>	<b>Rs.</b>	
	<b>Add SGST @ 9%</b>	<b>Rs.</b>	
	<b>Add CGST @ 9%</b>	<b>Rs.</b>	
	<b>FINAL AMOUNT INCLUDING GST</b>	<b>Rs.</b>	

**Total Amount**  
**Rupees in words:** \_\_\_\_\_

\_\_\_\_\_  
**Signature & Seal of Contractor**

**Date:** \_\_\_\_\_