

Sealed bid for the strong room construction in the first floor of KUOC branch					
Sl. No	Description	Qty	Unit	Rate	Amount
1	DISMANTLING OF BRICK WORK				
a	Dismantling of brick wall carefully by using chiesel to cut & making good wall edges with 1: 4 cement plaster including removal of debris from site	8	Cum		
b	Dismantling of RCC sunshade and lintel by using chiesel to cut & making good wall edges with 1: 4 cement plaster including removal of debris from site	0.9	Cum		
2	BRICK WORK				
	Brick work in cement mortar 1:6 using 8' concrete solid block of approved quality for super structure including curing and hire charges for scaffolding etc., complete.	3	Cum		
3	PLASTERING				
	Providing cement plaster on to brick /RCC walls Plastering with C.M 1:4, 12mm thick on both sides or as per site conditions . The rate shall be inclusive of any scaffolding required curring etc.. complete	140	Sqm		
4	RCC WALLS /RCC WORK				
	Constructing RCC wall, sunshade,lintel in 1:1.5:3 mix (M20) concrete of required thockness as per the structural design. All RCC works should be machine mixed and vibrated , clear cover provided for reinforcement the rate shall be inclusive of any scaffolding required curring etc.. complete	20	Cum		
5	WORKS				
a	Providing and laying structural steel reinforcement as per the structural details for the slabs beams, walls, etc. including shuttering , binding etc complete in all respect 12mm dia to steel at 150mm c/c both ways and both faces of wall (Aformation of reinforcement mat of 150mm x 150mm on either face of the wall to be obtained) The reinforcement shall be staggered in such a manner that any view taken at right angles to the mat formation would show reinforcement at every 75mm centre to centre.	2200	kg		

b	Providing and fixing ceiling may be fortified with M S Grills consisting of 20mm rods spaced 75mm centre to centre in angle iron frame work	1400	kg		
6	PAINTING				
a	Finishing the new cement plastered wall with 1coat of primer and painted with 2 coat of plastic emulsion paint after cleaning the surface	140	Sq m		
b	Finishing the door and Grill with 1coat of primer and painted with 2 coat of Enamel paint after cleaning the surface	20	Sq m		
7	FLOORING				
	Providing and laying vitrified floor tiles of size more than 600x600 mm (thickness to be specified by the manufacturer) of 1st quality of approved make in all colours, shades, laid on 20 mm thick Cement Mortar 1:4 including pointing the joints with white cement and matching pigments etc., complete (Lowest retail price not less than Rs. 600/m2) Make: NITCO, KAJARIA, ORIENT, SOMANY, JOHNSON.	180	Sq m		
8	Supply and fixing additional MS rod for existing 7 Nos of wondows including enamel painting	20	Sq m		
9	Supply and fixing of collapsible gate , one coat primer and 2 coats enamel paint including materials and labour charges etc complete.	3.5	Sq m		
	Total				
	GST@ 18% of				
	Grand Total				