

TENDER NO	BHU202001028
DATE	24.01.2020



SBI INFRA MANAGEMENT SOLUTIONS PVT. LTD.

(WHOLLY OWNED SUBSIDIARY OF SBI)

CIRCLE OFFICE

SBI Local Head Office, 4th Floor, III/1 Pandit Jawaharlal Nehru Marg,
Bhubaneswar- 751001

TENDER DOCUMENT FOR
AIR-CONDITIONING WORKS AT SBI ANANDAPUR BRANCH
(KEONJHAR RBO)

Price Bid (Part-2)

THROUGH E-TENDER

Manufacturers / approved dealers of (Daikin, Carrier, Blue Star, Mitsubishi Heavy & Mitsubishi Electric, Toshiba, Trane, O-General, LG, Voltas and Hitachi) are eligible to apply. Proof of dealership to be submitted by Vendor/Dealers

LETTER OF AUTHORISATION FROM MANUFACTURER TO PARTICIPATE IN THIS TENDER SHOULD BE ENCLOSED

Note: Firm should possess valid digital signature for this e-tender.

Vendor has to provide their E- MAIL id, Contact No & GSTIN No:

Manufacturers / approved dealer Name:

Email:

Contact No:

GSTIN No:

Last date & time of submission of online Tender: 04.02.2020 upto 3:00 PM

Sr. No	Description	Unit	Qty	Rate (in Rs)	Amount (In Rs)
	PART A: HIGH SIDE WORKS				
1	Supply of ceiling suspended Cassette type Split Air-conditioning unit 3.0 Tr capacity , four- way one indoor unit, one outdoor unit having refrigerant with single Reciprocating/Scroll compressor, Thermo sensor temperature control, timer setting, Auto air swing, Multifunction cordless remote control including topping of eco-friendly coolant	Nos	5		
2	Supply and fixing of Copper pipe line with good quality high density PU foam insulation pipe covering with flexible PVC pipe all complete as per standard specification and practice and instruction of Engineer-in charge as per site conditions, with proper saddling (S.S Saddle) on wall / terrace including making good the damages with cement mortar 1:2:4 on walls /floor with similar finish. Copper line sizes for cassette type 3 Tr A/C (Liquid line & Suction line of suitable size	mtr	80		
3	Laying control FRLS copper wire of 4x2.5 sq mm size pulled through rigid FR/FRLS PVC conduits of 20mm Dia 1.5 mm thick from outdoor unit to indoor unit as required to complete the work in all respect	mtr	90		
4	Supply and fixing ISI mark PVC pipe 25mm dia with elbow, tee socket for condensate water drainage line with nitrle insulation Make: Supreme/National/Prince or equivalent.	mtr	75		
5	Supply and fixing of M.S stand wall/ floor mounting brackets suitable for holding the outdoor units structure made of M.S angles for installation of outdoor unit with anti-vibration pad including grouting on wall /floor etc as may be required depending upon site condition and as per the instruction. Grouting to be done by cutting necessary holes in wall and grouting with M-12 anchor fasteners/ cement concrete 1:2:4 and making good the damages with similar finish, two coats of synthetic enamel paint over a coat of metal primer.	nos	05		
6	Installation, testing and commissioning of 3 tr cassette AC units including gas top up etc	Nos	5		
7	Air conditioning related civil works like making opening in wall for copper pipe/drain pipe etc and finishing it neatly with cement work and as per site requirement	LS	LS		

					Total (A)
1	Buy back of existing 1.5 TR split ac unit	08	nos		
					Total (B)
					Grand Total (A- B) excluding GST
	Total Amount in Word..... ...				

	NOTES:
1	The quoted rate should be inclusive of materials, labour, wages, fixtures, transportation, installation, all taxes (excluding GST), wastage's, Octroi, Insurance, machinery, temporary works such as scaffolding, cleaning, overheads, profit, statutory expenses, incidental charges and all related expenses to complete the work. GST will be paid as per prevailing rate
2	The contractor should depute one Person at Site from Start of Work to Finish.
3	The contractor should work according to the final layout and in close co-ordination with interior and electrical Work. As work to carried out in existing office premises so utmost care to be taken while executing the work. The SBIIMS/Bank has discretion to drop any of the items (low side works) from the scope of work at the time of execution and as per the site requirements. Vendor has to take the confirmation from before placing the final order.