

**SBI FORTUNE TOWER BRANCH, BHUBANESWAR****INTERIOR FURNISHIN WORKS PRICE BID****TENDER ID: BHU201909034****Date: 28.09.2019**

SI No	Item Description	Unit	Qty	Rate	Amount
1	Single Window Counter - Repair				
	Providing and fixing necessary hardwares such as channels, locks, handles, hinges, keyboard trays, sliding channels etc, as per the site condition. Design and detail of the counters shall be as per Bank's new uniform colour, layout & elevation policy, with curvature in front made of flexi ply and supporting structure in 12 mm ply MR grade. Scrapping or making the existing surface rough. Providing and fixing 4mm thick MDF board on the existing partition/door/table top or side etc., with necessary adhesive and nails/screws, hardwares etc. Thereafter, providing and fixing 1mm thick laminate of approved shade & colour, complete in all respect as per the direction of EIC. Polishing the beading etc, as per the site condition to match with the new ambience policy of the Bank. All unexposed surfaces of the table/counters/ shelves to be painted with synthetic enamel paint/ fixing 0.8 mm thick laminate, as per the site condition.	Nos	3		
2	Work-station for Officer/staff with side credenza				
	Repair of BM/Officer table including side credenza irrespective of dimension				
	Providing and fixing necessary hardwares such as channels, locks, handles, hinges, keyboard trays, sliding channels etc, as per the site condition. Remodeling the table as per Bank's new uniform colour, layout & elevation policy. Scrapping or making the existing surface rough. Providing and fixing 4mm thick MDF board on the existing partition/door/table top or side etc., with necessary adhesive and nails/screws, hardwares etc. Thereafter, providing and fixing 1mm thick laminate of approved shade & colour, complete in all respect as per the direction of EIC. Polishing the beading etc, as per the site condition to match with the new ambience policy of the Bank. All unexposed surfaces of the table/counters/ shelves to be painted with synthetic enamel paint/ fixing 0.8 mm thick laminate, as per the site condition.	Nos	10		
3	Partition work (Semi Glazed/Solid- Full/Low Height)				

a	Providing and Erecting in position low/ full height (upto ceiling) partitions to be made out of 50 mm X 50 mm X 1.5mm thick Aluminum Tubular section frame work 600 mm c/c bothways (Vertical & Horizontal) fixed with 50 mm X 50 mm X 2.5mm thick Aluminum Angle Cleats with Pan Headed Screws covered with 9mm thick MR PLY on both sides and ply fixed with Flat Headed Metal Screws .The aluminum members of partition shall rigidly fixed to the existing Ceiling /Floors / Beams & Side Walls, whichever is applicable & as directed, the alternate members and corner members fixed upto existing Slab, Beams, whichever applicable. The glass panel shall be 8mm thick (saint gobin or eqv.) duly supported by teak wood lipping and melamine polished. All exposed surfaces of the partition shall have approved brand and shade 1.0mm thick laminate from both sides as directed complete. The necessary openings in the partitions shall be provided for A.C. Grill, Electrical Conduits, Electrical Switches, A.C. Opening, Electric Fixtures and Fittings etc. complete as per requirements/instructions of the Architect / Engineer.	Sqm	20		
b	Scrapping or making the existing surfce rough. Providing and fixing 4mm thick MDF board on the existing partition/door/table top or side etc., with necessary adhesive and nails/screws, hardwares etc. Thereafter, providing and fixing 1mm thick laminate of approved shade & colour, complete in all respect as per the direction of EIC. Polishing the beading etc, as per the site condition to match with the new ambience policy of the Bank.	sqm	15		
c	Removing and resizing the 12mm glass of low height partition or counters and fixing the same with S.S D bracket of size 32mm etc, as per the site condition.	Sqm	3		
d	Providing, making and fixing in position new 12mm thick toughened clear float glass in the front side/ transcation side of half height partitions of Single Window Counters of appropriate size . All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost	Sqm	8.5		
4	Etching Film				
	Providing and fixing 3m etching film on glass partitions as per approved pattern or design	Sqm	25		
5	Doors				
a	Flap doors: Proving and fixing flap door shutter made out of 50mm x 75mm wood sections for frame work 6mm ply fixed on both sides with 1mm laminate including all hardware fittings of S.S. finish, door stopper, door buffer, auto locking SS Knob , 2 Nos. SS 2 ball-bearing hinges, slide bolt all complete as per drawing, design, specification & direction of Engineer-in-charge. The rate shall include cost of all materials, labour, taxes, T&P, transportation, royalties etc.	Sqm	3		
6	Fixing of solid acrylic surface				
	Supplying, Fabrication and Installation of Dupont-Corian/Merino solid surface of 6 mm thk of approved shade. Applied on table Top, Sides and any where wall, Logo etc in place of 1mm thick laminate. The edges to be joined should be straight, smooth and clean. Joints should only be made with joint Adhesive for Dupont Corian. All corners of a cutout must be rounded to 5mm radius and the edges smoothed, both on top & bottom, all around a cutout. "L" & "U" shaped corners need smooth 5mm	Sqm	10		
8	Storage Cabinet				
a	Providing and fixing openable or sliding shutter storage units at any hight and depth of 450 mm cabinet having minimum 2 filing cabinets made out of 19 mm thk. MR block board. All exposed surfaces shall be cladded with 1 mm thick s laminates of approved make and shade except edges . Edges which shall be covered with 1mm thk PVC lipping as directed by the Engineer-in-charge and Cabinet Top is to be provided with 1mm thick laminate. All un-exposed surfaces shall be cladded with 0.7 mm thick	Sqm	14		
b	Scrapping or making the existing surfce rough. Providing and fixing 4mm thick MDF board on the existing storage unit top or side etc (exposed surface)., with necessary adhesive and nails/screws, hardwares etc. Thereafter, providing and fixing 1mm thick laminate of approved shade & colour, complete in all respect as per the direction of EIC. Polishing the beading etc, as per the site condition to match with the new ambience policy of the Bank.	Sqm	9		
9	Vertical Blinds				
	Providing & fixing vertical blinds of approve pattern and shade of Vista Leveller / Mac/equivalent as approved of 100 mm size including nylon twisted cords, ladder cords, powder coated aluminium top & bottom rail to windows/ partitions etc. cost includes all materials, labour, tax, lead, T&P etc. complete in all respects as per the direction of Bank's Engineer.	Sqm	12.5		
10	False Ceiling Gypsum				

a	Providing & fixing at site plain gypsum board stepped/ flush false ceiling as per pattern & design made from 12.5mm thk paper reinforced gypboard sheets fixed with mainframe channels 80mm x 26mm x 0.5mm, every 450mm c/c or as mentioned in drawing intermediate channels 15mm x 45mm x 0.9mm at every 1220mm c/c with perimeter channel 20mm x 26mm x 0.5mm all along the wall shall be provided. The whole system to be suspended with strap bolts as recommended using rawl plugs 12.5mm dia. x 35mm long, with 6mm dia bolt & soffit cleat 27mm x 37mm x 25mm x 1.6mm thk. Gypboards to be screw fixed to the above framework using 25 mm dry wall screws. Provisions of melamine polished white beach wood moulding at wall / partition joints. Arrangements are to be made to accommodate light fixtures by forming recessed channels etc., wherever directed. Depressions, nails & screws, jointing & finishing etc., shall be done with jointing compound & paper tape. Ceiling to be leveled & free from cracks including fixing GI perimeter to hold light fittings. Item to be completed in all respect to the Architect's approval. Provision of Opening (openable) min 4 nos(for maintenance purpose) in ceiling as per site conditions are to be done with necessary timber frame work tied with perimeter channel properly such as to match the remaining area of ceiling by leveling perfectly complete in all respect. This rate includes cost of all materials, labours, royalty,taxes, lead & lift to the place of work& also the cost of all fittings, (Measurements shall be taken for flat surface)	Sqm	40		
b	Gyp False Ceiling Repair Repairing Gypsum board false ceiling & if required fixing gyp. board made from 12.5 mm thick paper reinforced gypsum board sheets the Gypboard should be fixed to G.I. grid with 25 mm long Drawali Screws. The 'Gypboard ' to be used should be 12.5mm thick tapered edge boards. The boards should Be taped and filled from underside to give smooth, seamless ceiling. The rate should include necessary additional ceiling sections and intermediate channels openings for light fixtures	Sqm	20		
11	Floor Spring				
	Providing and fixing floor spring of Godrej/ Dorma two speed in floors for fixing flush doors. Necessary pivot shall be provided at bottom and top so that the flush door shall be operated. The cost includes cutting and making the good of the floor etc complete as directed.	Nos	1.00		
12	Providing and fixing door closure two speed of Godrej/Dorma/Ebco as approved with all accessories to the doors.	Nos	2.00		
13	Emulsion Paint : Applying Roller Finishing the wall surface with two or more coat of wall primer followed by two or more coats of plastic emulsion paints of asian or equiv of berger/ ICI/ with approved shade and colour. Cost also include touch up finishing to the wall surface with putty of Birla/ Asian/Berger to make the surface in line and level.	Sqm	300.00		
15	Miscllaneous Work				
a	The contractor to quote for repair work as required to the cabinets/storage units as per site condition scope of work includes: replacement/ refixing of channels, locks handles and shifting of Counters/Tables/Work Stations/and Other movable furniture items as directed by EIC within branch premises labour charges.	Job	1.00		
b	Contractor to quote rate for catering away debris or any unused/ unnecessary furniture items from Bank's premises to outside municipal dumping yard , including cost for the buy back items	Job	1.00		
16	Glass Cabinet (approx size 6' x 2' x 1'6") : openable storage units of any height and depth of 450 mm cabinet having selves vertical 450 to 600 mm spacing made out of 8 mm thk glass in approved pattern and edge polished .The sides bottom and top of cabinet made of 19 mm thk MR block board. All exposed surfaces shall be clad with 1 mm thick s laminates of approved make . All un-exposed surfaces shall be clad with 0.8 mm thick laminate of approved make and shade storage cabinet should be complete in all respect as per the direction of Engineer-in-charge including all hardware and locking arrangements. The rate shall include cost of all materials, labour, taxes, T&P, transportation, royalties etc.	Sqm	1.00		
17	Providing and applying Melamine polish of approved make quality & shade as per engineer in charge direction on wooden or metal surface.the rate shall be include scrapping , levelling & preparing the surface	Sqm	50.00		
18	Wall panelling : Providing and fixing aluminum frame 25mmx50mmx1.20mm with a grid of 600mmx600mm duly fixed with screws to the walls and finished with 6mm thick thick ply MR grade and and finished with 1mm thick laminate of approved colour and shade.	Sqm	5.00		
19	P & F wall mounted running table of depth 600 mm and upto height 750 mm in 19 mm thk MR ply of approved brand for table & top sides with necessary frame work made of sal wood / aluminum tubular section for fixing table in position & finished with 1mm laminate on exposed surface and 0.8 mm laminate at interior surface. Cost also include one single drawer unit per 1500 mm length of table.	rmt	3.00		
20	P & F kiosk size 3'3" x 3' made of 19 mm MR ply of approved design and pattern as directed by EIC finished with 1 mm laminate and rate is inclusive of keyboard tray made of 12mm thk MR grade ply	Each	1.00		
21	P & F dorma/haflle/ozone make heavy duty sliding profile of PT standard fitting U shaped aluminum powder coated rails and EPDM gaskets including cuttings , making holes necessary hardware and fittings for the existing 12 mm thk toughened glass doors. The railing profile to be fitted to RCC ceiling/Beam. The rates are also incl of removing and refixing the existing 12mm glass doors.	Rmt	6.00		