

**BOQ AND SPECIFICATIONS FOR INTERIOR & FURNISHING OF GORBI BRANCH, RBO-6, REWA**

Sl.No	Description of Items	Unit	Qty	Rate	Amount
1	<b>INDEPENDENT TYPE STANDARD COUNTER:</b>				
	Providing, fabricating and fixing at site and in position independent type modern single window counters as per detailed drawing and or as directed at site, made up of 19.00 mm thick approved make commercial MR grade ply. The single window counter shall have 32" wide writing/work top as per drawing /site details including providing drawer unit of standard size with telescopic channels of Ebco, Godrej, Hetteich or equivalent approved make as directed by Bank/ Architect. Each counters shall be approx 1500 mm wide or as per site conditions and approved layout plan and consisting of 19 mm thick commercial MR grade ply specified makes. The front side (Public side) of the counters shall be consisting of 19 mm thk commercial ply MR grade of approved makes. All external faces of the counter including front face of the drawer cum cupboard unit etc. shall be finished with 1.0 mm plain, high gloss lamination SF Finish and internal faces with 0.8mm laminate as per sample approved by bank. The public side of the counter shall have skirting 100.00mm high finished with approved quality and shade laminate. The rate should include providing and fixing seasoned teak wood beading of size 19 mm x 6 mm or as required to all exposed edges of the ply. Each cupboard/drawer shall be provided with approved quality handles/knobs and Godrej / Doorset make approved quality cupboard auto locks. The rate should include providing and fixing seasoned wood foot rest to each counter complete as per the layout plan and as directed by Bank's Engineer/ Architect complete.	Rmt	6.00		
2	<b>12MM THICK ETCHED GLASS TO SINGLE WINDOWS COUNTERS</b>				
	Providing and fixing 12 mm thick ATUL/SAINTGOBIN float glass with polished edges and etching as per approved pattern fixed suitably to the public side and transaction top of counters including cutting suitable size transaction/ conversation window, finishing the supports in matching 1.00 mm plain and metallic high gloss laminate complete as directed at site.	Sqmt	10.00		
2.a	<b>Toughened Glass Dividers For Single Window Counters and Front Partition Glazing / ATM :</b>				
	Providing, making and fixing in position 12mm thick toughened clear float glass in the front side of half height partitions of Single Window Counters of approximate size 1450mm x 400mm - 100mm in tapered shape. Also to provide toughned glass iat the entrance as partiton in Branch & at ATM. All the edges of the glass to be polished for a smooth finish and the glass is to be embedded in half partitions/ floor/ wall and fixed with " D " brackets/ SS fittings as required. The glass bottom to be min. 75 mm above tile surface at SWO and at floor level at partition. Etching of glass with film to be done as directed ( measured separately). The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.	Sqmt	18.00		
3	<b>LOW HEIGHT PARTITIONS</b>				
	Providing and fixing in position 1250/1200 mm height double skin wooden partition made out of Frame work to be 50X50X1.60mm thick aluminum section weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways(Horizontal/Vertical) or as directed. The spacing of the members may vary either side depending upon the site conditions as per approval of Bank Engineer. The partition shall be provided 12mm thick exterior grade HDF/MDF board to be fixed over the frame work on both side.approved make on both sides finished with 1.0mm plain high gloss laminate of approved makes in combination and shade up to about 750mm height. The remaining upper portions of the partitions shall have 12 mm thick plain float glass with etching and polished edges of SAINTGOBIN/MODI/TRIVENI. Rate inclusive of beadings etc. complete in all respects.	Sqmt	10.00		
4	<b>FULL HEIGHT PARTITIONS</b>				
	Providing and fixing full height partly double skin wooden partitions made out of of Frame work to be 50X50X1.60mm thick aluminum section weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways(Horizontal/Vertical) or as directed. Floor or slab with 65 to 75 mm long screw. The vertical GI member shall be placed at 450 to 500 mm center to center and horizontal members to be placed at 600 mm c/c or as directed by the Bank's Engineer as per site conditions with necessary grooves and cuts etc. including anti-termites treatment to all wooden members.				
	The lower and upper panel should be provided with The partition shall be provided 12mm thick exterior grade HDF/MDF board to be fixed over the frame work on both side.approved make on both sides finished with 1.00 mm thick approved quality plain and metallic high gloss laminate as per approved design/pattern. The middle panel shall be provided 8mm thick float glass of approved make with necessary etching/frosting as per design. Rate inclusive of material, transportation, loading/unloading labor, tools etc. for all heights complete in all respects. The rate should also include the following:-				

	(a) Applying anti-termite and anti- borer paint to wooden frame work wherever directed				
	(b) Applying three or more coats of melamine polish /painting of approved quality and shade to have desired, finish to all exposed surface of teak wood members beadings, board etc. including preparing of surface by sand papering, applying putty etc. complete	Sqmt	10.00		
4.a	<b>12 mm Additional Plywood framing/ Boxing :</b>				
	Providing and fixing additional ply framing/boxing in 12 mm commercial ply (and/or 8mm commercial ply if required) for fixing of softboards/ whiteboards etc on wall surfaces or existing single/double skin partitions or boxing on walls/columns including levelling on walls, and in double thickness for small partitions on tables, etc. The framing shall be finished with 1mm thick plain or Textured Laminates (up to Rs 350/- per sqm) (on one exposed surface) of approved shades including inlay etc if required and as directed along back credenza as required as per fixing pattern to achieve overall flush appearance. The framing shall include the provision of switchboard, lan cabling, telephone wiring etc. The cost shall also include providing and applying polish/paint, etc. complete. ..contd..				
	..contd.. to match similar material in the surrounds, on all exposed wooden surfaces including lippings, laminated surfaces etc. wherever instructed of approved shade and finish including thorough cleaning, rubbing and surface preparation, application of primer, sealers, colour tone, and including polish if required. The measurement shall include only the framed areas and softboard/ whiteboard/glass etc. shall not be included in either the area or the rate. cost shall however include all lippings, mouldings, beadings etc required for the proper execution of work.	Sqmt	15.00		
5	<b>Providing in position Officer's table of sizes mentioned hereinafter.</b> It shall consists of 19mm thick block board/18 mm ply of approved make on the top finished with 1.00 mm approved quality plain and metallic high gloss lamination as per approved sample design. The writing top shall be supported over two vertical supports made out of 19 mm thick block board/18 mm ply of above specified makes with lamination as above. The supports shall be connected together with 19 mm thick board laminated front as per approval and design/detail.				
	The table shall be complete with one drawer unit having a drawer at top and cupboard with shelves at lower, necessary hardware's, sliding channel, knobs, godrej / doorset multipurpose locks etc. The rate should include providing and fixing suitable foot rest, providing 0.8mm approved quality white laminate to all internal faces and applying 3 coats of melamine spray polishing/ painting etc. to the moldings/ beadings, providing plastic shoes complete. The rate should include providing and fixing seasoned teak wood beading of size 19mm X 5mm or as required to all exposed edges the block board as desired by the bank.				
	(i) Table of size 7'6"0" X 3'0" X 2'6" height with table top and front to be in curved shape as per detailed drawing with 12mm thick bevelled/ polished edges Glass top.	No.	3.00		
	(ii) Table of size 5'0" X 2'6" X 2'6" ht. As per detailed drawing.				
	(iii) Table of size 4'6" X 2'6" X 3' ht. as per detailed drawing for Grahak Mitra with front curve design and 12 mm glass with SS Studs etc. direction.				
6	<b>Providing in position side tables of sizes mentioned hereinafter.</b> It shall consist of 19mm thick board of approved make on top , middle shelf, bottom and sides as per detailed drawing. The top and bottom shall be laminated with 1.0 mm thick approved quality and shade plain and metallic high gloss laminate as per design detail. The cabinet shall be covered from back with 6.0 mm ply, providing drawers at the top and cupboards with laminated block board shutter in remaining lower partition with necessary hardware, knob, telescopic sliding channel, godrej lock etc. complete as per sample approved. The rate should include providing 0.8mm white laminate to all internal surfaces and applying 3 coats of melamine polishing/painting to beadings/moldings etc., providing plastic shoes and also providing and fixing 19 X 4 mm suitable wood beading to all exposed edges to all the block boards etc. as per Bank's approval.				
	(a) Side rack of size 4'0" X 1'6" X 2'6"				
	(b) L-Support side rack of size 4'0" X 1'6" X 2'6" one end tied to Table as per drawing.	No	3.00		
	(c)L-Support side rack of size 3'6" X 1'6" X 2'6" for other officers.				
	(d) L-Support side rack of size 3'0" X 1'6" X 2'6" one end tied to Table as per drawing.				
7	<b>Providing and fixing 6 lever Godrej</b> night latch lock with non-interchangeable key to doors of cash department. Rate inclusive of materials, transportation, unloading/loading labor,tools and tackles up to any lead and lift complete in all respects.	No.	4.00		

8	<b>Providing and fixing voucher writing table</b> with about 5 voucher slots/pockets as per the detail drawing consisting of 19 mm commercial block board /MR ply of approved makes duly laminated using 1.0mm plain and metallic high gloss laminate approved by the bank having slanting top and waste paper box with dumping and cleaning window, in the lower supporting column including polishing/enamel painting etc. complete.	No.	1.00		
9	<b>Providing and fixing wall/column panneling</b> made out of 18 mm double ply / seasoned second class teak wood framing in vertical and horizontal sections placed at 45 c/c both ways or as per site conditions finished with 8mm MR ply grade and 1.0mm thick approved quality and shade plain and metallic high gloss laminate. The rate to include providing 6mm thick seasoned teak wood beading/lamination to exposed edges wherever required complete.	Sqmt	95.00		
10	<b>-----do----- as above but in 4 to 6 wide</b> bands, doors windows jambs, lintel etc. made out of 19 mm block board/18 mm MR grade ply finished with color contrast 1.0 mm high gloss laminate. TW lipping to edges completed as directed at site.	Sqmt	5.00		
11	<b>Providing and fixing 35/40 mm thick solid core flush door shutters of</b> CORBAT/REGAL/GOLDEN FOREST or per sample approved by the Bank finished with approved quality and shade 1.0mm thick lamination plain & metallic high gloss on both side of the shutter with matching wood beading duly melamine polished. The rate should include the following:-				
	(i) Providing 8 mm thick float glass of MODIGUARD/SAINTGOBIN or other equivalent make approved by the Bank with necessary etching/frosting as per design fixed in position with 40x20mm seasoned teak wood suitable beadings.				
	(ii) Providing 100mm high skirting with 1.0mm approved quality high gloss lamination on both sides.				
	(iii) Door shall be hinged on 4 nos. 125 X 30 X 3 stainless steel bearing hinges, providing door stopper, door handles 200mm long. Doorset mortised lock tower bolt etc. as per samples approved and as per site requirements.	Sqmt	5.00		
12	<b>Providing and fixing suspended false ceiling made out of 12.0 mm (apprx.) thick Gypsum Plaster Boards of Indian Gypsum or equivalent made G.I</b> standard section framework in the pattern and design directed by the Bank Engineer. The G.I. Section frame work shall be tied to the roof and walls with the anchor fastener screws/bolts of appropriate size recommended by the Indian Gypsum. The boards shall be fixed to the frame work with the screws and the joints shall be flushed and finished with requisite jointing compounds paper tapes etc. Rates includes execution of works in different levels/offsets etc. The surface shall be finished evenly by applying putty,sand papering,applying primer evenly complete. Rate inclusive of materials transportation, loading/unloading labor, tools and tackles up to any lead and lift complete in all respects.	Sqmt	70.00		
13	<b>Providing and fixing 600 mm X 600 mm size mineral fibers tiles acoustical ceiling</b> with tegular edge as approved by the Bank of 15 mm thick RH 90 or equivalent approved make board tiles fixed in position on STICHD TRULOK/24 mm PRELUDE exposed system hot dipped galvanized steel with white precooked exposed can and the frame shall comprise of:-				
	24mmX38mm- Main Tee of 3600mm				
	24mmX30mm-Cross Tee Of 1200mm				
	24mmX25mm-Cross Tee of 600mm				
	22mmX22mm-Wall Angle of 3000mm length				
	The G.I. Wall angle to be fixed the G.I. Wall angle to be fixed along the perimeter fixed with screws/rawl plugs. The G.i. Main runners spaced at 1200 mm counters securely fixed to the structural soffit by approved hangers of 2.0mm GI wire pre stressed at 1200mm Max. centers. Flush fitting 1200mm long cross tee.				
	To be interlocked between main runners at 600 mm centers. The 600mm cross tees are placed between 1200mm Cross Tee (parallel to main runner) to form a 600 X 600 mm module. Extra suspension to be provided around light fixtures.	Sqmt	50.00		
	Make: ARMSTRONG				
14	<b>Low back visitors sofa without arms</b> made out of 25 mm thk block board structure finished with 4 mm thick veneer and 1.0mm lamination in combination as per sample approved with melamine polish complete. The seat size should be 21 X 21 upholstered over 4 thick high density ISI mark foam 40 density foam on back using approved quality and shade upholstery cloth costing Rs 450/mt.				
	(a) Three Seater	Nos.	1.00		
	(b) Two Seater				
	(c) Single Seater				
15	<b>Providing and fixing heavy duty DOOR CLOSURE</b> of Hardwyn / Everite make with stainless steel cover plate.	Nos.	5.00		
16	Providing and fixing in position stainless steel body with door set or approved equivalent <b>6 lever Cylindrical lock.</b>	Each	2.00		
17	<b>Providing and fixing wooden wicket gates</b> of apprx. Size 900mm X 1200 mm made out of 19mm thick block board both sides laminated with hinges, latch, double thickness at edges with painting/ polishing etc. wherever required complete	Sqmt	1.00		

18	<b>Providing and applying Birla white putty to walls</b> in proper lines and level including making grooves and preparing the surface by scraping and removing existing paint from walls, hacking etc. complete as per the direction of the Bank's Engineer.	Sqmt	540.00		
19	<b>Supplying and applying synthetic enamel paint</b> in 2 or more coats of approved shade, quality and make like Nerolac, Asain, Berger after preparations of surface properly with all labors and materials in all floors complete as per drawings, specifications and instructions of Engineer- Incharge. Rate inclusive of cost of materials,transportation, loading/ unloading, labor tools and tackles etc.	Sqmt	250.00		
20	<b>Providing and applying 3 coats of plastic emulsion paint</b> in roller finish to wall surfaces to give an even shade including necessary scaffolding etc complete as per approval of Bank Engineer	Sqmt	540.00		
21	<b>Providing and fixing in position 450 mm deep storage cabinet as directed made out of approved quality 19 mm thick MR grade borer &amp; termite resistant block board.</b> Shutter shall be of 19 mm thick block board with all hardware like 75 mm X 18 mm X 18 mm stainless steel bearing hinges, magnetic catchers, stainless steel handles, locks etc. complete as per sample approved. All internal surfaces of the cabinet including shutters and shelves to be finished with 0.8 mm thick white laminate of approved make and shade as per design. Rate to include providing 8mm thick BWP ply,providing and TW lipping to exposed edges of Block board, polishing/painting etc. complete.	Sqmt	10.00		
22	<b>Renovation of existing flush door/panelled shutters</b> by providing 6.00 mm MR grade ply and 1.00 mm laminate, TW edge lipping,polishing including necessary hardware etc. complete.	Sqmt	2.00		
23	<b>Providing and fixing 2'6" wide work top consisting of 19 mm thick VENUS or equivalent approved make block board finished with approved quality and shade laminate of GREEN/ROYAL TOUCH</b> or equivalent approved made with 19 mm thick block board supports at every 4' to 5' center to center. The rate should include providing 19 X 4 mm teak wood molded beading as per sample approved to the exposed edges of the block board and polishing/painting of all unlaminated surface of block board etc with 3 or more coats of wax polish in approved shade complete as per detailed drawing and instructions of Bank's Engineer. The rate should also include providing Tower type CPU compartment, key board drawer fixed on approved quality channels, 1 Nos. drawer 4" deep and Electrical switch board complete at every 4' length of work top as per directed.	Rmt	3.00		
24	<b>MAIN ENTRANCE DOOR:</b> Providing and fixing shutter to be made of 12 mm thick float glass with teak wood top, bottom rail and styles of section 125 X 45 mm(finished size) including Teak wood beading for fixing glass. All teak wood to be finished with melamine polish. The float glass to be etched as per approved design including etching color STATE BANK OF INDIA (SBI) logo as directed.				
	The rate should include necessary hardware's fixtures with heavy duly floor spring with stainless steel cover plate and one pivot at top, 2 Nos. 300 mm long decorative brass handles foe each shutter. The teak wood surface will be melamine polished to the satisfaction of Bank Engineer.	Sqmt	10.00		
25	Laying of <b>Etching flim on Glass-</b> Providing etching flim on glass in required design, pattern & shape wherever required and instructed.	Sqmt	10.00		
26	<b>Vertical Blinds-</b> Providing & fixing vertical blinds 100mm wide of washable synthatic material with extruded powder coated hearail housing control units spacers, runners, tilt rod with reduction gear mechanism tilt control for 180 degree Louvers made of approved fabric and colour having scratchgurd coating to be provided.	Sqmt.	15.00		
27	<b>Dismantling of existing wiremesh partitions/m.s. Grill/ false ceiling</b> and stored the same in a suitable places as per the instruction of the Branch including cleaning, shifting charges within the Branch premises etc. complete.	Job	1.00		
28	<b>Dismantling of cash, clerical counters, tables, side units etc.</b> and shifted the same in a suitable places as per the instruction of the Branch including cleaning, shifting charges within the Branch premises etc. complete.	Job	1.00		
29	<b>Dismantling of old Alluminium /Glass/ wooden partitions/ brick partition wall/flooring/sanitary fittings /water pipes</b> and shifting to a suitable place as per the instruction of the branch including shifting charges within the branch premises etc. Complete.	Job	1.00		
30	<b>Safe Dismantling of Old Plumbing works</b> including (a) safe disconnecting and removal of wash basins, taps, mixers, shower heads, hand showers, geysers, angle cocks, flexible connectors, western seats, flush tanks, and all such exposed plumbing fittings, mirrors, holders etc. (b) removal intact or in broken condition of indian seats/orissa pans , removal of concealed valves, gully and/or nahani traps, pipelines, mixers, diverters or all such concealed items causing hindrance to the new works on walls and/or floors (c)removal of all filling material, old waterproofing, including chiselling of extraneous materials, coba fillings etc so as to achieve the face of concrete slab of toilets suitable for reworking and waterproofing as required including minor repairing works like plaster etc.if required. including safe handling and removal of debris to a safe distance (ladies toilet- 5 sq.mt, gents toilet-6 sq. mt.)	No.	1.00		

31	<b>Providing &amp; fixing Jet Black Granite Staircase Treads</b> complete as per specifications with 15-18 mm thick mirror polished, machine cut jet black granite with double thick full round moulded edges and of required size. The granite treads shall be fitted with full round moulding shall be fixed with cement grout on treads and the double thick moulded edge shall be joined with araldite adhesive to the tread. The cost shall be inclusive of cutting, moulding, transportation, edge polishing, etc. complete and also providing two parallel grooves in the treads as specified.	Sqmtr.	1.00		
32	<b>Providing &amp; constructing Jet Black Granite platform for pantry and wash basin counters</b> complete as per specifications with 18-24 mm kota stone stand and kota stone or MS angle/T section supports as required and as instructed, including base stone in kota stone and fixing of 15-18 mm thick mirror polished, machine cut jet black granite with simple full round edge moulding and fascia for pantry counter and double thick edges with full round moulded edges and of required size. The granite full round moulding shall be fixed with araldite adhesive to the counter top. The cost shall be inclusive of cutting for sink, basin, taps etc. as and when required.	sqmt	1.00		
33	<b>Providing and fixing stainless steel sink</b> 1 number Nirali Make or equivalent as per approval of size approx. 18inch X 24 inch or as available per approval in platform complete including all required cutting, filling, preparation for installation, connecting waste coupling, waste pipe, adhesives/ sealers/ fillers etc.	nos	1.00		
34	<b>Providing &amp; laying matt finish Non-skid ceramic floor tiles in toilet</b> areas as per specifications of size 300X300 of make Nitco, Bell, Johnson, Somany etc, or equivalent in first quality and of design, colour and make as per approval laid over cement plaster. The joints shall be filled and finished neat with cement grout as per specifications cleaning shall be done by applying acid wash curing etc. complete at all levels.	Sqmt	5.00		
35	<b>Providing &amp; laying glazed ceramic wall tiles for dado in pantry area and on walls in toilets</b> as per specifications of size 300X600 or 300x450mm of make Nitco, Bell, Johnson, somany etc, or equivalent in first quality of design, colour and make as per approval laid and border in special/dark colours as per approval laid over fresh or existing cement plaster including surface preparation if required to the architect's satisfaction, joints to be filled and finished neat with cement grout as per specifications including cutting at traps, mitring of joints if required cleaning applying acid wash curing etc. complete at all levels.	Sqmt	6.00		
36	Providing and fixing <b>1<sup>st</sup> class premium quality, double charged vitrified tiles</b> of approved size (800x800mm or 600x600mm as directed) with water absorption less than 0.08% and conforming to IS:15622 of approved make in all colours shades of any size in floors and skirting over 20 mm thick bed of cement mortar 1:4 and jointing with grey cement slurry @3.3 kg per Sqmt, including pointing in white cement mixed with pigment of matching shade complete.	Sqmt	200.00		
37	<b>Providing and fixing in position first quality white Hindware make Wall Mounted European WC ENIGMA</b> (cat. no. 92024) or equivalent strictly upon approval with P trap, High Quality brackets as required and as integral part removing the existing pan (broken) and/or making connections of W.C. with other accessories such as flush valve inlet, outlet, anti syphonic pipe etc. (if required) complete including making chases and holes in floors and walls and repairing the same with cement mortar (1:3) plastering, tiling etc. to the architect's satisfaction.	nos	1.00		
38	Providing and fixing in position <b>Flush Valve Dual Flush Concealed Body Type</b> Jaquar make or equivalent upon approval with all WCs complete including all required connections and settings for proper functioning to the Engineer's satisfaction.	nos	1.00		
39	Providing and fixing in position <b>Angular Stop Cock with Wall Flange Jaquar make (Cat. No. FLR 5053N)</b> or equivalent upon approval complete including all required connections and settings for proper functioning to the Engineer's satisfaction.	nos	1.00		
40	<b>Providing &amp; Fixing CP finish Two Way Bib cock with wall flange Jaquar make (Cat. No. FLR 5041N) or equivalent along with Hand Shower (Health Faucet)</b> (ABS Chrome Plated) with 8mm dia and 1 M long Flexible tube and wall hook (Cat. No. ALD 573) or equivalent upon approval make and design as per approval complete including fixing and connecting and including all materials, teflon tape, cp nipples, cover plates with testing etc. complete	Set	1.00		
41	<b>Providing &amp; Fixing CP finish Pillar cock long body bib cock</b> of Jaquar make (Cat. No. FLR 5011N/ FLR 5047N) or equivalent make upon approval and design as per approval complete including fixing and connecting and including all materials, teflon tape, cp nipples, cover plates with testing etc. complete	nos	1.00		
42	<b>Providing and fixing sets of Bathroom Accessories of reputed brand and matching designs with concealed/ hidden screws strictly upon approval by engineer-in-charge.</b> The cost shall include proper and careful fixing of all sets with Galvanised countersunk screws and nylon gattis as required without damaging existing pipelines, conduits, cables, wires, switchboards or any such item concealed inside wall below the tiles. The fixing must be in proper level and at places as directed by the engineer-in-charge.				
a	S.S. Soap Dish Wall Mounted single dish	Nos	2.00		

b	S.S. Clothes Hook with 5 hooks on one plate	Nos	2.00		
c	SS Finish Toilet Paper Holder as per approval	Nos	2.00		
d	SS Napkin Holder Oval or Hook shape as approved	Nos	3.00		
43	<b>Providing and fixing in position 15mm Class 'B' G.I. Pipe line</b> Prakash Surya/ Tata or equivalent make or CPVC pipe of approved ISI branded complete with fittings Tees, Bends etc, except controls such as cocks and valves fitted and fixed to the walls with G.I. Approved clamps or buried underground including making necessary chases and holes in walls and floors or trenching etc. complete with making good or refilling including painting of pipes if required.	RM	15.00		
44	<b>Providing and fixing in position 20mm Class 'B' G.I. Pipe line</b> Prakash Surya/ Tata or equivalent make or CPVC pipe of approved ISI branded complete with fittings, Tees, Bends etc, except controls such as cocks and valves fitted and fixed to the walls with G.I. Approved clamps or buried under ground including making necessary chases and holes in walls and floors or trenching etc. complete with making good or refilling including painting of pipes if required	RM	10.00		
45	<b>Providing and fixing in position 25mm Class 'B' G.I. Pipe line</b> Prakash Surya/ Tata or equivalent make or CPVC pipe of approved ISI branded complete with fittings, Tees, Bends etc, except controls such as cocks and valves fitted and fixed to the walls with G.I. Approved clamps or buried under ground including making necessary chases and holes in walls and floors or trenching etc. complete with making good or refilling including painting of pipes if required	RM	10.00		
46	Providing and fixing brass/ gun metal <b>high pressure full way or gate valves</b> with MS handle head complete with fitting, teflon tape, testing etc.	NOS.	1.00		
47	<b>Providing and fixing 75 mm PVC pipes</b> for soil waste/rain water/drainage disposal of superior Indian make such as Kisan, Premium, Supreme, Prince or Kasta i/c jointing with rubber ring, adhesive lubricant solvent cement with PVC clips as per site requirement with testing etc. complete.	RM	10.00		
48	<b>Providing and fixing 100 mm PVC pipes for soil waste/rain water/drainage disposal</b> of superior Indian make such as Kisan, Premium, Supreme, Prince or Kasta i/c jointing with rubber ring, adhesive lubricant solvent cement with PVC clips as per site requirement with testing etc. complete.	RM	10.00		
49	<b>Providing and fixing Mirror of make modiguard/ saint gobain</b> etc or equivalent of height 1220 mm complete with flat polished edges, fitted on site on 12 mm ply base, base having wooden lipping border and finished with laminate if instructed. The mirror shall be either pasted on the ply with silicon adhesive or fitted with stud-head screws with air gap in between (minimum 6 nos average per location) or both as per approval complete to the Engineer's satisfaction.	Sq.M	2.00		
50	Providing and fixing <b>stainless steel jali (grating)</b> with or without hole for waste pipe for floor/ Nahani trap inner lining in SS.	NOS.	1.00		
51	Providing and fixing <b>PVC waste pipe</b> for wash basin and kitchen sink including PVC waste fittings complete.	NOS.	2.00		
52	<b>Providing and laying 125 mm thick Brickwork</b> in CM 1:4 including R.C.C. Band 100mm thick @ every 1 metre layer including curing etc complete (Steel reinforcement paid separately)	Sqmt	10.00		
53	<b>Providing and Laying Brick work with common burnt clay non modular bricks</b> of class designation 12.5 conforming to IS 2222 in superstructure above plinth level up to the bottom of slab in cement mortar 1:4 @ every 1 metre layer including curing etc complete ( steel reinforcement to be paid separately)	Cum	1.00		
54	Providing and placing in position 2 nos 6 mm dia <b>M.S bars at every third course of brick masonry.</b>	Kg	50.00		
55	12 mm thick <b>Plastering of walls</b> and ceiling with cement mortar 1:4	Sqmt	20.00		
56	<b>Providing and fixing premium quality white vitreous china below counter Wash Hand Basin</b> of Hindware / Jaguar / Johnson/Parriware fixed over jet black granite counter including edge moulding, CP Brass bottle Trap (Parko or equivalent approve), 32mm dia Waste Coupling (Parko/Plumber/Jaguar), Auto closing Pillar Cock (Jaguar Cat No. PRS-031), including PVC connection etc. complete. as per sample approved.	Nos.	1.00		
57	Providing and fixing 15mm dia <b>Swan type CP Bib cock</b> of Jaguar make for Kitchen sink	Nos.	1.00		
58	Aluminium Ventilator 3x2 ft incl. labour, material etc complete	No.	1.00		
59	RCC work of 1:2:4 in small lintels i/c reinforcement,	Cum	1.00		
60	Providing & fixing iron door MS iron sheet heavy duty 16SGW, iron angle frame 35X35mm and internal cross support to sheet, interlocking together their entire length & joint together at ends lock, handle, hinges with two l drop etc complete with suitable coat of red oxide paint.	Kg	250.00		

61	<b>ACP Panelling on walls</b> - Providing and fixing 3 mm thick ACP Wall Paneling to internal/external surfaces of the walls of the ATM and Branch including necessary aluminium pipe framework (50x25mm 2mm thick Al tubes @ 60cms C/C bothways) )and using approved quality double sided adhesive Tape, screwing the ACP sheet to the pipe framework including providing silicon gel filling to joints complete as directed at site. The pipes to be placed both ways at adequate spacing as per manufacturer's specifications to avoid perfectly leveled surface free from undulations etc. complete .	Sqmt	60.00		
62	<b>Providing and fixing ACP panelled Rolling shutter boxing</b> with aluminium composite panel fixed to Aluminium pipe framework placed at adequate spacing complete.	Sqmt	10.00		
63	<b>Providing and fixing of wall papers</b> as per approved make and brand on wall surfaces including Teak wood edges/corner with melamine polish and surface preparation with all material and labour complete.	Sqmt	10.00		
64	<b>Providing and fixing of green channel box</b> on the column made out of 18 mm thick commercial block board and green coloured 1mm thick laminate as per design and as directed by the Engineer Incharge.	No.	2.00		
<b>TOTAL AMOUNT (IN RS.) EXCLUDING GST*</b>					

(\*GST will be paid additionally by the Bank as applicable)

**SEAL & SIGNATURE OF CONTRACTOR/FIRM**