BOQ FOR SITC OF AIR CONDITIONERS- NEW ESTABLISHMENT OF RBO AT FATEHPUR DISTT. ALLAHABAD:

S.NO.	ITEM DESCRIPTION	Qty	Rate	Amt.
1.	Supply , installation, testing & commissioning(SITC) of 1.5TR high wall 3 star rated /maximum rating in this range, BEE rated, mounted type air conditioner, wireless remote controlled with auto restart feature complete in all respect with indoor, outdoor unit, copper condenser & copper cooling coil interconnecting piping, wiring/ installation / drain pipe etc. (Upto 3 meters length). Item should also include 4 KVA hi/lo cut off, TDR relay start stabilizer. Make of Air Conditioner: Voltas/Bluestar/Carrier/Hitachi/Daiken Make of Stabilizer: Servel/V Guard/Stambh/Inmag	03 NOs		
2	Additional refrigerant interconnecting copper piping (both) with insulation, drain pipe, wire mesh cover throughout for protection for 1.5/2.0 TR high wall ACs. Item is for interconnection piping additional to 3 meters which is included in item sl. No2.	30 Mtrs		
3.	Supply , installation, testing & commissioning(SITC) of 2 TR high wall 3 star rated /maximum rating in this range, BEE rated, mounted type air conditioner, wireless remote controlled with auto restart feature complete in all respect with indoor, outdoor unit, copper condenser & copper cooling coil interconnecting piping, wiring/ installation / drain pipe etc. (Upto 3 meters length). Item should also include 4 KVA hi/lo cut off, TDR relay start stabilizer. Make of Air Conditioner: Voltas/Bluestar/Carrier/Hitachi/Daiken Make of Stabilizer: Servel/V Guard/Stambh/Inmag	02 N0s		
4.	Suitable angle iron stand for 1.5/2 Tr. spilit AC made of minimum section 35x35x4 mm. duly painted with one coat of primer and two coats of enamel paint. The stand will have to be grouted /anchored to wall/ ledge in a safe manner to suit site conditions. (as per sl 2.)	05 Nos		

PLACE:	Signature and Seal of Bidde
DATE:	

BOQ FOR SITC OF AIR CONDITIONERS- NEW ESTABLISHMENT OF RBO AT FATEHPUR DISTT. ALLAHABAD:

5.	Electrical cabling from indoor to out door unit with suitable	60 mtrs	
	PVC copper wire for 1.5/2TR high wall ACs. Item is for		
	cabling additional to 3 meters included in item sl. 2		
TOTAL			

PLACE: Signature and Seal of Bidder

DATE: