

**Tender for Supply, Installation, Testing & Commissioning of Airconditioners at
State Bank of India - RBO V Thodupuzha, additional space on 2nd floor**

	Description	Qty	Rate(Rs)	Amount(Rs)
1a	Supply, Installation, Testing & Commissioning (SITC) of factory made air-conditioners (approved make only) having energy efficient compressors, condenser and evaporator coil, aesthetically finished indoor units, automatic temperature control, safety controls, including supply & filling of required quantity of refrigerant to maintain prescribed temperature levels as recommended by the manufacturer, cordless remote etc., complete having capacity 3.0 TR, 3-phase, 415 V, cassette type ceiling mounted . Also, the air-conditioners along with all accessories and workmanship including installation work shall conform to all mechanical and electrical safety standards as per relevant IS specifications. The equipment shall be properly earthed (connected to the earthing system of the electrical cabling of the premises) by using earthing conductors as per relevant IS code. Quoted rate is inclusive of cost of all thermal insulation (Approved makes : Voltas, Blue Star, Carrier Aircond.& Refrigeration Ltd , LG Electronics , ETA Engineering & DAIKIN having service Centres in Ernakulam and other districts of Kerala need only quote)	02 nos		
b	Same as above but 2.0 TR Cassette airconditioner, 1 phase, 230 V	01no		
c	Same as above, but 2.0 TR split airconditiner with 3 star rating, 230 Volt, 1 phase including standard length of refrigerant pipe & control cable offered by the manufacturer (tender to mention the std. Length here.....)	01no		
	Total			
	GST for the above @.....% (tenderer shall mention the rate here)			
	Total including GST (A)			

2	SITC of hard drawn copper pipe for suction & discharge for cassette ACs (measured as single unit) as required at site.	30 m		
3	SITC of soft drawn copper pipe for suction & discharge (measured as single unit) as required at site.	15m		
4	SITC of power and control cables for interconnecting indoor and out door units.	60 m		
5	SITC of PVC drain pipe	40m		
6	SITC of Heavy duty MS angle pedestal/ support for out door units for Cassette ACs	2 nos		
7	SITC of MS angle pedestal/ support for out door units for split AC	02 nos		
8	SITC of stabilizers 4KVA, 1Ph., 230v	02 no		
9	Supply & fixing of 20cm wide prefabricated and painted tray made out of 22 SWG GI sheet supported from ceiling using threaded rods to draw refrigerant piping between outer wall and condensing unit for collecting condensed water from the refrigerant pipe as required at site	20m		
	Total for items under Sl. No 2 to9			
	GST for the above (sl no. 2 to 9) @.....%. (contractor shall mention the GST rate here)			
	Total of above (including GST) (B)			
	Grand Total (including GST) (ie; A + B)			

	<p>Post warranty Annual Maintenance charges including GST (mention GST rate.....)for 2 years for the above new air-conditioners including cost of refrigerant and all other spares required for the maintenance (tenderer is requested to record here the Warranty period offered by them).</p>	<p>3TR Cass ette (x2)</p> <p>2TR Cass ette (x1)</p> <p>2TR split (x 1)</p>	<p>1st year..</p> <p>2nd year...</p> <p>1st year...</p> <p>2nd year.....</p> <p>1st year...</p> <p>2nd year.....</p>	
	<p>Total AMC charges for 2 years</p>			
	<p>GST for AMC charges @.....% (contractor shall mention the GST rate here)</p>			
	<p>Total AMC charges including GST (C)</p>			
	<p>Grand total (A + B + C)</p>			

(In Words) : Rs

)

