

**PART-A3**  
**BILLS OF QUANTITIES FOR THE PROPOSED SUPPLY AND INSTALLATIONS OF STORAGE RACKS**  
**FOR STATE BANK OF INDIA AT DOCUMENT ARCHIVAL CENTER AT FIRST FLOOR**  
**VILLAGE: ALSLAI, DIST. AHMEDABAD**  
**BILLS OF QUANTITIES**  
**( NOT TO BE FILLED BY THE BIDDER)**

Sr. No.	DESCRIPTION	Qty	Unit
	<b>STORAGE RACK AT FIRST FLOOR</b>		
<b>1</b>	<b>Supplying, providing and installing Storage Racks.</b>		
	Fabricating, Supplying & Installing 50 Micron thick Powder Coated, knock down type documents storage racks assembling at site, the tubular / edge bend profiles / sections members made out of HRC / CRCA sheet as per enclosed Technical Brief / Specifications & conditions, drawings, site measurements, load bearing capacity etc including preparing & getting approval of detailed design & working drawings, load testing etc complete as per instructions of the Architects / Bank	27130	KG
	The suggestive profile / sections (in mm) are Vertical Member – 65x85x1.8, Horizontal Members – 75x50x1.6, Shelf Planks – 210 W x 1005/1925x1.25, Bracings 20x30x1.25 & Base Plate 250x150x3 with necessary stiffeners, fasteners, slots, bending, welding (not at site), joinery, nut-bolts (minimal use)		
	Total No of Racks 126 Nos		
	Approx. weight of one Rack 215 Kg		
	126 No Racks X 215.32 Kg = 27130 Kg		

**Note:**

- Execution Drawings shall be prepared by the contractor in consultation with the Bank & Architects and shall be submitted to them for approval. Work will be executed as per Design, Drawing, Specifications, samples etc. approved by Bank and Architect.
- Rate quoted shall includes all Taxes such as VAT, Excise, Octroi, Sales Tax etc. including transportation charges, loading & unloading etc complete GST shall be paid separately as per Govt. guideline as per applicable as per actual.
- Supplier must prepare sample of Rack and carry out load test for carrying load of 300 kg UDL on each shelf. After written approval of Rack from Bank/Architect remaining Racks shall be made. No extra payment shall be made for preparing of sample.
- Weigh Bridge receipts must be produced along with bills, Material shall be weighed in presences Bank's representative. For payment purpose, total weight will be obtained by multiplying quantity with unit weight derived by averaging minimum ten samples.
- Powder coating shall be done by using Berger paint. Material as per company specifications Thickness of powder coating shall be 50 microns

- 6 Test Reports shall be provided to Bank from Reputed laboratory approved by Bank for Finished and Raw material used and powder coating.
- 7 Size, thickness , dimensions or design may change as per requirement. No extra payment shall be made for this.
- 8 Top shelf of Rack shall not have stiffners and hollow tube at egde
- 9 Base plate of 1.25mm thick CRC sheet shall be provided at base