

PRICE BID: LAST DATE AND TIME FOR SUBMISSION 2:00 PM ON 10.01.2020

BOQ FOR INTERIOR FURNISHING WORKS

SBI CHANDAKA INDUSTRIAL ESTATE BRANCH, RBO-III (KHURDA), AO-I, BBSR

Sl No.	Description of items	Unit	Quantity	Rate	Amount
1	Repair of BM/Officer table including side credenza irrespective of width dimension				
	Providing and fixing necessary hardwares such as channels, locks, handles, hinges, keyboard trays, sliding channels etc, as per the site condition. Remodeling the table as per Bank's new uniform colour, layout & elevation policy. Scrapping or making the existing surface rough. Providing and fixing 3.4 mm thick MDF board on the existing partition/door/table top or side etc., with necessary adhesive and nails/screws, hardwares etc. Thereafter, providing and fixing 1mm thick laminate of approved shade & colour, complete in all respect as per the direction of EIC. Polishing the beading etc, as per the site condition to match with the new ambience policy of the Bank. All unexposed surfaces of the table/ counters/ shelves to be painted with synthetic enamel paint/ fixing 0.8 mm thick laminate, as per the site condition.	Each	12		
2	Repair of counters including side credenza for five/six feet width SWO counter				
	Providing and fixing necessary hardwares such as channels, locks, handles, hinges, keyboard trays, sliding channels etc, as per the site condition. Design and detail of the counters shall be as per Bank's new uniform colour, layout & elevation policy, with curvature in front made of flexi ply.Scrapping or making the existing surface rough. Providing and fixing 4mm thick MDF board on the existing partition/door/table top or side etc., with necessary adhesive and nails/screws, hardwares etc. Thereafter, providing and fixing 1mm thick laminate of approved shade & colour, complete in all respect as per the direction of EIC. Polishing the beading etc, as per the site condition to match with the new ambience policy of the Bank. All unexposed surfaces of the table/ counters/ shelves to be painted with synthetic enamel paint/ fixing 0.8 mm thick laminate, as per the site condition.	Each	11		
3	Fixing/replacement of skin in the partition, storage, door, panelling, table top/side, etc.				
a	Scrapping or making the existing surface rough. Providing and fixing 3.4 mm thick MDF board on the existing partition/door/table top or side etc., with necessary adhesive and nails/screws, hardwares etc. Thereafter, providing and fixing 1mm thick laminate of approved shade & colour, complete in all respect as per the direction of EIC. Polishing the beading etc, as per the site condition to match with the new ambience policy of the Bank.	Sqm	390		
b	Providing and fixing mortise cylindrical lock in the door, as approved by the EIC.	Each	5		
c	Providing and fixing Godrej / equivalent approved make over head door closers in door with necessary fixtures and fittings etc.	Each	5		
4	Full Height/Low Height Glazed Partitions				
	Providing & fixing in position as per the layout full metal stud dry wall partition with the following specifications: a) supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick aluminium studs @ 600 mm c/c and 51 X 32 mm aluminium tracks at floor, middle, door and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. The rate should include necessary strengthening with studs/tracks or channel at doors and other openings. b) 9 mm BWR plywood fixed on both sides with 25 mm dry wall screws. c) 1 mm laminate on both sides (dark for bands, light for body) upto false ceiling level. d) 6 mm thick clear float glass with frosted film design as directed between 1050 X 2000 mm level in specified areas fixed with 85 X 15 mm beech wood jamb and 12 X 12 mm beech wood beading. e) All beech wood members to have melamine polish finish. Length X height upto false ceiling will measured for payment.	Sqm	1.00		
5	Low Height Glazed Partitions				

PRICE BID: LAST DATE AND TIME FOR SUBMISSION 2:00 PM ON 10.01.2020

BOQ FOR INTERIOR FURNISHING WORKS

SBI CHANDAKA INDUSTRIAL ESTATE BRANCH, RBO-III (KHURDA), AO-I, BBSR

Sl No.	Description of items	Unit	Quantity	Rate	Amount
	Providing and fixing GI metal stud low height partitions with the following specifications. a) Supporting system comprising of best locally available make 51 X 35 mm aluminium studs at 600 mm c/c and 51 X 32 mm aluminium tracks at floor, middle and at 1200mm level with joints staggered. The rate should included necessary strengthening with studs/tracks or channels at openings. b) 9mm plywood with 1mm laminate (dark for bands and light for body) on both sides c) 85 X 15mm beech wood capping on top and sides of openings. The beech wood members to have melamine polish finish. d) 8 mm glasses with edges polished and with frosted film design above 3'-0" height at specified areas as directed.	Sqm	1.00		
6	Wall/Column Panelling				
	Providing & fixing GI metal stud wall panelling with the following specification: a) Supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick aluminium studs @ 600 mm c/c and 51 X 32 mm aluminium tracks at floor, middle, door level and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. b) 9 mm BWR plywood fixed on one side with 25 mm dry wall screws for the entire height of panelling. c) 1 mm laminate (dark for bands, light for body) upto false ceiling level. e) All beech wood members to have melamine polish finish. length X height up to false ceiling will be measured for payment.	Sqm	60.00		
7	Storage Units				
	Providing/making and placing in position low height storage units upto 0.762m or 2'-6" height or height as directed and 0.457m or 1'-6" deep made with 18/19 mm BWR plywood front sides and middle shelf and back side with 6 mm BWR ply covered with 1 mm laminate (dark for bands and light for body) at all exposed surfaces. Inner/unexposed surfaces to painted with two or more coats of enamel paint with putty finish including melamine polish finish for all wooden members. The rate to include cost of all necessary hardware viz., cabinets hinges, locks, handles, tower bolts etc. The unit should have beech wood beading 25 X 40 mm at top and edge lipping 20 X 6 mm complete.	Sqm	1		
8	Roller blinds				
	Providing, Fitting & Fixing of Roller Blind of approved Make and approved Fabric Shade with Head Box. The blind should be of manual control by means of roller glide chain drive system. Fabric shall be manufactured from polymer coated glass of Luxaflex/MAK/Vista/Equivalent. Etc. complete in all respects as per the direction of Bank's Engineer	Sqm	56		
9	Emulsion paint				
	Applying Roller Finishing the wall surface with two or more coat of wall primer followed by two or more coats of plastic emulsion paints of asian or equiv of berger/ICI/ with approved shade and colour. Cost also include touch up finishing to the wall surface with putty of Birla/ Asian/Berger to make the surface in line and level.	Sqm	380		
10	Synthetic enamel paint				
	Scrapping the old surface of the grills/rallings as directed by the Bank. making the surface free from dust thereafater applying one coat primer with two or more coat of synthetic enamel paint of Asian or equiv of berger/ ICI/ with approved shade and colour. Cost also include touch up finishing to the surface/wall surface to get uniform and smooth look, complete in all respect as per the direction of EIC.	Sqm	236		
11	Plain Gypsum False Ceiling				

PRICE BID: LAST DATE AND TIME FOR SUBMISSION 2:00 PM ON 10.01.2020

BOQ FOR INTERIOR FURNISHING WORKS

SBI CHANDAKA INDUSTRIAL ESTATE BRANCH, RBO-III (KHURDA), AO-I, BBSR

Sl No.	Description of items	Unit	Quantity	Rate	Amount
	Providing and fixing Concealed Grid suspended ceiling system of 12.5mm India Gypsum Plaster Boards fixed to Frame Work of the company, Metal System concealed grid key lock suspended ceiling system consisting of 5mm suspension rod, adjustable spring loaded suspension clip, top cross rail of 3000mm long of 0.55BMT and furring channel 4000mm long made of 0.5mm BMT the top cross rail to be suspended from ceiling at every 1200mm and furring channel to be fixed to top cross rail at every 600mm to make a grid of 1200 x 600m. All the above components are to be made of galvanized steel. The rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape, two coats of emulsion paint over a coat of primer etc., complete as directed.	Sqm	1		
12	Repair of gypsum board ceiling				
	Repair of existing gypsum false ceiling by strengthening the supports and providing all necessary materials as required at the site including cutting for light fixtures, AC vent etc, complete in all respect as per the direction of EIC.	Sqm	90		
13	Repair of existing grid false ceiling				
	Repair of existing grid false ceiling by providing all necessary materials as required at the site, complete in all respect as per the direction of EIC.	Sqm	1		
14	Repair to entrance door.				
a	Providing bottom rails (aluminium/wooden), greacing the hydraulic closer/floor spring, as per the site condition. Polishing the glass to utmost satisfaction, as directed by the EIC.	Lumpsum	1		
b	Providing and fixing Godrej / equivalent approved make heavy duty floor spring (120 kg capacity) in entrance door with necessary fixtures and fittings etc.	Each	1		
c	Open able portion (it include 4 nos SS finished H type 1'-6" long door handle)	Each	2		
15	Repair and skin replacement of writing desk, suggestion box etc.	Lumpsum	1		
16	Fixing of solid acrylic surface				
	Supplying, Fabrication and Installation of Dupont-Corian/Merino solid surface of 6 mm thk of approved shade. Applied on table Top, Sides and any where wall, Logo etc in place of 1mm thick laminate. The edges to be joined should be straight, smooth and clean. Joints should only be made with joint Adhesive for Dupont Corian. All corners of a cutout must be rounded to 5mm radius and the edges smoothed, both on top & bottom, all around a cutout. "L" & "U" shaped corners need smooth 5mm radius inside corner. All works done to the satisfaction of the Architect/Engineer. Note:- Work done including labour, material wastage, time limits, required hardware etc.	Sqm	35		
17	Glass works				
a	Removing and resizing the 12mm glass of low height partition or counters and fixing the same with S.S D bracket of size 32mm etc, as per the site condition.	Sqm	1		
b	Providing, making and fixing in position new 12mm thick glass in the front side/ transacion side of half height partitions of Single Window Counters of appropriate size . All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, fixing frosted film and cut outs etc., for a neat finished job as per drawings and diretions etc., complete.	Sqm	14		
c	Providing, making and fixing in position new 12mm thick toughened clear float glass of trapizoidal shape in the front side/ transacion side of half height partitions of Single Window Counters of appropriate size . All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, fixing frosted film and cut outs etc., for a neat finished job as per drawings and diretions etc., complete.	Sqm	10		
18	Polishing of furnitures.				

PRICE BID: LAST DATE AND TIME FOR SUBMISSION 2:00 PM ON 10.01.2020

BOQ FOR INTERIOR FURNISHING WORKS

SBI CHANDAKA INDUSTRIAL ESTATE BRANCH, RBO-III (KHURDA), AO-I, BBSR

Sl No.	Description of items	Unit	Quantity	Rate	Amount
	Scrapping the old surface of the centre table/tea poy/baluster/rallings as directed by the Bank, making the surface even and smooth free from dust thereafater applying one coat primer with two or more coat of melamaine polish with approved shade and colour. Cost also include touch up finishing to the surface of the wood to get uniform and smooth look, complete in all respect as per the direction of EIC.	Lumpsum	1		
19	Cover to rolling shutter				
	Providing, fabricating and fixing cover for rolling shutter made of 51mmX51mm (2"x2") sal wood frame work spaced at 460mm (18") c/c both directions, fixing 19mm plywood and 1mm laminate(only out side), providing trap door for rolling shutter maintenance with necessary hardware all complete.	Sqm	5		
	Total				

Amount in words:

GST WILL BE PAID EXTRA AS PER THE ACTUAL

NOTE:

- 1) The quantities put to tender are tentative only. Payment would be made on the basis of the actual quantity executed after completion of the work.
- 2) Materials specification to be strictly as per items and approved materials only. A copy of approved materials to be obtained by the contractor from the Engineer-in-Charge before commencement of the work.
- 3) Prior to starting of work contractor to discuss with the Engineer-in-Charge and sample materials are to be approved before start of the work at site.
- 4) The colour scheme has been finalized and the Contractor to collect the same from the Engineer-in-Charge before procurement of the materials from the market.
- 5) The successful Contractor should be responsible to make the area/duct/walls water tight without any extra charges.

Signature of the Contractor