

#### **SBI INFRA MANAGEMENT SOLUTIONS PVT.LTD.**

#### (A wholly owned subsidiary of SBI)

## TENDERS ARE INVITED FOR PROPOSED AIR CONDITIONING WORK AT SBI PARLEPOINT BRANCH, SURAT.

#### **FROM**

# AUTHORISED DEALER OF RECOMMENDED MAKE (CARRIER, HITACHI, DAIKIN, TOSHIBA) IN GUJARAT

#### PART - B : PRICE BID

| IENDER SORMILIED BY: |   |  |
|----------------------|---|--|
| NAME                 | : |  |
| ADDRESS              | : |  |
|                      |   |  |
| DATE                 |   |  |
| DAIL                 | • |  |

#### ARCHITECT:

Ar. VISHAL PAREKH
409, KINARO APPARTMENT, NEAR MAKKAI POOL,
NANPURA, SURAT-395001
Mobile – 9879317886
Email – vishalvparekh@yahoo.com



## **INDEX**

## Tender documents are in two parts (Volumes) i.e. Part - A and Part - B

### PART - B (PRICE BID)

| Sr. No. | Description        | Page No. |
|---------|--------------------|----------|
|         |                    |          |
| 1       | Cover page         | 1        |
| 2       | Index              | 2        |
| 3       | Bill of Quantities | 3 - 4    |

## PROJECT: SBI , PARLE POINT BRANCH, SURAT

## BOQ of Air conditioning works for SBI, Parle point Branch, Surat

| NAME OF WORK: AIR CONDITIONING |   |           |      |      |        |  |
|--------------------------------|---|-----------|------|------|--------|--|
| Sr.<br>No.                     | Description   | Qty (Apx) | Unit | Rate | Amount |  |
| 1                              | Supplying, installing, pressure testing, gas charging (R22 / R410), vacumising of air-conditioning system of 2 ton each. (Hitachi, Carrier (superia), diakin, Toshiba). The work includes Installation of indoor unit on wall and outdoor unit on bracket/stand, concealing work of copper pipe, drain pipe, cables etc complete. 5 star latest BEE rating Jan 2018 (EER-3.5 with remote control) | 4         | nos. |      |        |  |
| 2                              | Supplying, installing, pressure testing, gas charging, vacumising of air-conditioning system of 1 ton each. (Hitachi, Carrier, diakin, Toshiba). The work includes Installation of indoor unit on wall and outdoor unit on bracket/stand, concealing work of copper pipe, drain pipe, cables etc complete. 5 star letest BEE rating Jan 2018(EER- 3.5 with remote control)                        | 2         | nos. |      |        |  |
| 3                              | Extra copper pipe (mandav / totaline) with nacessary control cables with class 'o' nitrile insulation, supply and istallation.  | 20        | mtr  |      |        |  |
| 4                              | Extra drain pipe (UPVC - Astral/Prime), supply and installation   | 20        | mtr  |      |        |  |
|                                | TOTAL   |           |      |      |        |  |

|    | notes:   |          |        |           |          |  |  |
|----|--|----------|--------|-----------|----------|--|--|
| 1  | From the total machines of copperpipe used 24 metres (4mx6 nos.) will be deducted.   |          |        |           |          |  |  |
|    | 4 metres of drain pipe, insualtion, electric cable should be supplied free along with each machine.  |          |        |           |          |  |  |
| 3  | Bracket support should be supplied free along with each machine.   |          |        |           |          |  |  |
| 4  | 4 Each AC to have copper condensing coil, cost of stand(wall mounted) for external unit including installation   |          |        |           |          |  |  |
| 5  | 5 All AC should be of same brand irrespective of individual lap mentioned on the model no and brand of ac  |          |        |           |          |  |  |
| 6  | complete clamping and sadling of cabling work and refrigerent piping included in the cost  |          |        |           |          |  |  |
| 7  | All chases in walls/columns/slabs made for installtion of copper pipes/ cables and fitting of the same is in the scope of the contractors including necessary material and labour. |          |        |           |          |  |  |
| 8  | All rates should be included of all taxes except service taxes on work contract service.   |          |        |           |          |  |  |
|    | the contractor should work according to the final layout and depute one pe   | ersong o | n site | from star | t of the |  |  |
| 9  | work till the completion.  |          |        |           |          |  |  |
| 10 | 0 GST will be extra as applicable.   |          |        |           |          |  |  |