

BOQ FOR INTERIOR FURNISHING WORK

PEARSONMUN BRANCH

Sl.No	Description of items	Unit	Qty	Rate(Rs.)	Amount
1	Supply and installing new Front Counters of overall size 5'6"X5'6", including cost of side credenza (3'x1'6") with top made up of 19 mm thick ply finished with laminate of 1.0 mm thick as approved by the Bank and wooden beading / moulding all round melamine polished. The cost to include two drawers of 100 mm deep & a file shutter of 450mm, a keyboard tray 250 mm wide with CPU stand, foot rest. The works to include all hardware like castors, brass hinges, ball catchers, fully extendable drawer slides, locks, handles etc. of approved make. Locks to be of single control type. All exposed edges to have wooden lipping stained to match the desk and melamine finished. Rate to include cost of Studds. Design and detail of the counters shall be as per Bank's new uniform colour, layout & elevation policy 2016 available with Bank's engineer, at A.O., with curvature on front with flexi ply. Counter & Credenza top to be provided with 8mm thick glass duly finished on edges and necessary cut to accommodate wires, edges to be m/c polished, with ms powder coated wire manager, complete as directed by EIC and placement as per layout given Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalent	nos	3		
2	Providing & fixing counter Front glass 12 mm thick duly bevelled of size - 1500mm x 750mm with frost film as per design directed, including cost of studs, making cut-outs for transaction and voice hole. Rate shall includes etching of glass as directed by bank.	SQM	6		
3	Providing & Fixing 12 mm thk clear float glass of size 320mm (width) x 1500mm (height) & tapering towards bottom as per the design and shape as shown in Bank's new uniform colour, layout & elevation policy fixed with necessary supports, on either sides at two of SWO ends as per design. Rate shall includes etching of glass as directed by bank. Make: Saintgobin/ Modiguard or equivalent.	SQM	5		
4	Supply and installing Branch Head Table of Overall size-7'6"X7'0" including cost of side credenza (4'x1'6") with top made up of 19mm thick ply with 1 mm thick laminate on top as approved by the Bank and wooden beading/ moulding all round melamine polished. The table cost to include (pedestal) , two drawers of 100mm deep & a file shutter of 450 mm, a keyboard tray 250mm wide with CPU stand. The works to include all hardware like castors, brass hinges, ball catchers, fully extendable drawer slides, locks, handles foot rest etc. of approved make. Locks to be of single control type. All exposed edges to have wooden lipping stained to match the desk and melamine finished. Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish & 8mm thick glass duly finished to be placed on top of table & credenza and necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy 2016 available with Bank's engineer, at A.O. Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalent	nos	1		

5	<p>Fabricating and installing Grahak Mitra table of overall size-5'x5'6'' including cost of credenza in straight or curved profile as per design and direction of EIC. The vertical supports and the front panel will be made of 2 nos of 19mm ply finished with 1 mm thick laminate and glass 12mm as per details. The table cost to include (pedestal) two drawers of 100mm deep & a file shutter of 450 mm, a keyboard tray 250mm wide with CPU stand. The works to include all hardware like castors, brass hinges, ball catchers, fully extendable drawer slides, locks, handles foot rest etc. of approved make. Locks to be of single control type. All exposed edges to have wooden lipping stained to match the desk and melamine finished. All the surfaces to be in laminate finish & 8mm thick glass duly finished to be placed on table & credenza top and necessary cut-out to accommodate wires, edges to be m/c polished, with m.s. powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy 2016 available with Bank's engineer, at A.O.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalent</p>	nos	1		
6	<p>Providing and fixing storage units 1'-6" wide & 2'6" high. The storage units shall have shutters made in 19mm thick plwood and finished in 1 mm thick laminate of approved shade including top. The storage units shall have intermediate shelves made in 19mm thick plywood with matching wood lipping. The storage shall have wood edge moulding as per the direction of EIC. This also includes providing necessary hardware like handles, hinges, locks, tower bolts etc of approved make. All exposed wooden surfaces shall be stained to shade as directed by the EIC and polished melamine</p>	m	10		
7	<p>Fabricating and fixing wall/column paneling, consisting of 25 mm x 35 mm (thickness not less than 1.5 mm) aluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical.) Panelling framework to be secured to wall surface / column surface and to be finished with 1 mm thick laminate of approved colour, brand and shade over 12 mm thick ply. Design and detail shall be as per direction of EIC and Bank's new uniform colour, layout & elevation policy.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalent</p>	sqm	36		
8	<p>Fabricating and fixing full height solid partition, made of 6 mm ply approved brand both side and to be finished with 1 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm (thickness not less than 1.5 mm) aluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. All exposed edge shall be covered with teakwood lipping with polishing complete in all respect. Payment will be made for the area upto false ceiling only.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalent</p>	sqm	8		

9	<p>Fabricating and fixing full height semi glazed partition, made of 6 mm ply of approved brand in both side and to be finished with 1 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm (thickness not less than 1.5 mm) alluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling. Middle portion at 900 mm to 2100 mm height shall have 5 mm thick plain float glass (Make: Saintgobin/Modigurd) fixed with 10 mm thick teak wood moulding duly polished. All exposed edge shall be covered with teakwood lipping with polishing complete in all respect. Payment will be made for the area upto false ceiling only. Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalen</p>	sqm	20		
10	<p>Providing and fixing low height semi glazed wooden partitions made of 6 mm ply of approved brand in both side and to be finished with 1 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm (thickness not less than 1.5 mm) alluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical). Middle portion at 900 mm to 1200 mm height shall have 5 mm thick plain float glass (Make: Saintgobin/Modigurd) fixed with 10 mm thick teak wood moulding duly polished. All exposed edge shall be covered with teakwood lipping with polishing complete in all respect. Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalen</p>	sqm	24		
11	<p>Providing and fixing Semi glazed doors of average size of 3'0"X7'-0" made of top, bottom and side wooden framework of teak wood of size 5"x2" and finished with 1.0 mm thick laminate 6 mm thick glass to be provided on upper portion between the framework. Glass to have frost film as per design directed. Doors to beequipped with heavy duty door closer. 1"dia and 12" long brush S.S.. finish handle of approved make to be provided. All complete including locks and necessary hardwares etc. Door should include door frames of size 2.5"x2.5" (doors of other sizes will be paid on pro rata basis.) Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalent</p>	Each	4		
12	<p>Providing and fixing low height door shutter in back side of SWO counter of average size of 750 mm x 1500 mm and 38 mm thick made of block board of approved brand and quality, finshed with 1 mm thick laminate of approved brand, colour and shade. The door shall includes all hardware such as: lock, handle, tower bolt, door stoper, door coloser, hinge etc. of approve make. All exposed edge shall be covered with teakwood lipping with polishing complete all respect. (doors of other sizes will be paid on pro rata basis.) Ply/Block Board Make: MR Grade of Century/ Green or equivalent. Laminate Make: Greenlam/Centurylam or equivalen</p>	Each	4		

13	Providing & fixing in position Aluminium Composite Panel (ACP) Shutter Boxing with framing of Aluminium Tube section of min 1.5"x1" and 20 gauge 2'-0" C/C both ways. ACP to be in 2' width panels or distributed equally. The Panels to be fixed to the frame with 3M or equivalent adhesive and mirror screws. Joints to be finished with Silicon based sealant. ACP thickness of 3 mm minimum. Aluminium foil thickness to be min 0.20 mm. Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used. Shades to be as per Bank's approval. ACP Trap door will be 12 mm marine ply finished with ACP.	sqm	12		
14	Providing and fixing suspended false ceiling with 600x600 mm size Fine Fisher tiles/Gypboard/Minwool/Armstrong and suspenders, frame work as per manufacturer's specifications. With Tagular edges Prima dune plus. The item to include cost of making necessary cut-outs for lights/air-conditioning grills as per design directed	sqm	45		
15	Providing and fixing suspended 12mm thick Gypsum board false ceiling with GI framework of standard gauge and as per the specifications of India Gypsum Co. The rate to include painting with lustre paint and making necessary design, pattern & cut outs for light fittings etc. complete as per direction of EIC	sqm	69		
16	Providing and fixing Roller blinds/Vertical Blinds of approved shade, design and texture Vista Levelor/Mac/Eqvt	sqm	20		
17	Providing and fixing floor mounted writing desk of size 4'x1'x3'(H) with 12 mm thick glass on top and voucher pigeon holes as directed, with laminated boards support	nos	2		
18	Providing and fixing glazed doors at Main entrance of average size of 2'6"x7'-0" made of top, bottom, middle and side wooden framework of teak wood of size 5"x2" and finished with 1.0 mm thick laminate & 8 mm thick float glass with frost film to be provided between the framework. Glass to have acid etched design pattern with logo as directed. Doors to be mounted on heavy duty floor spring. 1"dia and 15" long brush S.S. finish handle of approved make to be provided. All complete including locks and necessary hardwares such as hinge, stopper, tower bolt etc. Door should include 1st class local wood door frames of size 3"x2.5'" and cover all exposed edge with bidding as directed by EIC. (doors of other sizes will be paid on pro rata basis.)	each	4		

Rates are exclusive of statutory taxes (GST)

Note : Design and Detail of the counters shall be as per Bank's engineer at LHO and A.O