

**BOQ FOR INTERIOR WORKS OF E-LOBBY OF DIMAPUR BAZAR BRANCH**

Sl.No	Description of items	Unit	Qty	Rate(Rs.)	Amount(Rs.)
1	<b>SOLID ACP PARTITION FOR UPS ROOM:</b> Providing & fixing double skin 3mm thk ACP partition over 50 mm x 50 mm (thickness not less than 1.5 mm) aluminium section framework at spacing not exceeding 600 mm both ways (horizontal and vertical). Frame should be firmly fixed to the ceiling with necessary <b>louvers and door of size 750mm (W) x2000mm (H)</b> . Make: Alubond, Eurobond, Fujibond, Alcobond or equivalent.	SQM	16.99		
2	<b>FIXED ALUMINIUM PARTITION WITH 6mm THK GLASS AT FRONT PORTION:</b> Providing and fixing black powder coated aluminium partition with 6mm thk float glass with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge.	SQM	21.91		
3	<b>ALUMINIUM DOOR WITH GLASS:</b> Providing & fixing aluminum openable door comprising of approximate 83.5mm vertical members, black powder coat (minimum thickness of powder coating 50 micron) and thickness of section not less than 1.5mm, 6mm float glass openable with 4 nos 3" SS hinges, handle, door size 1050x2100mm. The rate to include design etching as directed by EIC.	SQM	3.4		
4	Providing & fixing in position <b>Aluminium Composite Panel (ACP)</b> Panelling with frame of min 20 gauge 35 mm x 25 mm Aluminium Tube section in 600 mm C/C both ways. Minimum 3 mm thick ACP to be fixed over the freamework with 3M or equivalent adhesive and mirror screw in 600 width panels or distributed equally. Joints to be finished with Silicon based sealant.  Make: Alubond, Eurobond, Fujibond, Alcobond or equivalent.	SQM	46.45		
5	Providing & fixing in position Aluminium Composite Panel (ACP) <b>Shutter Boxing</b> , ACP to be in 2' width panels or distributed equally. The Panels to be fixed to the frame with 3M or equivalent adhesive and mirror screws. Joints to be finished with Silicon based sealant. ACP thickness of 3 mm minimum. Aluminium foil thickness to be min 0.20 mm. Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used. Shades to be as per Bank's approval. ACP Trap door will be 12 mm marine ply finished with ACP	SQM	20.03		
6	<b>False ceiling :</b> Providing and fixing suspended <b>false ceiling with 600x600 mm size &amp; 12mm thick</b> mineral fiber ceiling tiles of Armstrong dune or approved make. Suspender, frame work as per manufacturer's specifications. The item to include cost of making necessary cut-outs for lights/air-conditioning grills as per design direction by bank.	SQM	48.3		
7	<b>Gypsum board false ceiling :</b> Providing and fixing suspended 12mm thick <b>Gypsum board false ceiling</b> with GI framework of standard gauge and as per the specifications of India Gypsum Co. The rate to include painting with lustre paint and making necessary design, pattern & cut outs for light fittings, cove light etc. complete as per design direction by bank.	SQM	21.46		
8	Dismantling of existing walls, doors etc and carting away from the site.	SQM	12.93		
9	Providing half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in cement mortar 1:3 (1 Cement : 3 coarse sand) in superstructure.	SQM	3.78		
10	12 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement : 4 fine sand) <b>with putty</b> .	SQM	7.56		

**BOQ FOR INTERIOR WORKS OF E-LOBBY OF DIMAPUR BAZAR BRANCH**

SI.No	Description of items	Unit	Qty	Rate(Rs.)	Amount(Rs.)
11	Scrapping off the old paint and finishing walls with two coats emulsion paint of required shade. Make: Asian paint, Dulux and including scaffolding complete.	SQM	41.97		
12	Painting of steelwork with enamel paint by removing the existing paint, dust and dirt as required . One or more coats on old work	SQM	58.37		
13	Removing existing exterior paint by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete and finishing walls with one coat of priming coat of primer along with putty wherever required, two or more coats of apex weather coat exterior paint of required shade. Make: Asian paint, Dulux and including scaffolding complete.	SQM	80.8		
14	Providing and laying vitrified floor tiles in 600mmx600mm size of 10mm thickness with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete.	SQM	42.26		
15	Supplying and fixing rolling shutter of approved make, made of 80 x 1.25 mm thick M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of 1.25 mm thick for rolling shutters. Rate to include providing fixing of ball bearing for rolling shutter.	SQM	2.98		
	<b>Grand Total</b>				

**NOTE :GST to be considered extra**