

**BOQ FOR INTERIOR WORKS –SHIFTING RBO 1 ( KADAPA-URBAN) INTO AN ALTERNATE PREMISES.****Banks Uniform Layout Policy Colour Scheme to be followed.****All contractors are requested to understand the uniform layout policy colour scheme and the specifications of the SBI before**

Item No.	Description	Qty.	Unit	Rate	Amount
1	<p><b>MAKING NEW CLUSTER OF FOUR TABLES OF SIZE 5' X 2'6" WITH SIDE UNITS and LOW HT PARTITIONS: TABLES OF EACH SIZE 1500mm X 750mm X 750 mm, Side table: 1050X450X750mm: Tables are placed back to back and side by side :</b> a) Table top and all over /other members to be made in 18/19 mm BWR plywood and 1mm laminate, all edges to have 20 X 6 mm teak wood lipping. b) One drawer cum shutter unit with necessary hardware viz: drawer channels,handles, locks etc. c) One ready made mobile CPU pedestal. d) One plywood key board tray with channels to be provided e) One foot rest f) Side table made with 25 mm BWR ply and 1mm laminate all over and other members with necessary hardware viz., cabinet hinges, handles, locks, tower bolts, etc. and 25 X 40 mm beech teak beading and 20 X 6 mm beech wood lipping etc. g) All the exposed surfaces to have 1 mm laminate to match with other parts of the cabin of approved shade and brand. All wooden members to have melamine polish. All internal area of the drawers, leg rooms to be finished with 0.8 mm thick half white laminate. Specifications of low ht partitions shall be same as mentioned in low ht or full ht partitions items. Partitons shall have pin up board with white lenin cloth for full width and height 1' above the table. Rate to be quoted shall be for low ht partitions, pin up board, four tables complete.COST OF LOW HEIGHT PARTITIONS IN BETWEEN THE FOUR TABLES TO BE INCLUDED IN THE QUOTED RATE. LOW HT PRITIONS ALONG THE PASSAGE SIDE SHALL BE PAID FOR EXTRA.</p>	4	EACH CLUSTER		
2	<p><b>FULL HEIGHT PARTLY GLAZED PARTITIONS: (AGM cabin)</b> Providing &amp; fixing in position metal stud dry wall partition with the following specifications: A) supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, door and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. The rate should include necessary strengthening with studs/tracks or channel at doors and other openings. B) 9 mm BWR plywood fixed on both sides with 25 mm dry wall screws. C) 1 mm laminate on both sides (Banks uniform color layout color scheme) up to false ceiling level. D) 6 mm thick clear float glass with etching design as directed between 1200 X 2000 mm level in specified areas fixed with 85 X 15 mm Teak wood jamb and 12 X 12 mm teak wood beading. E) All Teak wood members to have melamine polish finish. Doors in partitions wherever required to be provided with 35 mm thick solid core ISI approved alround beach wood lipping, alround fixed in a concealed door frame of best quality beach wood three sides of sections size of 75x75 mm or as advised by the engineer in charge. Flush door shutters to be fixed with 1 mm laminate (banks uniform layout color scheme) on both sides and 8 mm clear float glass with etching design as directed with 50 X 15 mm teak wood jamb around the glass opening and 12 X 12 mm teak wood beading for fixing of glass on both sides including necessary hardware viz: door stopper, door silencer, Door set lock, handles, brass hinges of approved make &amp; quality, melamine spray polish finish to all beech wood members etc. complete as directed. F)Door Closer of heavy duty 'Godrej' make or equivalent to be fixed. Length X height up to false ceiling will measured for payment. Plywood area all over to be sprayed with an ti termite solution before use in the work.</p>	10	Sq.M		

3	<p><b>Low Height Partition:</b> Providing &amp; fixing metal stud low height partitions with following specifications. a) Supporting system comprising of best locally available make 51 X 35 mm metal studs at 600 mm c/c and 51 X 32 mm metal tracks at floor, middle and at 1200mm level with joints staggered. The rate should included necessary strengthening with studs/tracks or channels at openings. b) 9mm plywood bwr grade with 1mm laminate (as per banks uniform colour scheme) on both sides. c) 85x15mm Teak wood capping on top and sides of openings. d) 12mm glass of 12"height on top of low height partition (total height to be 4'6" to 5') with necessary beach wood beading and etching work wherever required also to be fixed. e) All the (horizontal and verticle) edges of the low height partitions shall be covered with 12mm thick best quality corian beading materials and the edges to be rounded off and polished to look elegant. The beech wood members to have melamine polish finish. Anti termite solution to be sprayed before using the ply wood in the work.</p>	100	Sq.M		
4	<p><b>PARTITIONS- FIXED GLAZED PARTITIONS</b>          Providing Supplying and fixing Full Height Glazed Partition with 12 mm thick toughened glass of approved brand and manufacture, edges with Crystal/pencil polished around with patch fittings Ozone make of top and bottom patch (OPF- 640) &amp; bottom (base rate Rs.1250/- ) or equivalent fixing arrangement and making necessary holes cutout etc. all complete as per the direction of Engineer. (hardware make:- Ozone/ Dorset/ trium/Enox/Dorma/kich or Equivalent. <b>FULLY GLAZED DOOR</b>          Providing Supplying and fixing, of 12 mm thick frameless toughened glass door shutter of approved brand and manufacture, edges with Crystal/pencil polished around including patch fittings Ozone make of top patch (OPF-2) &amp; bottom (OPF 3) top pivot (OFS-ACC-GDP), corner patch lock (OPL-1). 'H' type handle 20mm x 600 mm Ozone make Model No.OGH.55 (base rate Rs.2030/- ) &amp; heavy duty floor machine (model no's 8400 of Ozone) or equivalent fixing arrangement and making necessary holes cutout etc. all complete as per drawing and as per direction of Engineer. (hardware make:- Ozone/ Dorset/ trium/Enox/Dorma/kich or Equivalent, Glass make SAINT GOBAIN/MODI Float OR EQUIVALENT) as per the design. The glass shall be filmed with frosted fill or etched as per the Directions. The rate shall be quoted along with the film. The rate shall be inclusive of all the necessary material, required hardware, labor, transportation, necessary for the complete execution of the item.          AT Main Entrance Door 1050 mm x 2400mm. 2 no.s for or as suitable at site as directed. Glass make SAINT GOBAIN/MODI Float OR EQUIVALENT) as per the design. The rate shall be inclusive of all the necessary material, required hardware, labor, transportation, necessary for the complete execution of the item. The rate shall be inclusive of all the necessary material, required hardware, labor, transportation, necessary for the complete execution of the item. Glass should have etching work done as per design suggested. This includes for doors wherever necessary along with standard fittings (patch of ) banks approved quality</p>				
5	<p><b>Wall Panelling with ply and 1mm laminate):</b> Providing &amp; fixing metal stud wall panelling with the following specification: a) Supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, door level and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. b) 9 mm BWR plywood fixed on one side with 25 mm dry wall screws for the entire height of panelling. c) 1 mm laminate (dark for bands, light for body) up to false ceiling level. e) All teak wood members to have melamine polish finish. Length X height up to false ceiling will be measured for payment. plywood to be used in the work to be sprayed with anti termite solution. banks uniform layout policy color scheme to be followed. (Location and extant of partition shall be strictly as advised by the engineer in charge)</p>	210	Sq.M		
6	<p><b>COULMN AND WALL PANELLING WITH LACQUERED GLASS IN COMBINATION OF BLUE AND WHITE COLOUR</b>          Providing and Fixing of Column and Wall Panelling with following specifications          a) Supporting system comprising of best locally available make 25mm x25mm mmx 1.2 mm aluminium sections at 600 mm c/c as per the drawing b) 12 mm BWR PLY/MDF(TESA) with 8 mm thk LACQUERED GLASS IN COMBINATION OF BLUE AND WHITE COLOUR TOUGHEN of saint gobin/modi float /asahi float on all the exposed surfaces with natural silica.(as per banks uniform color scheme) as per the drawing Anti termite solution to be sprayed before using the ply wood in the work. making complete as per the design. The rate shall be inclusive of all the necessary material, required hardware, labour, transportation, necessary for the complete execution of the item, as per the directions at site.</p>	106	Sq.M		

7	<u>Wall Panelling with VENEERed ply</u> : Providing & fixing metal stud wall panelling with the following specification: a) Supporting system comprising of best locally available make 51 X 35 X 0.55 mm thick metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, door level and ceiling level with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. b) 9 mm BWR plywood fixed on one side with 25 mm dry wall screws for the entire height of panelling. c) 4 mm thick veneered ply (dark for bands, light for body) up to false ceiling level, of banks approved quality in the price range of Rs 90-Rs 100 per sq ft d) Melamine polishing on veneered ply. Length X height up to false ceiling will be measured for payment. plywood to be used in the work to be sprayed with anti termite solution. banks uniform layout policy color scheme to be followed. (Location and extent of partition shall be strictly as advised by the engineer in charge)	160	Sq.M		
8	<u>REGULAR Grid False Ceiling</u> :- Providing and fixing in true horizontal level false ceiling grid system of Armstrong World Industries/ Daikin / CEPro etc. The suspension system shall be REGULAR revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitered ends with "birds mouth" notches to provide mitered cruciform junctions. Main runners to be spaced at 1200mm c/c fixed by using 2mm pre-straightened GI wire. Main tee, rotary stitched of size 15mm x 44mm x 3600mm at every 1200mm c/c maximum and 1200mm cross tee of size 15mm x 44mm x 1200mm at every 600mm c/c maximum and 600mm cross tee of size 15mm x 44mm x 600mm at every 1200mm c/c maximum and 19mm x 19mm x 3000mm wall angle all-round the wall to form grid size of 600mm x 600mm and suspending the grid using 2mm pre-straightened GI wire and 6mm nylon rawl plug at every 1200mm intervals at the main tee and laying of dunne premier micro look mineral fiber tiles manufactured by Armstrong World Industries of size 600mm x 600mm x 15mm over the formed grid etc., complete as directed. Rate to be quoted should include charges for dismantling the existing false ceiling neatly and disposing off the unserviceable materials.	560	Sq.M		
9	<u>Storage Units</u> : A) Providing, making and placing in position low height storage units upto 750 mm height or height as directed and 450 mm deep made with 18/19 mm plywood front sides and middle shelf and back side with 9 mm BWR ply covered with 1 mm laminate (dark for bands and light for body) at all exposed surfaces. The top shall have 25 mm mdf board 'post-formed' edge with pf lamination, Inner/unexposed surfaces to be painted with two or more coats of enamel paint with putty finish including melamine polish finish for all wooden members. The rate to include cost of all necessary hardware viz., cabinets hinges, locks, handles, tower bolts etc. The unit should have beech wood beading 25 X 40 mm at top and edge lipping 20 X 6 mm complete. All internal areas to be sprayed with anti termite solution and finished with 0.8 mm thick laminate of half white shade.	85	Sq.M		
10	<u>OFFICERS TABLES (Size 1500 X 900 X 750 mm. Side table 1050X450X750mm)</u> : Providing, making & placing in position executive table and side table with the following specifications: a) Table top and all over /other members to be made in 18/19 mm BWR plywood and 1mm laminate, all edges to have 20 X 6 mm teak wood lipping. b) One drawer cum shutter unit with necessary hardware viz: drawer channels, handles, locks etc. c) One ready made mobile CPU pedestal. d) One plywood key board tray with channels to be provided e) One foot rest f) Side table made with 25 mm BWR ply and 1mm laminate all over and other members with necessary hardware viz., cabinet hinges, handles, locks, tower bolts, etc. and 25 X 40 mm beech teak beading and 20 X 6 mm beech wood lipping etc. g) All the exposed surfaces to have 1 mm laminate to match with other parts of the cabin of approved shade and brand. 6mm thick laquered glass for the modesty panel (in front of tables). All wooden members to have melamine polish. All internal area of the drawers, leg rooms to be finished with 0.8 mm thick half white laminate. Special locks to be fixed which can be opened with single key.	29	Each		

11	<p><b>TABLES --UNIT HEAD TABLE</b>          Providing and Fixing Branch Head table of size 1800 mmx 900x750mm and Credenza of size 1200 mm x450 mm 750 mm with following specifications          The Table Top shall be made of 18 mm thk BWR PLY Century/Archid/Green/Marino with 4mm thk veneer on all the exposed surfaces finished with High Gloss PU finish as per the Drawing The sides (Verticals) shall be made of 18 mm thk BWR PLY Century/Archid/Green/Marino /HDF(TESA)with 4mm thk veneer on all the exposed surfaces finished with High Gloss PU finish as per the Direction as per the Drawing Front Modesty Panel of the table shall be 6 mm thk toughen blue lacquered glass as per the drawing The Table Top Shall be provided with 10mm thk plain glass with bevelling as per the drawing The Table shall be provided with Drawer unit Comprising of 3 nos of sliding drawers with sleek Telescopic channels, Handles ,locks and Necessary Hardware,ss cabel manager, required as per the Drawing The Table shall be provided with Moulded CPU Trolley with castors and Moulded Key board Tray with Telescopic Channels.          All the Internal Surfaces and leg room areas shall be finished with 0.8 mm thk laminate of approved shade and colour as per the direction.The Foot rest shall be made with 18mm thk BWR PLY with 1mm thk laminate on all the Internal and exposed surfaces SIDE CREDENZAS UPTO 750 MM HT</p>	1	Each		
12	<p><b>MAIN ENTRENCE GLASS DOOR- 12MM THICK TOUGHENED GLASS BRANCH MAIN DOOR</b> :Providing and fixing Main door using <u>12mm clear</u> float toughened Glass (entire elevation area of the main door shall look glass with patch fittings only, no wooden or plywood sections/panels). The cost to include all hardware required viz., Dorma or approved equivalent make floor springs, patch fittings etc its accessories, top pivot, center lock, 900mm glass door handle etc.shall be provided. 3M privacy film to be pasted as per design and directions. The rate is for a finished item of work etc., complete as directed.Height shall be measured up to false ceiling or actual glass height.. Supporting work to be/ extended up to rcc slab level shall not be paid for separately.</p>	10	Smt		
13	Providing and fixing 4mm new vennered PLY instead of 1 mm laminate of banks approved quality over exisintg surfaces of furniture such as tables, side units, low or full ht partitions etc and PU polishing etc comple.(basic rate of veneer selected shall be about 80/- to 90/- per sft	35	Smt		
14	<p><b>REMOVING AND REFIXING CONFERENCE TABLE FROM OLD PREMISES TO NEW PREMISES</b></p> <p>Removing and refixng the conference table including making good all the damages if caused while shftng. Contractors are requested to visit RBO1, Kadapa understand the exteant and quote accordingly.</p>	18	RMT		
15	<p><b>TEXTURED PAINT-</b> at selected areas Applying painting of two or more coats of plastic/ acryliclight textured emulsion paint of approved shade&amp; manufactured by spectrum or equivalent conforming to ISI to walls after scraping the original surface rubbing with sand paper of zero sizefor smooth, surface , two coats putty &amp; two coats of emulsion paint of approves colour. Coats have to be made successively after drying each coat and finishing with sponge roller(matt finish) over a coat of approved primer with necessary scaffolding etc.The rate shall be inclusive of all the necessary material,required hardware, labour, transportation, necessary for the complete execution of the item.</p>	200	Smt		
16	<p><b>ROLLER BLINDS:</b>          Providing supplying and fixing of transparent Roller blinds of approved make,shade and texture of TOUCH make or equivalent using good quality of roller mechanism of Acmeda or equivalent as per the design and direction. The rate shall be inclusive of all the necessary material,required hardware, labour, transportation, necessary for the complete execution of the item</p>	50	Smt		
17	<p><b>SOFT BOARD</b>          Providing &amp; Fixing of soft board, made of molded stream beach frame size of 25mm x 12mm x 6mm thick shall be finished with melamine polish. 6mm thick BWR PLY on back side &amp; 12mm thick soft board shall be fixed on front. Fixing cloth of selected design of Basic rate of Rs. 270 per sq. mtr</p>	10	Smt		

## RBO KDP

18	ROLLING SHUTTER BOX Supplying and fixing 50mmx50mm TW frame and closing with 18 mm thk BWR PLY on all sides as per the design and finished with 1mm thk laminate on all internals areas of bank and 4mm thk ACP with natural silica as per the design and directions of the architects. The rolling shutter box shall be provided with necessary locks ,handles as directed Anti termite solution to be sprayed before using the ply wood in the work. making complete as per the design. The rate shall be inclusive of all the necessary material,required hardware, labour, transportation, necessary for the complete execution of the item	5	Smt		
19	DIGITAL WALL BEHIND GRAHAKMITRA (OR GREETING AREA) Providing and fixing display boards (behind Help desk & counters) using twin perplex sheets of highly transparent clear acrylic sheets of 5mm thick sand witted with display sheet (placed in between) with required information display sheets made with 3M thickers material as per banks approved design and write up of Uniform layout policy of SBI and fixed to walls with suitable SS studs. The information or display material to be printed should be strictly as per banks approved patterns and contractor must arrange designer for making sample approval of the image. A Caption "THE BANKER FOR EVERY INDIAN" to be printed on the flex in bold and standard specified color as above caption. The subject to be displayed for the DIGITAL wall has to be designed by the vendor as directed by the Engineer The rate shall be inclusive of all the necessary material,required hardware, labour, transportation, necessary for the complete execution of them	10	Smt		
20	ACP PANELLING WHITE AND BLUE OR ANY OTHER COLOUR COMBINATION FOR FRONT FACEDE Supply and fixing 3.5 mm thick ACP panels(exterior type) OF ALSTRONG, EURO/AULCOBAND/ ALSTONE MAKE and APPROVED COLOUR for panelling to walls ith25mmx38mmx1.5mm thick aluminium pipe sections for framing at 600mm intervals horizontally and vertically as per manufactures specification. The rate shall include cost of all material and labour etc.of light weight concrete core composed of Portland cement, binders siliceous and milceous materials aggregate with tongue and groove arrangement with two 4mm thick fibre reinforced cement facing sheets. The grooves and joints in the panels should be filled with suitable fillers. In extreme end in the elevation of the branch as directed by the Engineer, Vendor should fix ACP of white colour of 8'x8 with grids of suitable size in between on which Bank's logo shall be fixed. Therate shall include cost of necessary fixing material like cleats etc. Colours should be as per Banks uniform layout policy strictly. The base price for ACP per sft should be not less than Rs.55 to Rs60. The rate shall be inclusive of all the necessary material,required hardware, labour, scaffolding, transportation, necessary for the complete execution of the item	20	Smt		
21	NAME BOARD: Providng and fixing a 18 mm thick black galaxy granite 188 thick fully poshed stone on the existing wall and fixing chromium plated lettering STATE BANK OF INDIA, REGIONL OFFICE, KADAPA " IN ENGLISH AND HINDI at vantage location. The brass lettring shall be of suitable size height not less than 5", spaced neatly of standard make etc complete. The ganite sheet shall be 2.4 mt long, 1.2 mt height. The proof shall be submitted for banks approval before procurement. (STRICTLY AS PER APPROAL OF DRAFT)	1	Job		
22	FULL HT FULLY GLAZED PARTITIONS 11TH 12MM GLASS WITH PARTCH FITTINGS, ETCHING, GLASS DOOR ETC COMPELTE WITH ANECCESSARY AHRDWARE .	30	Smt		
23	BUY BACK OF OLD FURNITURE FROM EXISTING PREMISES	-1			
24	Removing the old fans, tube lights, banks wiring,	1			
	GRAND TOTAL				
	DISCOUNT IF ANY (REBATE MAY BE MENTIONED IN TERMS OF % OF QUOTED AMOUNT ON GRAND TOTAL)				
	Net				
	total				
	GST EXTRA				

Contractor's Signature with Seal &amp; Date