

**TENDER FOR CIVIL/INTERIOR FURNISHING WORK AT ADMINISTRATIVE OFFICE,
STATE BANK BHAVAN KOLLAM - PRICE BID**

No	Description of work	Unit	Qty	Rate	Amount
1	Cutting the false ceiling where ever required, removing the existing wall panelling glass and stacking it carefully without damages at location as advised by Engineer in charge.	M ²	15		
2	Removing the existing 12mmthk. Toughened glass with all fittings and fixtures intact and to be stacked safely without any damage at location as advised by EIC	M ²	15		
3	Demolishing of existing 9" thk. Brick wall mechanically without causing any damage to the existing structure and disposing of the waste at site away from the office at contractor's own risk and cost	M ³	8		
4	Providing and laying ready mix concrete M 20 including cost of all form work watering, curing etc complete but excluding cost of reinforcement for beam & lintel.	M ³	2		
5	Reinforcement for RCC work bent tied and placed in position plain grill requiring bending in cold using tor steel including cost of binding wire.	kg	220		
6	Patch Plastering after making the surfaces even with Cement Mortar 1:5, (1 cement 5 sand) 12mm thick one coat floated hard and traveled smooth to inside walls including all staging work watering,curing etc complete.	M ²	20		
7	Chipping the tiled flooring/Walls to make it rough to develop strong key for the new brick partition.	M ²	6		
8	Solid block works of approved qty of size 30x20x15cm & of compressive strength not<35 kg/cm ² in in C.M. 1:6 in super-structure above plinth level including staging if required watering ,curing etc complete.	M ³	10		

9	Plastering with Cement Mortar 1:5, (1 cement 5 sand) 12mm thick one coat floated hard and traveled smooth to inside walls including all staging work watering,curing etc complete.	M ²	55		
10	Finishing New cement plastered wall with 2 coat of putty and painted with 2 coat of plastic emulsion paint after cleaning the surface	M ²	80		
11	Dismantling the existing Record Room door (shutter with frame) and fixtures and refixing the same at the new location in line and level. Carrying out any fabrications and rectifications if required.	LS	1		
12	Providing and fixing of M/F suspended false ceiling as the detail given in the drawings. With G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprising	M ²	800		
	Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls around perimeter side of the ceiling. The intermediate channels suspended from ceiling,through starp hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional perimeter channels (MF 6A)for light fittings, Air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws to from grids with 2 coats of plastic emulsion paint of approved color and one coat of putty over a coat primer etc, complete.				
13	Full Height Solid/Partially Glazed Partition - Supply and set in position of double skin full height partitions as per shape and size shown in the drawing.	M ²	20		

	<u>Frame Work Detail:</u> Aluminium sections of size 63.5 X 38.1X1.2 mm thk. of INDAL/JINDAL as internal frame structure,vertically at about 60cm centers varied along columns wall ends, junctions of walls, as necessary. Horizontally of the same size of frames at floor level,750 mm, 1500 mm,2100 mm, and roof level. same size at 350					-
	<u>Lining Work:</u> 8 mm Plywood of approved make on both sides of framework from floor level to 6"above false ceiling level, and to be finished with 1mm laminate of approved color and shaped on both sides including necessary grooves and steam beach beadings.					-
	Measurement for the partition area shall be considered from floor level to false ceiling level only.					-
14	Providing and fixing Officer Table of size 1500 x 750 X 750 mm high to detail as shown in drg. Comprising table top out of 25mm thick Plywood Board post formed with 1mm thick flexy laminate of approved color and brand with both side half rounded edge and another two side edges with 3mm thick band strip.12 mm glass with edge rounded to be provided for the table top. Aqua blue shade of saint Gobain (or) equivalent toughened glass panel fixed on the 18mm thick to be fixed on front vertical laminated Plywood Board with SS studs.	Nos	2			
	On front and side of drawer finished with 1mm thk laminate and additional 18mm Plywood is fixed on front side to pattern with necessary grooves and finished with 1mm thick laminate.					-
	MS Powder coated Keyboard tray and 50mm Dia MS wire manager of approved quality.					-
	One set of 4 drawers about 450mm wide, 712.5 mm high and 600mm deep to shape supported with 18 mm Plywood at bottom, sides and rear. 4 nos. of drawers out of which 3 nos. of equal height and 1 no. drawer at the top most of 75mm high made out of 12 mm thick					-

	All concealed faces of Plywood finished with one coat of wood preservative paint and exposed faces of Steam beach beading polished to the satisfaction of the Bank. The inside faces of drawer should be waxed and finished with varnish of app color and shade				-
15	Side Tables For OFFICER	Nos	4		
	Providing and fixing side unit for Cash Officer table to detail as per drg. of size 1000mm x 450mm, 18 mm Plywood for top, bottom, rear, sides and One intermediate with necessary reeper. The unit top shall be with 25mm thick Plywood Board of approved make with 1mm thickness flexy laminate of approved color and brand with front side half rounded edge and all the edges and all the three sides with 3mm thick band strip. Side hung shutter in both the panels using 18 mm Plywood and finished with 1mm laminate of approved color and shade, including all necessary TW lipping, Box Type hinges, Locking arrangement, 100 mm long S.S brush finish handles, tower bolt, ball catch etc,.complete.12 mm glass with edges rounded to be provided for the table top				-
	All concealed faces of Plywood finished with one coat of wood preservative paint and exposed faces of Steam beach molding / beading polished to the satisfaction of the Bank. The inside faces of unit wax and finished with varnish of approved color and shade.				-
	TOTAL				
	GST 18%				
	GRAND TOTAL				