

**BOQ FOR INTERIOR FURNISHING WORKS OF SBI UDAIPUR CURRENCY CHEST AND BRANCH AT  
UDAIPUR, TRIPURA, INDIA**

<b>GROUND FLOOR WORKS</b>					
<b>SL</b>	<b>DESCRIPTION</b>	<b>UNIT</b>	<b>QNTY</b>	<b>RATE</b>	<b>AMOUNT</b>
<b>A</b>	<b>CARPENTRY WORKS</b>				
<b>1</b>	<b>SINGLE WINDOW COUNTERS (SWO) WITH PARTITION AS PER THE DRAWING (6'1" X 5'3")</b>				
	Providing and fixing in position the Single Window Counter of internal size 1500mm x 2100mm, made of 18mm thick MR grade Plywood and drawers/cup boards with 12mm/8mm(6mm for Back only) MR grade Plywood as per the drawing and direction of Engineer in Charge with key board drawer and necessary arrangements for keeping the monitor, CPU,UPS , printers , battery and note counting machine etc as shown in the drawing . All the horizontal surfaces shall be provided with 6mm thk Corian, Frosty White fully polished and front edge bended as per design and vertical surfaces to be finished with 1.0MM thk laminate of Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE of approved shade as per approved design. All other sides (Customer Side and inside) and shutters of of side storage and pedestal (Inside) shall be finished with 1.0MM thk laminate of Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE of approved shade as per approved design . It shall also consist of 12 mm thk clear Toughened glass of size 1'6 1/2 " x 4'3" on either sides as per the design and shape as shown in the detail drawing, fixed with necessary supports, on either sides at two ends as per design. All the Thickness shall be finished with Corian to desired polished and shade.The side storage/Cadenza shall have doors sliding on rollers as per disign with proper locking system. The key board drawer shall be provided with telescopic rail of "hettich/ Hafele" make . All internal surfaces shall be painted with 2 or more coats of synthetic enamel paint of approved colour and make over a coat of primer . The drawers /cup boards shall be fitted with best quality knob/handle and self locking arrangements of Hettich/ Hafele or equivalent make. The internal dimensions shall be 1500mm x 2100 mm as per drawing(Pl refer the Detail Drawing for Detailed Measurement and Specification). The rate to include all necessary charges of hardware materials, labour, taxes, transportation and contractor's overhead etc. Refer Detail Drawing of Single Window for reference. Rates Shall be inclusive of all locks , handles, magnets, Tower bolts etc and other hardware items as may be required and as asked by the architect/ engineer incharge	<b>NOS</b>	6		
<b>2</b>	<b>WORK STATIONS WITH SIDE STORAGE</b>				
<b>i</b>	<b>FOR OFFICERS (5'6" X 5'6")</b>	<b>NOS</b>	6		
	Providing and laying Officer's Workstations of over all size 1650mm x 1650 mm , of top as mentioned in the attached drawing. It shall consist of ¾" thk.MR grade Plywood top as per design (double edge on the front and back with ) supported on ¾" thk.MR grade Plywood verticals. Suitable (as per Architects design) . A ¾" thk.MR grade Plywood apron shall be provided as per Architects design with necessary pattern. The Table top and side storage alongwith all other external sides should be finished with 1.0MM thk laminate of Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE of approved shade as per approved design and a groove shall be maintained and provided at the joints between two colour shade. Each top should be provided with 3" dia PVC wire manager of approved quality near the CPU / Monitor , 1 no Metal Keyboard Tray of Best quality, 1 no Metal CPU Trolley at position as shown in drawing,.The side Storage shall have openable shutter on hinges with necessary locking arrangements. All exterior parts of the storage, including the shutters shall be finished with 1.0MM thk laminate of Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE of approved shade & colour over plywood . The Work station shall also consists of a pedestal for the table as per design with central locking system. The external face and sides of the pedestal shall be finished with with 1.0MM thk laminate of Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE of approved shade as per design .All internal surfaces shall be painted with 2 or more coats of synthetic enamel paint of approved colour and make over a coat of primer. All locks and other hardware fitting shall be strictly of Haffle or Hettich only and appropriate deduction/ penalisation as deemed fit by the enginger-in-charge/ architect shall be made if the same make for locks and all hardware fittings are not used by the contractor.				
<b>B</b>	<b>PARTITIONS WORKS</b>				
	<b>Note :- The rate shall be include of frame work above false ceiling level. Measurement should be taken up to false ceiling level and visible portion only.</b>				
<b>1</b>	<b>FULL HT SOLID PARTITION</b>				
	Providing and fixing partition framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm x 3mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. The framing shall be fixed with 8 mm thk. BWPI ply on both side and either kept naked or finished with Laminate/ Veneer/ Corian/ Lecquered Glass of thickness 1mm / 4 mm / 6mm and 6 mm respctively, as per the description as in below . The shade of laminate / veneer/ corian/ lecquered glass should be as per the direction and design of the architect concerned. The skirting should be as per approved laminate as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete. <b>The edge beadings with steam beach wood should be finished with melamine.</b>				
<b>i</b>	<b>WITH BOTH SIDE LAMINATE</b>	<b>SQM</b>	21.2		
<b>2</b>	<b>FULL HT PARTLY GLAZED PARTITION</b>				
	Specification same as 3 above except for 8mm approved make clear float glass shall be provided above 2'-6" from ffl or as advised by architect with necessary steam beach moulding finished with melamine. <b>The rate shall include necessary etching film / LOGO.</b>				
<b>i</b>	<b>WITH BOTH SIDE LAMINATE</b>	<b>SQM</b>	9.7		

SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
<b>3</b>	<b>SEMI HT. SEMI GLAZED PARTITION IN LAMINATE</b>				
	Specification same as 4 above but of low ht as per the drawing. A 70mm x 15mm steam beach moulding with champhered edge is to be provided on all external edges & finished in mellamine as per details. <b>Providing and Fixing inserted Soft board / White boards / Glass maintaining the vertical surface lines and no extra measurements would be taken for the soft boards / white boards / Glass.</b>				
i	<b>WITH BOTH SIDE LAMINATE</b>	SQ M	9.45		
ii	<b>WITH BOTH SIDE FINISHED IN High Gloss P U Coat over DUCO putty (FOR SW COUNTERS)</b>	SQ M	14.6		
<b>4</b>	<b>GLAZED PARTITIONS OVER WORKSATATIONS IN SINGLE WINDOW COUNTERS (FRONT SIDE)</b>				
	Providing and fixing glazed partition 450mm (Max Height) as per approved design of 12mm thk clear glass , mirror polished fixed with S S D Clips and grove made on Mullion Box as per design with a piegon hole at the centre as per design and as directed by the architect for Single Window Counter	SQ M	5.2		
<b>5</b>	<b>FULL HT. FULLY GLAZED PARTITION - WITH TOUGHENED GLASS</b>	SQM	9.5		
	Providing and fixing of Fixed Glass partition with 12mm thick toughened glass using PT Standard fittings like PT90/ PT92 of DORMA make at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealent wherever required. The top PT standard fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling.				
<b>C</b>	<b>PANELLING WORKS</b>				
<b>1</b>	<b>PANELLING WITH/ WITHOUT FRAMES</b>				
	Fabricating and fixing wall/column paneling with or without frame and the framing wherever necessary or as directed should consist of 37.5mm x 50mm x2mm thk Aluminium framework at spacing not exceeding 600mm bothways (horizontal and vertical). Paneling framework to be secured to wall surface/column surfac and should be fixed with 12 mm thk MR grade plywood in plumbline and surface finished with Laminate / Viner/ MDF JAALI/ LECQUERED GLASS/ BAFFLE ETC. as the case may be including polishing with melamine finish.				
i	<b>IN 1.0MM THK MERINO make METALLAM, MIRROR DECOR of shade- 98989V, STEEL MIRROR laminate (FOR COLUMNS)</b>	SQM	66.5		
ii	<b>IN WITH 12MM BWP PLY AND 6MM THK CORIAN FINISH OF APPROVED MAKE . The corian shall be embeded with lettering containing all the statutory notices of the bank, as per the BM's Directions and instructions</b>	SQM	5.2		
<b>2</b>	<b>COVERING OF COLUMN PANELLING WITH MDF LESSER CUT JAALI OF APPROVED DESIGN AND SHADE</b>	SQM	27.8		
	Providing and fixing in proper line and level, <b>6 mm thk MDF Jaali , lesser cut</b> , over existing Coulmn pannelled with Plywood and finished with approved shade of laminate as above by means of approved wooden screws/nails. The MDF surface to be finished with at least <b>three coats of DUCO paint</b> with putty, primer etc. complete so as to obtain the necessary shade and design as per the satisfaction of the architect/ Engineer-in-charge.				
<b>3</b>	<b>PANELLING WITH 4mm thk polished SS strips</b>	RM	34.8		
	Providing and fixing panelling on wall/ partition with 4mm thk polished SS strips of 304 grade - Bottomline make at palces as mentioned in the drawing and as directed by the architect. The rate includes cost of adhesives like fevicol,silicon, nails, screws and labour charges etc. all as per instructions of EIC / Architect.				
<b>4</b>	<b>PANELLING ON WALLWITH ACP / COMPACT LAMINATE</b>	SQM	78.5		
	Providing and fixing panelling on wall with or without frame. Framing shall consist of Aluminium Sections of 2"x1" as directed by Bank / Architect. This framing would be covered and finished with 3mm thick Aluminium Composite Panel/ Compact laminate. The rate shall inclusive of necessary fixtures and fittings, sealant etc. complete.				
<b>D</b>	<b>DOORS</b>				
<b>1</b>	<b>ENTRANCE DOORS - IN TOUGHENED GLASS</b>	SQM	7.48		
	Providing and fixing in position 12mm thick Clear Toughened Glass Door of AIS/SAINT GOBIN Make by using various glass patch fittings to be fixed with necessary fittings, duly finished without giving any load on the false ceiling by using necessary hardware to complete the job in all respects. Rate includes cost of glass door with approved hardware such as patch fitting, lock, handles, floor spring etc. of approved make. The contractor is advised to obtain approval for fixing details of the doors from EIC / Architect before execution of work. Schedule of hardwares per shutter is as follows:				
<b>A</b>	<b>OZONE Make: OSSPF-1</b> Over Panel Patch with pivot for 10 or 12mm thick Glass-Solid Stainless Steel in SS 304 grade - 1No.				
<b>B</b>	<b>OZONE Make: OSSPF-2</b> Top Patch Fitting for 10 or 12mm thick Glass-Solid Stainless Steel in SS 304 grade - 1No.				
<b>C</b>	<b>OZONE Make: OSSPF-3</b> Bottom Patch Fitting for 10 or 12mm thick Glass-Solid Stainless Steel in SS 304 grade - 1No.				
<b>D</b>	<b>OZONE Make: OSSPL-1</b> Patch Lock for 10 or 12mm thick Glass-Solid Stainless Steel in SS 304 grade - 1No.				
<b>E</b>	<b>OZONE Make: OSSPF-610</b> over Panel Side Panel Connector for 10 or 12mm thick Glass- Solid Stainless Steel in SS 304 grade - 1No.				
<b>F</b>	<b>OZONE Make: OCFH-100</b> Hydraulic Patch for 10 or 12mm thick Glass- Solid Stainless Steel in SS 304 grade - 1No.				
<b>G</b>	<b>OZONE Make: OGH-55</b> H-Type Handle, 25mm x 425mm Stainless Steel - 1 pair				

SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
2	<b>SOLID DOORS WITH/WITHOUT VISION PANEL- IN LAMINATE FINISH (with hardware fittings MAKE EVERITE / GOLDEN /HARDWIN /EVEREST) ( WITH OR WITH OUT VISION PANEL AS PER DIRECTION OF BANK / ARCHITECT</b>				
	Providing and fixing solid doors <b>with or without Vision Panel</b> of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 4mm thick approved <b>VEENER/LAMINATE</b> on both sides IN PU GLOSSY FINISH. A door frame of 3.5" x 2" steam beach section shall be provided finished in veener in PU GLOSSY FINISH. <b>Rate shall include Dead lock ( Godrej Make), floor springs / door closure ( as the case may be), door stopper, a pair of handles 12" SS Brushed finished, 5" hinges 4 Nos., buffers, tower bolts, etc with necessary hardware items</b> and with or with out door frames as mentioned above.				
A	<b>(Size as per Drawing) - IN LAMINATE FINISH - (WITH 2" x 3.5" finished size WOODEN FRAME)</b>				
i	With Door Closure	SQ M	5.2		
B	<b>(Size as per Drawing) - IN LAMINATE FINISH - WITHOUT FRAMES</b>				
i	With Door closure	SQ M	3.25		
3	<b>SINGLE WINDOW COUNTER DOORS (2' 0 X 4' 0" -IN LAMINATE FINISH)</b>	NOS	1		
	Providing and fixing solid doors of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 1mm thick approved laminate on both sides. The edges finished with steam beach lipping. A door frame of 3" x 1 1/2" teak wood / steam beach section shall be provided finished in mellamine. <b>Rate shall include approved make NIGHT LATCH LOCK, door closure, door stopper, a pair of handles 9" SS Brushed finished, 5" hinges 2 Nos., buffers, tower bolts, etc with necessary hardware items.</b>				
4	<b>TOILET DOORS (2'-6" X 7'-0" SIZE) ( with hardware fittings MAKE EVERITE / GOLDEN /HARDWIN /EVEREST)</b>				
	Providing and fixing solid doors of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 1mm thick approved laminate on both sides. The edges finished with steam beach lipping with melamine polish. A door frame of 2" x 3.5" Steam Beach wood section shall be provided finished in enamel paint. <b>Rate shall include approved door closure, door stopper, a pair of handles 5" SS Brushed finished, 5" hinges 4 Nos., buffers, tower bolts, etc with necessary hardware items and with or with out door frames as mentioned above</b>				
i	2'-6" x 7'-0" - IN LAMINATE FINISH - (WITH 2" x 3.5" WOODEN FRAME) With door closure	SQ M	3.3		
5	<b>UPVC / ALUMINIUM FABRICATION WORKS</b>				
a.	<b>UPVC LOUVERS VENTILATOR FOR TOILETS ( 3'X 2' WITH CUT OUT FOR EXHAUST FAN)</b>				
	Providing and fixing UPVC louvered Ventilators consists of 2" x 1" box type heavy duty approved make UPVC window frame. Adjustable UPVC louver system of same guage to have a 4" wide 6mm frosted glass for privacy. Provision for exhaust fan to be made and fixed frosted glass to be provided to adjustant to. Rate is inclusive all necessary fixtures and fittings, glass etc. complete in all respect.				
	<b>NOTE : Proper slots for exhaust fan should made in the lowered window in consultation with the Electrical Contractor</b>				
i	WITH UPVC SECTIONS ( As per Colour Specified by Architect)	SQ M	0.45		
E	<b>CARPENTRY WORKS 2</b>				
1	<b>UTILITY COUNTER (2'-6" TOP WIDE COUNTER WITH 1'-6" DEPTH STORAGE BELOW)</b>	RM	11.2		
	Providing and laying Utility Counter using 18mm thk.MR grade Plywood top, sides and back, with Storage units below the counter (450mm depth). 18mm thickMR grade Plywood shutter with box type higes of approved make & steam beach lipping finished with melamine. All external surfaces to be finished in 1.0 mm laminate (suede finish) of approved make.				
	Division of shutters shall be made equally according to the length of the storage. A 18mm thk.MR grade Plywood shelf on battens shall be provided in middle.				
	Suitable steam beach moulding ( as adviced by Bank/ Architect) 19mm x 7mm size, with mellamine shall be provided to the edge of the counter top. All internal surfaces shall be painted with 2 or more coats of synthetic enamel paint of approved colour and make over a coat of primer				
	<b>Rate shall be inclusive of all necessary approved fittings like hinges, locks, 100 mm long brushed finish handles,tower bolts and any necessary hardware items.</b>				
2	<b>PEGEON HOLE SHELVES FOR DESPATCH ROOM</b>	SQ M	1.5		
	Providing and fixing Pigeon Hole units of full height and 1'6" depth as per drwng. They shall be made of 19mm thk.Commercial grade Plywood/ Blockboard for both verticals and horizontal members. The bottom of the unit shall be at 3" from FFL. The top of storages shall touch the false ceiling level or 7'-0" ht. The facing edges of all ply wood sections should be finished with 1.0mm thick laminate. The size of pegeon hole to be adjusted equally as per the site condition. Approximate size of each pegeon hole should be 10" x 10" as per drawings and in consultation with Architect. All the internal surfaces shall be finished with paint.				
3	<b>SHUTTERS BELOW GRANITE COUNTERS IN PANTRY</b>	SQM	2.9		
	Providing and fixing 19mm thk. BWR ply shutters with ply frame, skirting gap as shown in the drg. shall be maintained. Division of shutters shall be made equally according to the length of the counter.				
	Shutters shall be hinged to the framework and finished with 1.0mm thk. Laminate (suede finish) of approved shade from outside, applied with approved oil paint from the inside and edges of shutters with steam beach lipping. Rate shall be inclusive of all necessary approved fittings like hinges, ball catch, handle, and any necessary hardware items.				

SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
4	<b>SIDE / CORNER TABLES</b>				
	Providing and making corner / side tables of above mentioned size as per drwng. Table top shall consist of 12 mm. Thk.float glass with champhered edge( bevelled edge) fitted to the frames with necessary arrangement. The base shall be made up of Steam beach wood frame as directed by the Bank / Architect. It should be with 4 Nos of 35mmx35mm for vertical members tied to each other with horizontal members of 20mm x 35mm frames at bottom and All wooden frames to be finished with melamine.				
a	<b>CORNER TABLES(1'-6" x 1'-6" x 1'-6"HT.)</b>				
(ii)	<b>FINISHED WITH 1.0MM thk Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE</b>	NOS	4		
b	<b>CENTER TABLES (1'-6" X 2'-6" X 1'-6"HT)</b>				
(ii)	<b>FINISHED WITH 1.0MM thk Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE</b>	NOS	2		
5	<b>PIN-UP BOARDS</b>	SQM	2.24		
	Providing and fixing pinup boards. It consist 12mm thick soft boards of good density to be mounted over 12mm thick Commercial grade Plywood/ Blockboard. The soft board will be covered with a plain fabric (approx Rs.250 /Rmts. of approved colour) from front and edges. Suitable steam beach moulding 25mm x 25mm size to be fixed on all four sides and will be finished in melamine polish.				
	<b>Note : Only soft bords provided on other than the partitions will be measured and soft board made in the partitions will be the part of the partition measurement (rate) and not consider separately.</b>				
6	<b>WALL MOUNTED WRITING LEDGE 1'- 3" TO 1'- 6" WIDE FINISHED WITH LAMINATE</b>	RM	2.12		
	Providing and Fixing wall mounted writing LEDGE as per design. The top and central partitions should be with 12mm thick float glass ( approved make) with champhered edge ( Bevelled edges) for top piece and verticals with edge polish. The glass should be supported on 18mm thickMR grade Plywood base, rear and sides fixed to the wall. The bottom ply piece to be supported additionally with 2 Nos. of SS Brackets. The exposed faces should be finished with 1.0mm thk laminate of approved shade				
7	<b>BACK OFFICE RUNNING COUNTER (2'-0" WIDE)</b>	RM	12.4		
(i)	Providing and laying a Plain running counter with only key board and Pencil Drawers at every 3'-0" length for over all size of top as mentioned bellow. It shall consist of 3/4" thk. Commercial grade Plywood/ Blockboard top as per design (double edge on the front and back with 1 1/2" thk half round moulding on the edges) supported on 3/4" thk. Commercial grade Plywood/ Blockboard verticals at every 3' length. Suitable (as per Architects design) wooden moulding with mellamine shall be provided to the edge of the top. The top of the counter should be finished with 1.0mm Laminate and all other external surfaces to be finished in 1.0 mm. Thk. Laminate (suede finish)of approved make.				
	1no. Computer key board tray (either ready made / made to the order as per architects design using 3/4" thk comm ply base and 1" x 2" round edged moulding on the front fixed with telescopic/double(Hafele/ebco make) approved sliders)				
	1no. Pencil drawer unit as shown in the drg shall be provided. Drawer shall consist of 3/4" thk. Commercial grade Plywood/ Blockboard sides, back and 1/2" thk. Commercial grade Plywood/ Blockboard base. Facia of drawers shall be of 3/4" thk. Commercial grade Plywood/ Blockboard finished in 1.0 mm. Thk. Laminate and with a wooden moulding on top/bottom edge for handle. Each drawer shall slide on a pair of hafele make telescopic drawer sliders. Each desk shall be provided with a 3" dia PVC wire manager at the given location and a metal CPU Trolley				
(ii)	Specifications same as above but only the table Top to be finished with approved shade of 6mm thk Corian , highly polished over Plywood/Blockboard , instead of laminate				
8	<b>KEY BOX</b>	NOS	1		
	Providing and fixing key box of size 1' 6"x1' 6"x 6" with all sides and back with 18mm thick Commercial grade Plywood/ Blockboard wood and lockable glass shutters in 18mm ply , with 5 mm glass. Necessary hooks to be provided inside the box. All exposed areas and inside to be finished with 1 mm thick laminate of approved shade. The edges of shutter and box to be lipped with steam beach beeding polished with melamine. <b>Rate shall be inclusive of all necessary approved fittings like hinges, locks, hooks etc. and any necessary hardware items.</b>				
9	<b>FULL HT / MEDIUM HT / LOW HT / OVER HEAD STORAGEES.</b>				
a	<b>LOW HT RUNNING STORAGE(450mmDX750 HT) (BACK CADENZA)</b>				
	Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 18" thkMR Grade plywood for top, base and sides and base 9mm thk MR Grade plywood, 18mm thk MR Grade plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate/ veneer/ on all the edges. All external surfaces shall be finished with 1.0MM thk laminate of Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE / 4.0 mm thk veneerof approved shade and make.Divisions of the shutter shall be make equally according to the length of the storage. A 3/4" thk MR Grade fixed ply wood shelf on battens shall be provided @16" intervals from the base. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All internal surfaces shall be painted with 2 or more coats of synthetic enamel paint of approved colour and make over a coat of primer.Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make				
i	<b>FINISHED WITH LAMINATE</b>	SQM	6.9		

SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
<b>b</b>	<b>OVER HEAD STORAGE(375mmDX450 HT)</b>				
	Providing and fixing over-head storages which consist of 18mm thk. BWP. ply shutter with box type hinges of approved make & Steam beach lipping with approved laminate/ veneer/ High Gloss P U Coat over DUCO putty, on all the edges. The shutter should be made of 18mm thk. BWP. Ply top, sides, rear and bottom. All external surfaces shall be finished with 1.0mm thk laminate/ 4.0 mm thk veneer/ High Gloss P U Coat over DUCO putty of approved shade and make. Division of the shutters shall be made equally according to the length of the storage. The edges of the shutters shall be provided with steam beach lipping. One Ply shelf of 18mm thick BWP.ply removable type supported on side steam beach wood battens on both sides (divided equally) shall be provided. All internal surfaces shall be painted with 2 or more coats of synthetic enamel paint of approved colour and make over a coat of primer.. Rate shall be inclusive of all necessary approved fittings like box type hinges, locks, tower bolts, 100mm SS Brush finished handle etc.				
<b>i</b>	<b>FINISHED WITH 1.0mm thk laminate of approved shade</b>	<b>SQM</b>	6.34		
<b>c</b>	<b>FULL HT. STORAGE</b>				
	Providing and fixing storage units of full height as per drwng. They shall consist of 18mm thk.BMR Grade plywood top, sides,back, bottom, shelves and shutters. The bottom of the storages shall be at 3" from FFL. The top of storages shall touch the false ceiling level or 7'-0" ht. The shutter with box type hinges of approved make & steam beach lipping finished with melamine with approved laminate on all the shutter edges. Division of the shutters shall be made equally according to the length of the storages ( as approved by Bank/ architect). All the external surfaces shall be finished with 1.0mm thk. Laminate (suede finish) of approved make. 18mm thk. MR Grade shelves removable type supported on side steam beach wood battens on both sides at 16" interval ( approximately / divided equally) shall be provided.All internal surfaces shall be painted with 2 or more coats of synthetic enamel paint of approved colour and make over a coat of primer. Rate shall be inclusive of all necessary approved fittings like hinges, locks, 150mm long SS brushed finish handles,tower bolts, locks and any necessary hardware items. The top ply edge should be fitted with 19mm x 7mm size steam beach moulding finished with melamine.				
<b>i</b>	<b>IN LAMINATE FINISH</b>	<b>SQM</b>	6		
<b>10</b>	<b>BOXING FOR ROLLING SHUTTER</b>				
	Providing & fixing ¾" commercial ply boxing for the rolling shutters made on necessary wooden framing/ aluminium framing as per design and as directed by the architect. The boxing shall be finished on all exposed sides by 3mm Aluminium Composite panel sheet of approved shade in approved pattern and design and as directed by the architect and all internal surfaces should be painted with enamel paint. <b>Note : rate shall include all necessary hardware fittings, etc.</b>				
<b>a</b>	<b>WITH ACP FINISH</b>	<b>SQM</b>	6.45		
<b>11</b>	<b>BANK'S LOGO ON ACRYLIC SHEET OF MAXIMUM SIZE 2' X 2'</b>	<b>NOS</b>	1		
	Supplying and Fixing Bank's Logo made of Stainless Steel of 1" thk and 24" overall diameter with polishing etc as per design and direction of Engineer Incharge. <b>Complete in all respects</b>				
<b>E</b>	<b>FALSE CEILING AND P.O.P. WORK</b>				
<b>1</b>	<b>s</b>	<b>SQM</b>	203		
	Providing and fixing ½" thk. Gypsum India board false ceiling at levels as shown in the drg. From FFL. Rate shall be inclusive of all Gypsum India components contained G.I. perimeter channels of size 0.55 thick having one flange of 20mm and another flange of 30mm and a web of 27mm alongwith perimeter of ceiling, screw fixed to brickwall/partition with the help of nylon sleeves and screws, at 610mm centres. The suspending G.I.intermediate channels of size 45mm, 0.9mm thick with two flanges of 15mm each from the soffit at 1220mm centres with ceiling angle of width 25mm x 10mm x 0.55 thick fixed to soffit with G.I. cleat and steel expansion fastners at every 610mm c/c. Ceiling sections of 0.55mm thickness having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to intermediate channel with the help of connecting clip and in direction perpendicular to the intermediate channel at 457mm centres. 12.5mm tapered edge Gypboard is then screw fixed to ceiling section with 25mm drywall screws driver or drilling machine with suitable attachment.				
	The boards are to be jointed and finished with POP so as to have a flush look and ready to receive paint which includes filling and finishing the tapered and square edge of the boards with jointing compound & joint paper tape. <b>Rate shall be inclusive of Cut outs for A/c machiness, spot lights, light fixtures, A/C. Grills, fire and security systems cut outs, All Sections should adhere to the manufacturers guidelines. Vertical sides visible will be measured..Rates Shall also be inclusive of vertical drop in ceiling upto 12" and no extra measurement for the drop upto 12" will be entertained.</b>				
<b>2</b>	<b>MODULAR FALSE CEILING - ARMSTRONG / equivalent make</b>	<b>SQM</b>	76.2		
	Providing and fixing Armstrong (Fine Fissured Micro Look with Tagular Edge using 15mm Grid sections) false ceiling of size 24"x24" at levels as shown in the drwng. from FFL. Rate shall be inclusive of providing the total system with installation etc.. The contractor has to maintain all tiles in good order and replace the defected tiles (at his own cost) before handing over the site for Branch Operations (till Inauguration).				
<b>3</b>	<b>FALSE CEILING IN PLY WITH PAINT FINISH</b>	<b>SQM</b>	9		
	Providing and fixing 12mm ply with necessary support from ceiling of 2"x2" Sal wood members provided at 2'-0" c/c and finished with paint of approved shade, with necessary primer etc. as per the approved design. ( Painting will be measured separately)				
<b>4</b>	<b>FALSE CEILING IN PLY WITH LAMINATE FINISH</b>	<b>SQM</b>	4.12		
	Providing and fixing 12mm ply with necessary support from ceiling of 2"x2" Sal wood members provided at 2'-0" c/c and finished with 1.0mm thk laminate of approved shade, as per the approved design.				

SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
<b>F</b>	<b>PAINTING</b>				
<b>1</b>	<b>PLASTIC EMULSION PAINT FOR GYPSUM CEILING</b>	<b>SQM</b>	205		
	Providing & applying plastic emulsion paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make , quality & finish shall be provided.				
<b>2</b>	<b>LUSTRE PAINT FOR WALLS IN BANKING HALL</b>	<b>SQM</b>	102		
	Providing & applying Luster Paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make, quality & shade shall be provided.				
<b>3</b>	<b>TEXTURED FINISH ON THEAME WALL OR AS DIRECTED BY THE ARCHITECT</b>	<b>SQM</b>	15		
	Providing & applying a coat of textured finish on walls and columns. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats of approved make, quality & shade shall be provided.				
<b>G</b>	<b>MISCELLANEOUS ITEMS</b>				
<b>1</b>	<b>VERTICAL BLINDS WITH SCOTCH GUARD</b>	<b>SQM</b>	18.2		
	Providing & fixing in place 100 mm. Vertical blinds of approved make, quality and colour shade & pattern. Rate shall include necessary scotch guard treatment on both sides. The overlaps should be uniform & adequate.				
<b>2</b>	<b>PLANTER BOX</b>				
	Supplying fitting & fixing the Wooden flower box of Size 450 X 450 X 450 mm made of 18 mm thick block board /MDF Board with top beading and outside teak veneering and lamination inside including vernishing/ painting all complete	<b>NOS</b>	8		
<b>3</b>	<b>Wallpaper</b>	<b>SQM</b>	14.3		
	Providing and fixing in position Wallpaper fixed with approved make of adhesive of approved Make and Design as Specified by the Architect				
<b>4</b>	<b>FROSTING FILM</b>	<b>SQM</b>	22		
	Providing and fixing Non-reflective matte, frosted, scratch resistant, high performance resin coated polyster film with required frosting pattern on the glass surface complete as per the directions of EIC/ Architect (Payment shall be made for the finished area of the film actually provided. No deduction shall be made for openings upto 0.1 Sq.m. area each and nothing shall be paid extra for making such openings.)				
<b>5</b>	<b>NOTICE BOARD</b>	<b>SQM</b>	2.4		
	Providing and fixing notice board size as required/ directed (matching with the panel of the cabin) with openable shutter on the front. Made out of 19mm thick Steam beech veneered block board frame and outer frame in 2 1/2" x 1 1/2" Steam beech wood section , concealed hinges , locking arrangement , and glass of (5.5mm thick) with rear panel of SITATEX board , covered with fabric of approved shade. (Basic rate Rs.100/-per mtr , 48" width), fixed to back ply 6mm thick . All complete including melamine polish in stain of required shade. All complete as per approval of the Architect / employer				
<b>6</b>	<b>Glass divider</b>	<b>NOS</b>	2		
	Providing & fixing og 12mm thick toughened frosted glass divider between machines (sixe 5' x 2" maximum as per design ) with necessary fittings & hardware as per the drawing. A 3" high wooden boxing shall be made in the floor to fix the glass and shall be a part of this item				
<b>7</b>	<b>COMPLAIN BOX</b>	<b>NOS</b>	1		
	Supplying and erecting complaint box (overall size 450 mm x 300 mm x 750 mm) made. of 19mm thick phenol formaldehyde bonded plyboard and the curved portion at top made out of 90 mm x 90 mm C.Pteak wood section. A slit opening of 10 mm x 150 mm is to be provided at the top of the box. An openable shutter of 259 mm x 262 mm size made of 19 mm thick phenol formaldehyde bonded block board is to be provided at 1.50 mm above finished floor level. All the exposed timber surfaces including. all free edges are to be finished with 1 rnm thick laminate sheet of combination shade .Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enoma!. paint of approved shade and quality over a coat of approved primer.Rate .to include cost of necessary hardware fittings e.g. brass hinges, lock, knob etc. of approved.designand quality.				
<b>TOTAL OF CARPENTRY WORKS (A)</b>					

SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
<b>FIRST FLOOR INTERIOR WORKS</b>					
SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
<b>A</b>	<b>CARPENTRY WORKS</b>				
<b>1</b>	<b>SINGLE WINDOW COUNTERS (SWO) WITH PARTITION AS PER THE DRAWING (6'1" X 5'3")</b>				
	Providing and fixing in position the Single Window Counter of internal size 1500mm x 2100mm, made of 18mm thick MR grade Plywood and drawers/cup boards with 12mm/8mm(6mm for Back only) MR grade Plywood as per the drawing and direction of Engineer in Charge with key board drawer and necessary arrangements for keeping the monitor, CPU,UPS , printers , battery and note counting machine etc as shown in the drawing . All the horizontal surfaces shall be provided with 6mm thk Corian, Frosty White fully polished and front edge bended as per design and vertical surfaces to be finished with 1.0MM thk laminate of Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE of approved shade as per approved design. All other sides (Customer Side and inside) and shutters of of side storage and Pedestal (Inside) shall be finished with 1.0MM thk laminate of Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE of approved shade as per approved design . It shall also consist of 12 mm thk clear Toughened glass of size 1'6 1/2 " x 4'3" on either sides as per the design and shape as shown in the detail drawing, fixed with necessary supports, on either sides at two ends as per design. All the Thickness shall be finished with Corian to desired polished and shade.The side storage/Cadenza shall have doors sliding on rollers as per disign with proper locking system. The key board drawer shall be provided with telescopic rail of "hettich/ Hafele" make . All internal surfaces shall be painted with 2 or more coats of synthetic enamel paint of approved colour and make over a coat of primer . The drawers /cup boards shall be fitted with best quality knob/handle and self locking arrangements of Hettich/ Hafele or equivalent make. The internal dimensions shall be 1500mm x 2100 mm as per drawing(Pl refer the Detail Drawing for Detailed Measurement and Specification). The rate to include all necessary charges of hardware materials, labour, taxes, transportation and contractor's overhead etc. Refer Detail Drawing of Single Window for reference. Rates Shall be inclusive of all locks , handles, magnets, Tower bolts etc and other hardware items as may be required and as asked by the architect/ engineer incharge	NOS	4		
<b>2</b>	<b>WORK STATIONS WITH SIDE STORAGE</b>				
<b>i</b>	<b>FOR OFFICERS (5'6" X 5'6")</b>				
	Providing and laying Officer's Workstations of over all size 1650mm x 1650 mm , of top as mentioned in the attached drawing. It shall consist of ¾" thk.MR grade Plywood top as per design (double edge on the front and back with ) supported on ¾" thk.MR grade Plywood verticals. Suitable (as per Architects design) . A ¾" thk.MR grade Plywood apron shall be provided as per Architects design with necessary pattern. The Table top and side storage alongwith all other external sides should be finished with 1.0MM thk laminate of Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE of approved shade as per approved design and a groove shall be maintained and provided at the joints between two colour shade. Each top should be provided with 3" dia PVC wire manager of approved quality near the CPU / Monitor , 1 no Metal Keyboard Tray of Best quality, 1 no Metal CPU Trolley at position as shown in drawing,.The side Storage shall have openable shutter on hinges with necessary locking arrangements. All exterior parts of the storage, including the shutters shall be finished with 1.0MM thk laminate of Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE of approved shade & colour over plywood . The Work station shall also consists of a pedestal for the table as per design with central locking system. The external face and sides of the pedestal shall be finished with with 1.0MM thk laminate of Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE of approved shade as per design .All internal surfaces shall be painted with 2 or more coats of synthetic enamel paint of approved colour and make over a coat of primer. All locks and other hardware fitting shall be strictly of Haffle or Hettich only and appropriate deduction/ penalisation as deemed fit by the enginger-in-charge/ architect shall be made if the same make for locks and all hardware fittings are not used by the contractor.	NOS	6		
<b>(i)(b)</b>	<b>Specification same as above but of overall size (6' X 6')</b>				
<b>ii</b>	<b>For Chief Manager(7'6" X 7'0")IN CORIAN TOP</b>				
	Providing and laying Chief Manager's Workstations of over all size 2250 mm X 2100 mm , of top as mentioned in the attached drawing. It shall consist of ¾" thk.MR grade Plywood top as per design (double edge on the front and back with ) supported on ¾" thk.MR grade Plywood verticals. Suitable (as per Architects design) . A ¾" thk.MR grade Plywood apron shall be provided as per Architects design with necessary pattern. The Table top and side storage shall be finished with 8mm thk Corian of approved shade and make. All other surfaces alongwith all other external to be finished with 1mm thk laminate of approved shade and pattern as per design of approved make .The Front Modesty Penel of the Table (Customer Side) shall be of 19 mm thk MR grade plywood and finished with laminate of approved shade and make as per the pattern as directed. Each top should be provided with 6mm thk toughened clear glass top , a 3" dia PVC wire manager of approved quality near the CPU / Monitor , 1 no Metal Keyboard Tray of Best quality, 1 no Metal CPU Trolley at position as shown in drawing, .The side Storage shall have openable shutter on hinges with necessary locking arrangements. All exterior parts of the storage, including the shutters shall be finished with 4mm thk veneer of approved shade and make in mellamine polish. The Work station shall also consists of a pedestal for the table as per design with central locking system. The external face and sides of the pedestal shall be finished with 4mm thk veneer of approved shade and make in mellamine polish.All internal surfaces shall be finished with 0.80 mm thk white laminate of approved make. All locks and other hardware fittings shall be of Hafele or Hettich make only.Rates Shall be inclusive of all locks , handles, magnets, Tower bolts etc and other hardware items as may be required and as asked by the architect/ engineer incharge	NOS	1		

SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
iii	<b>FOR GRAHAK MITRA AND TECH MITRA</b>				
	For Grahak Mitra ( size2'3" X 5'0") of top as mentioned in the attached drawing. It shall consist of ¾" thk.MR grade Plywood top as per design (double edge on the front and back with ) supported on ¾" thk.MR grade Plywood verticals. Suitable (as per Architects design) . A ¾" thk.MR grade Plywood apron shall be provided as per Architects design with necessary pattern. The Table top and side should be finished with with 1.0MM thk laminate of Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE of approved shade as per design.The Front Modesty Penel of the Table (Customer Side) shall be finished with with 1.0MM thk laminate of Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE of approved shade as per the approved design. Each top should be provided with a 3" dia PVC wire manager of approved quality near the CPU / Monitor , 1 no Metal Keyboard Tray of Best quality, 1 no Metal CPU Trolley at position as shown in drawing. .The Work station shall also consists of a pedestal for the table as per design with central locking system. The external face and sides of the pedestal shall be finished with 1.0mm thk laminate of approved shade as per design.All internal surfaces shall be painted with 2 or more coats of synthetic enamel paint of approved colour and make over a coat of primer. All locks and other hardware fittings to be used shall be strickly of Haffle/ Hettich make only.Rates Shall be inclusive of all locks , handles, magnets, Tower bolts etc and other hardware items as may be required and as asked by the architect/ engineer incharge.	NOS	2		
<b>B</b>	<b>PARTITIONS WORKS</b>				
	<b>Note :- The rate shall be include of frame work above false ceiling level. Measurement should be taken up to false ceiling level and visible portion only.</b>				
<b>1</b>	<b>FULL HT SOLID PARTITION</b>				
	Providing and fixing partition framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm x 3mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. The framing shall be fixed with 8 mm thk. BWPI ply on both side and either kept naked or finished with Laminate/ Veneer/ Corian/ Lecquered Glass of thickness 1mm / 4 mm / 6mm and 6 mm respectively, as per the description as in below . The shade of laminate / veneer/ corian/ lecquered glass should be as per the direction and design of the architect concerned. The skirting should be as per approved laminate as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete. <b>The edge beadings with steam beach wood should be finished with melamine.</b>				
i	<b>WITH BOTH SIDE LAMINATE</b>	SQM	14.2		
ii	<b>WITH ONE SIDE LAMINATE AND ONE SIDE 6MM THK LEACQUERED GLASS OF AQUA BLUE COLOUR OF APPROVED SHADE (BEHIND GRAHAK MITRA AND TECH MITRA AND BEHIND SELF SERVICE KIOSK)</b>	SQM	11.9		
<b>2</b>	<b>SEMI HT. SEMI GLAZED PARTITION IN LAMINATE</b>				
	Specification same as 4 above but of low ht as per the drawing. A 70mm x 15mm steam beach moulding with chamfered edge is to be provided on all external edges & finished in mellamine as per details. <b>Providing and Fixing inserted Soft board / White boards / Glass maintaining the vertical surface lines and no extra measurements would be taken for the soft boards / white boards / Glass.</b>				
i	<b>WITH BOTH SIDE LAMINATE</b>	SQ M	28.5		
ii	<b>WITH BOTH SIDE FINISHED IN High Gloss P U Coat over DUCO putty (FOR SW COUNTERS)</b>	SQ M	10.5		
<b>3</b>	<b>GLAZED PARTITIONS OVER WORKSATATIONS IN SINGLE WINDOW COUNTERS (FRONT SIDE)</b>				
	Providing and fixing glazed partition 450mm (Max Height) as per approved design of 12mm thk clear glass , mirror polished fixed with S D Clips and grove made on Mullion Box as per design with a pigeon hole at the centre as per design and as directed by the architect for Single Window Counter	SQ M	3.7		
<b>4</b>	<b>FULL HT. FULLY GLAZED PARTITION - WITH TOUGHENED GLASS</b>	SQM	18.7		
	Providing and fixing of Fixed Glass partition with 12mm thick toughened glass using PT Standard fittings like PT90/ PT92 of DORMA make at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealent wherever required. The top PT standard fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling.				
<b>C</b>	<b>PANELLING WORKS</b>				
<b>1</b>	<b>PANELLING WITH/ WITHOUT FRAMES</b>				
	Fabricating and fixing wall/column panelling with or without frame and the framing wherever necessary or as directed should consist of 37.5mm x 50mm x2mm thk Aluminium framework at spacing not exceeding 600mm bothways (horizontal and vertical). Panelling framework to be secured to wall surface/column surfac and should be fixed with 12 mm thk MR grade plywood in plumbline and surface finished with Laminate / Veneer/ MDF JAALI/ LECQUERED GLASS/ BAFFLE ETC. as the case may be including polishing with melamine finish.				
i	<b>IN 1.0MM THK MERINO make METALLAM, MIRROR DECOR of shade- 98989V, STEEL MIRROR laminate (FOR COLUMNS)</b>	SQM	67.5		
ii	<b>IN VENEER FINISH</b>	SQM	38.8		
iii	<b>IN WITH 12MM BWP PLY AND 6MM THK CORIAN FINISH OF APPROVED MAKE . The corian shall be embeded with lettering containing all the statutory notices of the bank, as per the BM's Directions and instructions</b>	SQM	5.2		
<b>2</b>	<b>COVERING OF COLUMN PANELLING WITH MDF LESSER CUT JAALI OF APPROVED DESIGN AND SHADE</b>	SQM	43.3		
	Providing and fixing in proper line and level, <b>6 mm thk MDF Jaali , lesser cut</b> , over existing Coulmn pannelled with Plywood and finished with approved shade of laminate as above by means of approved wooden screws/nails. The MDF surface to be finished with at least <b>three coats of DUCO paint</b> with putty, primer etc. complete so as to obtain the necessary shade and design as per the satisfaction of the architect/ Engineer-in-charge.				



SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
3	<b>PANNELLING WITH Hunter Douglas Tavola Baffle Panel</b>	SQM	25.6		
	Providing and fixing 50mm wide Baffle wall System consisting of INFILL PANELS, AXIOMS & Baffle 50 mm wide x 50mm height x 0.4mm thick square edged baffle in module 150mm c/c as per design complete with the accessories, including hanger, end cap, etc , having a length up to 4 mtrs, Coil Coated (chromatised for maximum bond between metal and paint, enamelled twice under high temperature, visible side with a full primer and finish coat, the inner side with a Primer coating and skin coat on a Continuous Paint line) corrosion resistant aluminium alloy for higher strength. The Panel shall be clipped to a baked enamelled Aluminium Panel carrier of 32 mm wide x 39 mm deep x 0.95 mm thick in standard length of 5 mtrs made of double baked enamelled Aluminium alloy AA 5050 (Al.mg) black with cut-outs to hold the panels The L shaped galvanised angle is suspended by means of suspension angle and anchor fasteners at a centre to centre distance of 1200mm. Clear gap between 2 consecutive panels should be 100 mm ( Wood finish). Rates shall be inclusive of supplying , installation, transportation all complete as per client's satisfaction				
4	<b>PANNELLING WITH 4 MM THK LECQUERED GLASS OF APPROVED SHADE</b>	SQM	14.1		
	Providing and fixing of wooden panelling made out of salwood frame at 2' centre to centre bothways in section size 2"x2" & covered with 9mm thick commercial ply and finished with 6mm "Planileque" lacquered glass of approved shade and make as per the design . Rate shall be inclusive of 100 mm high skirting of silver metal laminate as and where required and as per the direction of the Consultant Architect/ Engineer.The item shall also include supply and fixing of vinyl sticker/ frosted film sticker of Bank of Baroda logo and the lettering for Learning Centre and other matter as directed by the architect as per consultation and finalisation from the bank officials				
5	<b>PANNELLING WITH 4mm thk polished SS strips</b>	RM	28.1		
	Providing and fixing panelling on wall/ partition with 4mm thk polished SS strips of 304 grade - Bottomline make at palces as mentioned in the drawing and as directed by the architect. The rate includes cost of adhesives like fevicol,silicon, nails, screws and labour charges etc. all as per instructions of EIC / Architect.				
6	<b>6-10" dia BAMBOO IN BUNCH AS PER DESIGN AS COLUMN</b>	RM	73.2		
	Providing and fixing 6"-10" dia Bamboo, chemically treated for internal use, in required number as combination, as per design as directed by the architect. The bunch od bamboo should be fixed in size and pattern as directed by the architect, finished with necessary polishing and treated for antritermite and to be fit for internal use. The payment for this item shall be made as per the total length of all the bamboo in the bunch fitted after finishing as per design				
7	<b>PANELLING ON WALLS WITH 6-10" DIA SPLIT BAMBOO</b>	SQM	15		
	Panelling on walls/ partition with termite treated bamboo splitted into halves and used as per the pattern as mention in the detail drawing or as directed by the architect. The bamboo shall be wax polished as per architect's satisfaction as to the shade and shape as desired.It shall be fixed to the wall with nails of required sizes				
8	<b>PANELLING ON WALL / COLUMN IN ACP FINISH</b>	SQM	24.5		
	Providing and fixing panelling on wall with or without frame. Framing shall consist of Aluminium Sections of 2"x1" as directed by Bank / Architect. This framing would be covered and finished with 2mm thick "Aluminium Composite Panel". The rate shall inclusive of necessary fixtures and fittings, sealant etc. complete.				
D	<b>DOORS</b>				
1	<b>ENTRANCE DOORS - IN TOUGHENED GLASS</b>	SQM	6.18		
	Providing and fixing in position 12mm thick Clear Toughened Glass Door of AIS/SAINT GOBIN Make by using various glass patch fittings to be fixed with necessary fittings, duly finished without giving any load on the false ceiling by using necessary hardware to complete the job in all respects. Rate includes cost of glass door with approved hardware such as patch fitting, lock, handles, floor spring etc. of approved make. The contractor is advised to obtain approval for fixing details of the doors from EIC / Architect before execution of work. Schedule of hardwares per shutter is as follows:				
A	<b>OZONE Make: OSSPF-1</b> Over Panel Patch with pivot for 10 or 12mm thick Glass-Solid Stainless Steel in SS 304 grade - 1No.				
B	<b>OZONE Make: OSSPF-2</b> Top Patch Fitting for 10 or 12mm thick Glass-Solid Stainless Steel in SS 304 grade - 1No.				
C	<b>OZONE Make: OSSPF-3</b> Bottom Patch Fitting for 10 or 12mm thick Glass-Solid Stainless Steel in SS 304 grade - 1No.				
D	<b>OZONE Make: OSSPL-1</b> Patch Lock for 10 or 12mm thick Glass-Solid Stainless Steel in SS 304 grade - 1No.				
E	<b>OZONE Make: OSSPF-610</b> over Panel Side Panel Connector for 10 or 12mm thick Glass- Solid Stainless Steel in SS 304 grade - 1No.				
F	<b>OZONE Make: OCFH-100</b> Hydraulic Patch for 10 or 12mm thick Glass- Solid Stainless Steel in SS 304 grade - 1No.				
G	<b>OZONE Make: OGH-55</b> H-Type Handle, 25mm x 425mm Stainless Steel - 1 pair				
2	<b>SOLID DOORS WITH/WITHOUT VISION PANEL- IN LAMINATE FINISH (with hardware fittings MAKE EVERITE / GOLDEN /HARDWIN /EVEREST) ( WITH OR WITH OUT VISION PANEL AS PER DIRECTION OF BANK / ARCHITECT</b>				

SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
	Providing and fixing solid doors <b>with or without Vision Panel</b> of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 4mm thick approved <b>VEENER/LAMINATE</b> on both sides IN PU GLOSSY FINISH. A door frame of 3.5" x 2" steam beach section shall be provided finished in veener in PU GLOSSY FINISH. <b>Rate shall include Dead lock ( Godrej Make), floor springs / door closure ( as the case may be), door stopper, a pair of handles 12" SS Brushed finished, 5" hinges 4 Nos., buffers, tower bolts, etc with necessary hardware items</b> and with or with out door frames as mentioned above.				
<b>A</b>	<b>(Size as per Drawing) - IN LAMINATE FINISH - (WITH 2" x 3.5" finished size WOODEN FRAME)</b>				
i	With Door Closure	SQ M	8.13		
<b>B</b>	<b>(Size as per Drawing) - IN LAMINATE FINISH - WITHOUT FRAMES</b>				
i	With Door closure	SQ M	1.7		
<b>3</b>	<b>SINGLE WINDOW COUNTER DOORS (2' 0 X 4' 0" -IN LAMINATE FINISH)</b>	NOS	1		
	Providing and fixing solid doors of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 1mm thick approved laminate on both sides. The edges finished with steam beach lipping. A door frame of 3" x 1 1/2" teak wood / steam beach section shall be provided finished in mellamine. <b>Rate shall include approved make NIGHT LATCH LOCK, door closure, door stopper, a pair of handles 9" SS Brushed finished, 5" hinges 2 Nos., buffers, tower bolts, etc with necessary hardware items.</b>				
<b>4</b>	<b>TOILET DOORS (2'-6" X 7'-0" SIZE) ( with hardware fittings MAKE EVERITE / GOLDEN /HARDWIN /EVEREST)</b>				
	Providing and fixing solid doors of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 1mm thick approved laminate on both sides. The edges finished with steam beach lipping with melamine polish. A door frame of 2" x 3.5" Steam Beach wood section shall be provided finished in enamel paint. <b>Rate shall include approved door closure, door stopper, a pair of handles 5" SS Brushed finished, 5" hinges 4 Nos., buffers, tower bolts, etc with necessary hardware items and with or with out door frames as mentioned above</b>				
i	2'-6" x 7'-0" - IN LAMINATE FINISH - (WITH 2" x 3.5" WOODEN FRAME) With door closure	SQ M	4.88		
<b>E</b>	<b>CARPENTRY WORKS 2</b>				
<b>1</b>	<b>UTILITY COUNTER (2'-6" TOP WIDE COUNTER WITH 1'-6" DEPTH STORAGE BELOW)</b>	RM	3.12		
	Providing and laying Utility Counter using 18mm thk.MR grade Plywood top, sides and back, with Storage units below the counter (450mm depth). 18mm thickMR grade Plywood shutter with box type higes of approved make & steam beach lipping finished with melamine. All external surfaces to be finished in 1.0 mm laminate (suede finish) of approved make.				
	Division of shutters shall be made equally according to the length of the storage. A 18mm thk.MR grade Plywood shelf on battens shall be provided in middle.				
	Suitable steam beach moulding ( as adviced by Bank/ Architect) 19mm x 7mm size, with melamine shall be provided to the edge of the counter top. All internal surfaces shall be painted with 2 or more coats of synthetic enamel paint of approved colour and make over a coat of primer				
	<b>Rate shall be inclusive of all necessary approved fittings like hinges, locks, 100 mm long brushed finish handles,tower bolts and any necessary hardware items.</b>				
<b>2</b>	<b>PEGEON HOLE SHELVES FOR DESPATCH ROOM</b>	SQ M	1.5		
	Providing and fixing Pegeon Hole units of full height and 1'6" depth as per drwng. They shall be made of 19mm thk.Commercial grade Plywood/ Blockboard for both verticals and horizontal members. The bottom of the unit shall be at 3" from FFL. The top of storages shall touch the false ceiling level or 7'-0" ht. The facing edges of all ply wood sections should be finished with 1.0mm thick laminate. The size of pegeon hole to be adjusted equally as per the site condition. Approximate size of each pegeon hole should be 10" x 10" as per drawings and in consultation with Architect. All the internal surfaces shall be finished with paint.				
<b>3</b>	<b>SHUTTERS BELOW GRANITE COUNTERS IN PANTRY</b>	SQM	3.49		
	Providing and fixing 19mm thk. BWR ply shutters with ply frame, skirting gap as shown in the drg. shall be maintained. Division of shutters shall be made equally according to the length of the counter.				
	Shutters shall be hinged to the framework and finished with 1.0mm thk. Laminate (suede finish) of approved shade from outside, applied with approved oil paint from the inside and edges of shutters with steam beach lipping. Rate shall be inclusive of all necessary approved fittings like hinges, ball catch, handle, and any necessary hardware items.				
<b>5</b>	<b>DRESSING MIRROR FOR LOCKER ROOM</b>	NOS	1		
	Providing and fixing dressing table with mirror of size 1' 6" x 3' 0" using 12mm thk. Commercial grade Plywood/ Blockboard with 6mm thk. clear Mirror fixed on the wall and tray of size 1' 6" x 1' 6" with one drawer for cosmetics. <b>(Measurement is measured only for mirror)</b>				
<b>6</b>	<b>SIDE / CORNER TABLES</b>				
	Providing and making corner / side tables of above mentioned size as per drwng. Table top shall consist of 12 mm. Thk.float glass with chamfered edge( bevelled edge) fitted to the frames with necessary arrangement. The base shall be made up of Steam beach wood frame as directed by the Bank / Architect. It should be with 4 Nos of 35mmx35mm for vertical members tied to each other with horizontal members of 20mm x 35mm frames at bottom and All wooden frames to be finished with melamine.				
<b>a</b>	<b>CORNER TABLES(1'-6" x 1'-6" x 1'-6"HT.)</b>				
(ii)	<b>FINISHED WITH 1.0MM thk Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE</b>	NOS	8		
<b>b</b>	<b>CENTER TABLES (1'-6" X 2'-6" X 1'-6"HT)</b>				

SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
(ii)	<b>FINISHED WITH 1.0MM thk Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE</b>	NOS	4		
7	<b>PIN-UP BOARDS</b>	SQM	4.46		
	Providing and fixing pinup boards. It consist 12mm thick soft boards of good density to be mounted over 12mm thick Commercial grade Plywood/ Blockboard. The soft board will be covered with a plain fabric (approx Rs.250 /Rmts. of approved colour) from front and edges. Suitable steam beach moulding 25mm x 25mm size to be fixed on all four sides and will be finished in melamine polish.				
	<b>Note : Only soft bords provided on other than the partitions will be measured and soft board made in the partitions will be the part of the partition measurement (rate) and not consider separately.</b>				
8	<b>WALL MOUNTED WRITING LEDGE 1'- 3" TO 1'- 6" WIDE FINISHED WITH LAMINATE</b>	RM	2.68		
	Providing and Fixing wall mounted writing LEDGE as per design. The top and central partitions should be with 12mm thick float glass ( approved make) with champhered edge ( Bevelled edges) for top piece and verticals with edge polish. The glass should be supported on 18mm thickMR grade Plywood base, rear and sides fixed to the wall. The bottom ply piece to be supported additionally with 2 Nos. of SS Brackets. The exposed faces should be finished with 1.0mm thk laminate of approved shade				
9	<b>KEY BOX</b>	NOS	1		
	Providing and fixing key box of size 1' 6"x1' 6"x 6" with all sides and back with 18mm thick Commercial grade Plywood/ Blockboard wood and lockable glass shutters in 18mm ply , with 5 mm glass. Necessary hooks to be provided inside the box. All exposed areas and inside to be finished with 1 mm thick laminate of approved shade. The edges of shutter and box to be lipped with steam beach beeding polished with melamine. <b>Rate shall be inclusive of all necessary approved fittings like hinges, locks, hooks etc. and any necessary hardware items.</b>				
10	<b>FULL HT / MEDIUM HT / LOW HT / OVER HEAD STORAGEES.</b>				
a	<b>LOW HT RUNNING STORAGE(450mmDX750 HT) (BACK CADENZA)</b>				
	Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 18" thkMR Grade plywood for top, base and sides and base 9mm thk MR Grade plywood, 18mm thk MR Grade plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate/ veneer/ on all the edges. All external surfaces shall be finished with 1.0MM thk laminate of Merino Make UNI MR+UNI COLOUR TUFF GLOSS LAMINATE / 4.0 mm thk veneerof approved shade and make.Divisions of the shutter shall be make equally according to the length of the storage. A 3/4" thk MR Grade fixed ply wood shelf on battens shall be provided @16" intervals from the base. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All internal surfaces shall be painted with 2 or more coats of synthetic enamel paint of approved colour and make over a coat of primer.Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make				
i	<b>FINISHED WITH LAMINATE</b>	SQM	23.2		
ii	<b>IN VENEER FINISH</b>	SQM	3.31		
b	<b>OVER HEAD STORAGE(375mmDX450 HT)</b>				
	Providing and fixing over-head storagees which consist of 18mm thk. BWP. ply shutter with box type higes of approved make & Steam beach lipping with approved laminate/ veneer/ High Gloss P U Coat over DUCO putty, on all the edges. The shutter should be made of of 18mm thk. BWP. Ply top, sides, rear and bottom. All external surfaces shall be finished with 1.0mm thk laminate/ 4.0 mm thk veneer/ High Gloss P U Coat over DUCO putty of approved shade and make. Division of the shutters shall be made equally according to the length of the storage. The edges of the shutters shall be provided with steam beach lipping. One Ply shelf of 18mm thick BWP.ply removable type supported on side steam beach wood battens on both sides (divided equally) shall be provided. All internal surfaces shall be painted with 2 or more coats of synthetic enamel paint of approved colour and make over a coat of primer.. Rate shall be inclusive of all necessary approved fittings like box type hinges, locks, tower bolts, 100mm SS Brush finished handle etc.				
i	<b>FINISHED WITH 1.0mm thk laminate of approved shade</b>	SQM	6.49		
c	<b>FULL HT. STORAGE</b>				
	Providing and fixing storage units of full height as per drwng. They shall consist of 18mm thk.BMR Grade plywood top, sides,back, bottom, shelves and shutters. The bottom of the storagees shall be at 3" from FFL. The top of storagees shall touch the false ceiling level or 7'-0" ht. The shutter with box type higes of approved make & steam beach lipping finished with melamine with approved laminate on all the shutter edges. Division of the shutters shall be made equally according to the length of the storagees ( as approved by Bank/ architect). All the external surfaces shall be finished with 1.0mm thk. Laminate (suede finish) of approved make. 18mm thk. MR Grade shelves removable type supported on side steam beach wood battens on both sides at 16" interval ( approximately / divided equally) shall be provided.All internal surfaces shall be painted with 2 or more coats of synthetic enamel paint of approved colour and make over a coat of primer. Rate shall be inclusive of all necessary approved fittings like hinges, locks, 150mm long SS brushed finish handles,tower bolts, locks and any necessary hardware items. The top ply edge should be fitted with 19mm x 7mm size steam beach moulding finished with melamine.				
i	<b>IN LAMINATE FINISH</b>	SQM	6.94		

SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
12	<b>BOXING FOR ROLLING SHUTTER</b>				
	Providing & fixing ¾" commercial ply boxing for the rolling shutters made on necessary wooden framing/ aluminium framing as per design and as directed by the architect. The boxing shall be finished on all exposed sides by 3mm Aluminium Composite panel sheet of approved shade in approved pattern and design and as directed by the architect and all internal surfaces should be painted with enamel paint. <b>Note : rate shall include all necessary hardware fittings, etc.</b>				
a	<b>WITH ACP FINISH</b>	SQM	2.9		
13	<b>BANK'S LOGO ON ACRYLIC SHEET OF MAXIMUM SIZE 2' X 2'</b>	NOS	1		
	Supplying and Fixing Bank's Logo made of Stainless Steel of 1" thk and 24" overall diameter with polishing etc as per design and direction of Engineer Incharge. <b>Complete in all respects</b>				
E	<b>FALSE CEILING AND P.O.P. WORK</b>				
1	<b>FALSE CEILING WITH POP FINISH - GYP BOARD</b>	SQM	138		
	Providing and fixing ½" thk. Gypsum India board false ceiling at levels as shown in the drg. From FFL. Rate shall be inclusive of all Gypsum India components contained G.I. perimeter channels of size 0.55 thick having one flange of 20mm and another flange of 30mm and a web of 27mm alongwith perimeter of ceiling, screw fixed to brickwall/partition with the help of nylon sleeves and screws, at 610mm centres. The suspending G.I.intermediate channels of size 45mm, 0.9mm thick with two flanges of 15mm each from the soffit at 1220mm centres with ceiling angle of width 25mm x 10mm x 0.55 thick fixed to soffit with G.I. cleat and steel expansion fastners at every 610mm c/c. Ceiling sections of 0.55mm thickness having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to intermediate channel with the help of connecting clip and in direction perpendicular to the intermediate channel at 457mm centres. 12.5mm tapered edge Gypboard is then screw fixed to ceiling section with 25mm drywall screws driver or drilling machine with suitable attachment.				
	The boards are to be jointed and finished with POP so as to have a flush look and ready to receive paint which includes filling and finishing the tapered and square edge of the boards with jointing compound & joint paper tape. <b>Rate shall be inclusive of Cut outs for A/c machiness, spot lights, light fixtures, A/C. Grills, fire and security systems cut outs</b> , All Sections should adhere to the manufacturers guidelines. Vertical sides visible will be measured. <b>Rates Shall also be inclusive of vertical drop in ceiling upto 12" and no extra measurement for the drop upto 12" will be entertained.</b>				
2	<b>MODULAR FALSE CEILING - ARMSTRONG / equivalent make</b>	SQM	146		
	Providing and fixing Armstrong (Fine Fissured Micro Look with Tagular Edge using 15mm Grid sections) false ceiling of size 24"x24" at levels as shown in the drwng. from FFL. Rate shall be inclusive of providing the total system with installation etc.. The contractor has to maintain all tiles in good order and replace the defected tiles (at his own cost) before handing over the site for Branch Operations (till Inauguration).				
3	<b>ASBESTOS SHEET CEILING</b>	SQM	10.5		
	Providing and fixing A.C BOARD false ceiling of size 24"x24" at levels as shown in the drwng. from FFL. Rate shall be inclusive of providing the total system with installation etc.. The contractor has to maintain all tiles in good order and replace the defected tiles (at his own cost) before handing over the site for Branch Operations (till Inauguration).				
4	<b>FALSE CEILING IN PLY WITH PAINT FINISH</b>	SQM	22.3		
	Providing and fixing 12mm ply with necessary support from ceiling of 2"x2" Sal wood members provided at 2'-0" c/c and finished with paint of approved shade, with necessary primer etc. as per the approved design. ( Painting will be measured separately)				
5	<b>FALSE CEILING IN PLY WITH VENEER IN MELLAMINE POLISH</b>	SQM	5.5		
	Providing and fixing 12mm ply with necessary support from ceiling of 2"x1" Sal wood members provided at 2'-0" c/c and finished in veneer with mellamine polish of approved shade.				
6	<b>FALSE CEILING IN PLY WITH LAMINATE FINISH</b>	SQM	8.26		
	Providing and fixing 12mm ply with necessary support from ceiling of 2"x2" Sal wood members provided at 2'-0" c/c and finished with 1.0mm thk laminate of approved shade, as per the approved design.				
F	<b>PAINTING</b>				
1	<b>PLASTIC EMULSION PAINT FOR GYPSUM CEILING</b>	SQM	140		
	Providing & applying plastic emulsion paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make , quality & finish shall be provided.				
2	<b>LUSTRE PAINT FOR WALLS IN BANKING HALL</b>	SQM	132		
	Providing & applying Luster Paint on walls, columns & ceilings. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats to get evenly spread quality finish (roller finish) of approved make, quality & shade shall be provided.				
3	<b>TEXTURED FINISH ON THEAME WALL OR AS DIRECTED BY THE ARCHITECT</b>	SQM	34.8		
	Providing & applying a coat of textured finish on walls and columns. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats of approved make, quality & shade shall be provided.				
G	<b>MISCELLANEOUS ITEMS</b>				
1	<b>VERTICAL BLINDS WITH SCOTCH GUARD</b>	SQM	44.5		
	Providing & fixing in place 100 mm. Vertical blinds of approved make, quality and colour shade & pattern. Rate shall include necessary scotch guard treatment on both sides. The overlaps should be uniform & adequate.				

SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
2	<b>PLANTER BOX</b>				
	Supplying fitting & fixing the Wooden flower box of Size 450 X 450 X 450 mm made of 18 mm thick block board /MDF Board with top beading and outside teak veneering and lamination inside including vernishing/ painting all complete	NOS	12		
3	<b>ANTI STATIC LUXURY WOVEN CARPET FLOORING</b>	SQM	62.5		
	Providing supplying and fixing 2.5MM -2.8MM thick, Sound Absorbent, Anti Bacterial, Stain, Water and Oil Resistant, Higenic and Easily Installable, LUXURY WOVEN VINYL FLOORING suitable for Office, Corporates and Public area having overall length of 20-25 metres and Roll width of 1.80 m, having basic rates Rs 155-180/sft, of shade as mentioned below- Conference/FAO- NATURAL SOUL, Reception/passage and other area- NATURAL CORAL & NATURAL BLACK( Special design below reception table as heighlitters only) on the existing floor with proper adhesive. The rate to include preparation of sub-floor to even surface including all materials, labour, transportation , adhesive, fixing all complete as per the direction of the engineer incharge				
4	<b>Wallpaper</b>	SQM	19		
	Providing and fixing in position Wallpaper fixed with approved make of adhesive of approved Make and Design as Specified by the Architect				
5	<b>FROSTING FILM</b>	SQM	24.8		
	Providing and fixing Non-reflective matte, frosted, scratch resistant, high performance resin coated polyster film with required frosting pattern on the glass surface complete as per the directions of EIC/ Architect (Payment shall be made for the finished area of the film actually provided. No deduction shall be made for openings upto 0.1 Sq.m. area each and nothing shall be paid extra for making such openings.)				
6	<b>CLAY MURAL ON THEAME WALL</b>	LS	1		
a	Supplying erecting & fixing 2 -Dimensional fibre art work depicting our regional rich culture will be created of size 6ft x 4ft x 3" depth as shown in the drawing. Mural embossed art work shall be created in the media of clay on wooden base according to the drawing. Initially Art work shall be made with clay in accordance to the drawing. After completing the detailed work POPmould will be prepared. Once it dries and harden, fiber casting of all moulds will be processed. The fibre art work taken out of the moulds will be fine polished and painting will be done. After this whole Mural relief work with the suitable frame will be placed (fixed) in the both wall. The Mural art will be given proper lighting with LED lights all around aluminum profile. For further details please refer Technical Speciofications of this Art work attached with this document.				
b	Supplying erecting & fixing 2 -Dimensional fibre art work depicting our regional rich culture will be created of size 4ft x 3ft x 3" depth as shown in the drawing. Mural embossed art work shall be created in the media of clay on wooden base according to the drawing. Initially Art work shall be made with clay in accordance to the drawing. After completing the detailed work POPmould will be prepared. Once it dries and harden, fiber casting of all moulds will be processed. The fibre art work taken out of the moulds will be fine polished and painting will be done. After this whole Mural relief work with the suitable frame will be placed (fixed) in the both wall. The Mural art will be given proper lighting with LED lights all around aluminum profile. For further details please refer Technical Speciofications of this Art work attached with this document.	LS	1		
7	<b>STAINLESS STEEL TOILET SIGNAGES FOR WALLS/ PARTITION/ DOORS</b>	NOS	8		
	Supplying & fixing in position as directed by the architect, toilet Signages made of thickness 0.5mm and size 150mm x 100mm, made from high quality stainless steel, UV resistant and made for high quality vinyls with hater proof and heat resistance. It shall be fixed with double sided adhesive tape				
8	<b>DISCUSSION/ DINING TABLE</b>	NOS	7		
	Providing and making a table of over all size of top as mentioned above. It shall consist of two nos BWP ply 18/19mm and 6/8mm thk sandwiched as per design as Table Top and finished with 1mm thk laminate of approved shade , pattern & make.It shall be supported on 18/19mm thk comercial ply base as per the design as in the detailed drawing (as approved by the architect), finished with 1.0 mm thk laminate of approved shade.				
9	<b>NOTICE BOARD</b>	SQM	2.4		
	Providing and fixing notice board size as required/ directed (matching with the panel of the cabin) with openable shutter on the front. Made out of 19mm thick Steam beech veneered block board frame and outer frame in 2 1/2" x 1 1/2" Steam beech wood section , concealed hinges , locking arrangement , and glass of (5.5mm thick) with rear panel of SITATEX board , covered with fabric of approved shade. (Basic rate Rs.100/-per mtr , 48" width), fixed to back ply 6mm thick . All complete including melamine polish in stain of required shade. All complete as per approval of the Architect / employer				
10	<b>DISMENTLLING AND DEMOLISHING WORKS</b>	LS	1		
	Dismantelling works includes dismantelling of 6"/9" thk br. Wall, partition works, work stations, false ceings, pannellings, metal works, removal of doors, windows,etc. Dismantalling of platforms , counters, skirting, and as all as may be required for preparing the site for the interior furnishing work of the premises. The rate shall include removal of debris from the site				
11	<b>Glass divider</b>	NOS	3		
	Providing & fixing og 12mm thick toughened frosted glass divider between machines (sixe 5' x 2" maximum as per design ) with necessary fittings & hardware as per the drawing. A 3" high wooden boxing shall be made in the floor to fix the glass and shall be a part of this item				
12	<b>Minor patch tiling works to cover the floor with vitrified tiles of matching shade at the point where Br.walls is dismantelled for door opennings</b>	LS	1		

SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
13	<b>COMPLAIN BOX</b>	NOS	1		
	Supplying and erecting complaint box (overall size 450 mm x 300 mm x 750 mm) made. of 19mm thick phenol formaldehyde bonded plyboard and the curved portion at top made out of 90 mm x 90 mm C.Pteak wood section. A slit opening of 10 mm x 150 mm is to be provided at the top of the box. An openable shutter of 259 mm x 262 mm size made of 19 mm thick phenol formaldehyde bonded block board is to be provided at 1.50 mm above finished floor level. All the exposed timber surfaces including. all free edges are to be finished with 1 rnm thick laminate sheet of combination shade .Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enoma! . paint of approved shade and quality over a coat of approved primer.Rate .to include cost of necessary hardware fittings e.g. brass hinges, lock, knob etc. of approved.design and quality.				
	<b>TOTAL OF CARPENTRY WORKS (B)</b>				
<b>E-LOBBY</b>					
SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
	<b>CARPENTRY WORKS</b>				
<b>A</b>	<b>PARTITIONS WORKS</b>				
	<b>Note :- The rate shall be include of frame work above false ceiling level. Measurement should be taken up to false ceiling level and visible portion only.</b>				
<b>1</b>	<b>FULL HT SOLID PARTITION</b>				
	Providing and fixing partition framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm x 3mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. The framing shall be fixed with 8 mm thk. BWPI ply on both side and either kept naked or finished with Laminate/ Veneer/ Corian/ Lecquered Glass of thickness 1mm / 4 mm / 6mm and 6 mm respectively, as per the description as in below . The shade of laminate / vineer/ corian/ lecquered glass should be as per the direction and design of the architect concerned. The skirting should be as per approved laminate as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete. <b>The edge beadings with steam beach wood should be finished with melamine.</b>				
i	<b>WITH BOTH SIDE LAMINATE</b>	SQM	12		
<b>2</b>	<b>FULL HT. FULLY GLAZED PARTITION - WITH TOUGHENED GLASS</b>	SQM	8.5		
	Providing and fixing of Fixed Glass partition with 12mm thick toughened glass using PT Standard fittings like PT90/ PT92 of DORMA make at the top and grouting at the bottom with U - Shaped Aluminium rails and EPDM gaskets including cutting, making holes in glass and fixing the fittings in floors, false ceiling etc. and making the same good with necessary screw, sealent wherever required. The top PT standard fittings to be fitted to the Wooden section fixed above the Gypsum board in the level of GI channels of False ceiling.				
<b>B</b>	<b>PANELLING WORKS</b>				
<b>1</b>	<b>PANELLING WITH/ WITHOUT FRAMES</b>				
	Fabricating and fixing wall/column paneling with or without frame and the framing wherever necessary or as directed should consist of 37.5mm x 50mm x2mm thk Aluminium framework at spacing not exceeding 600mm bothways (horizontal and vertical). Paneling framework to be secured to wall surface/column surface and should be fixed with 12 mm thk MR grade plywood in plumblin and surface finished with Laminate / Veneer/ MDF JAALI/ LECQUERED GLASS/ BAFFLE ETC. as the case may be including polishing with melamine finish.				
i	<b>IN 1.0MM THK MERINO make METALLAM, MIRROR DECOR of shade- 98989V, STEEL MIRROR laminate (FOR COLUMNS)</b>	SQM	31.2		
<b>2</b>	<b>COVERING OF COLUMN PANELLING WITH MDF LESSER CUT JAALI OF APPROVED DESIGN AND SHADE</b>	SQM	12.3		
	Providing and fixing in proper line and level, <b>6 mm thk MDF Jaali , lesser cut</b> , over existing Coulmn pannelled with Plywood and finished with approved shade of laminate as above by means of approved wooden screws/nails. The MDF surface to be finished with at least <b>three coats of DUCO paint</b> with putty, primer etc. complete so as to obtain the necessary shade and design as per the satisfaction of the architect/ Engineer-in-charge.				
<b>3</b>	<b>PANNELLING WITH Hunter Douglas Tavola Baffle Panel</b>	SQM	6.4		
	Providing and fixing 50mm wide Baffle wall System consisting of INFILL PANELS, AXIOMS & Baffle 50 mm wide x 50mm height x 0.4mm thick square edged baffle in module 150mm c/c as per design complete with the accessories, including hanger, end cap, etc , having a length up to 4 mtrs, Coil Coated (chromatised for maximum bond between metal and paint, enamelled twice under high temperature, visible side with a full primer and finish coat, the inner side with a Primer coating and skin coat on a Continuous Paint line) corrosion resistant aluminium alloy for higher strength.  The Panel shall be clipped to a baked enamelled Aluminium Panel carrier of 32 mm wide x 39 mm deep x 0.95 mm thick in standard length of 5 mtrs made of double baked enamelled Aluminium alloy AA 5050 (Al.mg) black with cut-outs to hold the panels The L shaped galvanised angle is suspended by means of suspension angle and anchor fasteners at a centre to centre distance of 1200mm. Clear gap between 2 consecutive panels should be 100 mm ( Wood finish). Rates shall be inclusive of supplying , installation, transportation all complete as per client's satisfaction				

SL	DESCRIPTION	UNIT	QNTY	RATE	AMOUNT
4	<b>PANNELLING WITH 4 MM THK LECQUERED GLASS OF APPROVED SHADE</b>	SQM	4.8		
	Providing and fixing of wooden panelling made out of salwood frame at 2' centre to centre bothways in section size 2"x2" & covered with 9mm thick commercial ply and finished with 6mm "Planileque" lacquered glass of approved shade and make as per the design . Rate shall be inclusive of 100 mm high skirting of silver metal laminate as and where required and as per the direction of the Consultant Architect/ Engineer.The item shall also include supply and fixing of vinyl sticker/ frosted film sticker of Bank of Baroda logo and the lettering for Learning Centre and other matter as directed by the architect as per consultation and finalisation from the bank officials				
5	<b>PANELLING ON WALL / COLUMN IN ACP FINISH</b>	SQM	4.68		
	Providing and fixing panelling on wall with or without frame. Framing shall consist of Aluminium Sections of 2"x1" as directed by Bank / Architect. This framing would be covered and finished with 2mm thick "Aluminium Composite Panel". The rate shall inclusive of necessary fixtures and fittings, sealant etc. complete.				
C	<b>DOORS</b>				
1	<b>ENTRANCE DOORS - IN TOUGHENED GLASS</b>	SQM	2.3		
	Providing and fixing in position 12mm thick Clear Toughened Glass Door of AIS/SAINT GOBIN Make by using various glass patch fittings to be fixed with necessary fittings, duly finished without giving any load on the false ceiling by using necessary hardware to complete the job in all respects. Rate includes cost of glass door with approved hardware such as patch fitting, lock, handles, floor spring etc. of approved make. The contractor is advised to obtain approval for fixing details of the doors from EIC / Architect before execution of work. Schedule of hardwares per shutter is as follows:				
A	<b>OZONE Make: OSSPF-1</b> Over Panel Patch with pivot for 10 or 12mm thick Glass-Solid Stainless Steel in SS 304 grade - 1No.				
B	<b>OZONE Make: OSSPF-2</b> Top Patch Fitting for 10 or 12mm thick Glass-Solid Stainless Steel in SS 304 grade - 1No.				
C	<b>OZONE Make: OSSPF-3</b> Bottom Patch Fitting for 10 or 12mm thick Glass-Solid Stainless Steel in SS 304 grade - 1No.				
D	<b>OZONE Make: OSSPL-1</b> Patch Lock for 10 or 12mm thick Glass-Solid Stainless Steel in SS 304 grade - 1No.				
E	<b>OZONE Make: OSSPF-610</b> over Panel Side Panel Connector for 10 or 12mm thick Glass- Solid Stainless Steel in SS 304 grade - 1No.				
F	<b>OZONE Make: OCFH-100</b> Hydraulic Patch for 10 or 12mm thick Glass- Solid Stainless Steel in SS 304 grade - 1No.				
G	<b>OZONE Make: OGH-55</b> H-Type Handle, 25mm x 425mm Stainless Steel - 1 pair				
2	<b>SOLID DOORS WITH/WITHOUT VISION PANEL- IN LAMINATE FINISH (with hardware fittings MAKE EVERITE / GOLDEN /HARDWIN /EVEREST) ( WITH OR WITH OUT VISION PANEL AS PER DIRECTION OF BANK / ARCHITECT</b>				
	Providing and fixing solid doors <b>with or without Vision Panel</b> of sizes as shown in the drawing. The door shutter shall of 35 mm thick flush shutter of approved make and finished with 4mm thick approved <b>VEENER/LAMINATE</b> on both sides IN PU GLOSSY FINISH. A door frame of 3.5" x 2" steam beach section shall be provided finished in veener in PU GLOSSY FINISH. <b>Rate shall include Dead lock ( Godrej Make), floor springs / door closure ( as the case may be), door stopper, a pair of handles 12" SS Brushed finished, 5" hinges 4 Nos., buffers, tower bolts, etc with necessary hardware items</b> and with or with out door frames as mentioned above.				
A	<b>(Size as per Drawing) - IN LAMINATE FINISH - WITHOUT FRAMES</b>				
i	With Door closure	SQ M	1.65		
D	<b>FALSE CEILING AND P.O.P. WORK</b>				
1	<b>FALSE CEILING WITH POP FINISH - GYP BOARD</b>	SQM	5.2		
	Providing and fixing ½" thk. Gypsum India board false ceiling at levels as shown in the drg. From FFL. Rate shall be inclusive of all Gypsum India components contained G.I. perimeter channels of size 0.55 thick having one flange of 20mm and another flange of 30mm and a web of 27mm alongwith perimeter of ceiling, screw fixed to brickwall/partition with the help of nylon sleeves and screws, at 610mm centres. The suspending G.I.intermediate channels of size 45mm, 0.9mm thick with two flanges of 15mm each from the soffit at 1220mm centres with ceiling angle of width 25mm x 10mm x 0.55 thick fixed to soffit with G.I. cleat and steel expansion fastners at every 610mm c/c. Ceiling sections of 0.55mm thickness having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to intermediate channel with the help of connecting clip and in direction perpendicular to the intermediate channel at 457mm centres. 12.5mm tapered edge Gypboard is then screw fixed to ceiling section with 25mm drywall screws driver or drilling machine with suitable attachment.				
	The boards are to be jointed and finished with POP so as to have a flush look and ready to receive paint which includes filling and finishing the tapered and square edge of the boards with jointing compound & joint paper tape. <b>Rate shall be inclusive of Cut outs for A/c machiness, spot lights, light fixtures, A/C. Grills, fire and security systems cut outs</b> , All Sections should adhere to the manufacturers guidelines. Vertical sides visible will be measured. <b><u>Rates Shall also be inclusive of vertical drop in ceiling upto 12" and no extra measurement for the drop upto 12" will be entertained.</u></b>				
2	<b>MODULAR FALSE CEILING - ARMSTRONG / equivalent make</b>	SQM	15.8		
	Providing and fixing Armstrong (Fine Fissured Micro Look with Tagular Edge using 15mm Grid sections) false ceiling of size 24"x24" at levels as shown in the drwng. from FFL. Rate shall be inclusive of providing the total system with installation etc.. The contractor has to maintain all tiles in good order and replace the defected tiles (at his own cost) before handing over the site for Branch Operations (till Inauguration).				

