

Page 1 of 2
STATE BANK OF INDIA
RBO 2 ERNAKULAM

NAME OF WORK		LAMINATION CHANGE WORK OF MULAVUKAD AND PUTHUVYPE BRANCHES			
SCHEDULE OF ITEMS FOR LAMINATE CHANGE FOR MAKING UNIFORM LAYOUT FOR HIGHWAY KUNDANNOOR AND EROOR BRANCHES					
Sl No.	Description of work	Quantity	Unit	Rate	Amount
HIGHWAY KUNDANNOOR					
1	Providing and fixing 6 mm marine flexy plywood with high glossy white flexy laminate of approved make and shade with curved bend in front modesty to the existing surface of counters using necessary frames with 19 mm plywood.	16	Sq.M		
2	Providing and fixing 6 mm ply wood finished with 1 mm laminate of approved make and shade to the existing table top finishing with necessary PVC edge band etc complete.	9	Sq.M		
3	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing partition/ panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings/ handles/ locks etc. complete. Edges should be neatly finished using pvc edge band	125	Sq.M		
4	Remove the existing laminate and fix with new 1 mm laminate of approved make and shade	75.00	Sq.M		
5	Providing and fixing side portion glazing with "Blue Laminated / Lacquered transperated glass of 12mm thick of approved brand and shall be fixed with 'Doma' (or) equivalent brand 'SS ' 'D' brackets. The curved 12mm thick lacquered transperant toughened glass shall be fixed at front size in between counters as per drawing and shall be fixed suitably with 'SS' brackets	5.00	Sq.M		
6	Providing and fixing front Modesty with 8 mm thick Aqua blue shade of Saint Gobain glass or equivalent fixed 3M sticking suitable at front vertical finished with 1 mm laminate.	6.00	Sq.M		
7	Painting the false ceiling with 1 coats of plastic emulsion paint of approved color	200.00	Sq.M		
8	Painting banking hall using approved quality ' Asian paint or equivalent two coats without putty finish	280.00	Sq.M		
9	Paint the windows with synthetic enamel paint 2 coats after cleaning the surface	50.00	Sq.M		
10	Providing PVC telescopic key boad tray with channel	8.00	Nos.		
11	Removing the existing drawer channel and fixing new telescopic channel of approved make	12.00	set		
12	Providing and fixing Godrej auto lock	10.00	Nos.		
13	Providing and fixing Godrej night latch	3.00	Nos.		

EROOR BRANCH					
14	Providing and fixing 6 mm marine flexy plywood with mm high glossy white flexy laminate of approved make and shade with curved bend in front modesty to the existing surface of counters using necessary frames with 19 mm plywood.	14	Sq.M		
15	Providing and fixing 6 mm ply wood finished with 1 mm laminate of approved make and shade to the existing table top finishing with necessary PVC edge band etc complete.	12	Sq.M		
16	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing partition/ panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings/ handles/ locks etc. complete. Edges should be neatly finished using edge band if necessary	94	Sq.M		
17	Remove the existing laminate and fix with new 1 mm laminate of approved make and shade	60.00	Sq.M		
18	Providing and fixing side portion glazing with "Blue Laminated / Lacquered transperated glass of 12mm thick of approved brand and shall be fixed with 'Doma' (or) equivalent brand 'SS ' 'D' brackets. The curved 12mm thick lacquered transparent toughened glass shall be fixed at front size in between counters as per drawing and shall be fixed suitably with 'SS' brackets.	4.00	Sq.M		
19	Providing and fixing front Modesty with 8 mm thick Aqua blue shade of Saint Gobain glass or equivalent fixed 3M stickering suitable at front vertical finished with 1 mm laminate.	5.00	Sq.M		
20	Painting the false ceiling with 1 coats of plastic emulsion paint of approved color	180.00	Sq.M		
21	Painting banking hall using approved quality ' Asian paint or equivalent two coats without putty finish	300.00	Sq.M		
22	Paint the windows with synthetic enamel paint 2 coats after cleaning the surface	65.00	Sq.M		
23	Providing PVC telescopic key boad tray with channel	6.00	Nos.		
24	Removing the existing drawer channel and fixing new telescopic channel of approved make	15.00	set		
25	Providing and fixing Godrej auto lock	10.00	Nos.		
26	Providing and fixing Godrej night latch	3.00	Nos.		
27	Providing and fixing cylindrical lock	2.00	Nos.		
	TOTAL				
	GST				
	GRAND TOTAL				