

BOQ FOR INTERIOR WORKS OF DISTRICT SALES HUB AT DIMAPUR BAZAR BRANCH

SI.No	Description of items	Unit	Qty	Rate(Rs.)	Amount
1	<p>Supply and installing Branch Head Table of size- 2130 mm x 1830 mm x 750 mm including cost of side credenza (1080mm x 600mm x 750 mm) made up of 19mm thick Block board all around, finished with 1 mm thick laminate of colour, shade & brand as approved. The table cost to include (pedestal), three drawers of 450 mm wide made with 6mm/12mm ply on right hand side on telescopic slider and a keyboard tray 250mm wide, CPU stand, foot rest as per design and direction by bank. The credenza unit should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/ beading of required size stained to match the desk and melamine finished. All inner surfaces to be finished with 0.8mm thk laminate of approved brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved brand. Locks to be of single control type. Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish & 8mm thick glass duly finished to be placed on top of table & credenza and necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply or equivalent. Laminate Make: Greenlam/Centurylam/Royaltouch or equivalent.</p>	Each	1		
2	<p>Supplying and installing Tables of Overall size - 1500 mm X 1830 mm x 750 mm including cost of side credenza (1050 mm x 450 mm x 750 mm) made up of 19mm thick block board of approved brand all around and finished with 1 mm thick laminate colour, brand and shade as approved by the Bank. The table cost to include (pedestal) three drawers of 375 mm wide made with 6mm/12mm ply on right hand side on telescopic slider, a keyboard tray 250mm wide with CPU stand and foot rest as per design and direction by Bank. The credenza unit should have openable/sliding shutter cupboard and intermediate horizontal shelves made in 12 mm thick plywood. All exposed edges to have teak wood lipping/beading of required size, stained to match the desk and melamine finished. All inner surface to be finished with 0.8mm thk laminate of approved brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks , handles etc. of Godrej or approved make. Locks to be of single control type.Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish & 8mm thick glass duly finished to be placed on top of table & credenza and necessary cut-out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply or equivalent. Laminate Make: Greenlam/Centurylam/Royaltouch or equivalent..</p>	Each	3		
3	<p>Supplying and installing running Tables 1370mm (L)x600 mm depth, made up of 19mm thick Block board of approved brand for top and vertical support, finished with 1 mm thick laminate of colour, brand and shade as approved by the Bank. The table cost to include to provide one drawers made of of 6mm/12 mm ply, a keyboard tray 250mm wide and CPU stand as per design & direction of bank. All exposed edges to have teak wood lipping/bidding of requierd size stained to match the desk and melamine finished. The works to include all hardware like castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved make. All inner surface to be finished with mat finish enamel paint of approve branecd. Design and detail of the table shall be as per direction of EIC. All the surfaces to be in laminate finish 8mm thick glass duly finished to be placed on top of table and necessary cut out to accommodate wires, edges to be m/c polished, with ms powder coated wire manager complete as per Bank's new uniform colour, layout & elevation policy.</p> <p>Ply/Block Board Make: MR Grade of Century/ Green/Archidply or equivalent. Laminate Make: Greenlam/Centurylam/Royaltouch or equivalent.</p>	Each	3		

BOQ FOR INTERIOR WORKS OF DISTRICT SALES HUB AT DIMAPUR BAZAR BRANCH					
Sl.No	Description of items	Unit	Qty	Rate(Rs.)	Amount
4	Providing & Fixing 10 mm thick float glass of size 600mm (width) x 750mm (height) & tapering towards bottom as per the design and shape as shown in Bank's new uniform colour, layout & elevation policy, fixed with silicon and T.W beading support on wooden partition as directed, on either sides of SWO as per design. Rate shall include etching of glass as directed by bank. All edges of glass shall be duly beveled & polished as directed complete. Make: Saintgobin/ Modiguard or equivalent.	SQM	1.5		
5	Low ht storage unit: Providing and fixing storage units of size 450 mm (D) x 750 mm (H), made up of 19 mm thick block board of approved brand on top & vertical support and finished with 1 mm thick laminate of approved brand on side and top. The storage units shall have openable/sliding shutters made up of 19mm thick plywood and finished in 1 mm thick laminate of approved shade. The storage units shall have intermediate horizontal and vertical shelves made in 19 mm thick plywood. All exposed edges to have teak wood lipping/beading of required size, stained to match the desk and melamine finished. All inner surface to be finished with 0.8mm thk laminate of approved brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, locks, handles etc. of Godrej or approved make. Ply/Block Board Make: MR Grade of Century/ Green/Archidply or equivalent. Laminate Make: Greenlam/Centurylam/Royal touch or equivalent.	rm	14.3		
6	Fabricating and fixing centre column paneling , with 12 mm thick ply finished with 1 mm thick laminate of approved shade & brand over 25 mm x 35 mm (thickness not less than 1.5 mm) aluminium section framework of approved brand at spacing not exceeding 600 mm both ways (horizontal and vertical.) Ply/Block Board Make: MR Grade of Century/ Green/Archidply or equivalent. Veneer Make: Greenlam/Centurylam or equivalent.	SQM	20.72		
7	Providing and fixing low height semi glazed wooden partitions made of 6 mm ply of approved brand in both side and to be finished with 1 mm thick laminate of approved brand, colour and shade over 50 mm x 50 mm (thickness not less than 1.5 mm) aluminium section framework of approved brand at spacing not exceeding 600 mm both ways (horizontal and vertical). Portion from 900 mm to 1500 mm height shall have 6 mm thick plain float glass (Make: Saintgobin/Modigurd) fixed with 10 mm thick teak wood moulding duly polished as per designed and direction by bank. All exposed edge shall be covered with teakwood lipping with polishing complete in all respect. Rate shall includes making provision for fixing of counter top 12 mm glass on its edges with necessary fixing arrangement as directed. Ply/Block Board Make: MR Grade of Century/ Green/Archidply or equivalent. Laminate Make: Greenlam/Centurylam/Archidlam or equivalent.	SQM	9.53		
8	Providing fittings and fixing of woodwork in door frame (chowkhat) 75 mm x 62.5 mm section to the column/stiffeners/walls with necessary holdfast/sleeves etc. as specified and directed by bank. Allow making rebate for fixing of door shutter. rate shall includes applying of two coat of enamel paint. 1st class local wood.	RM	10.52		
9	MAIN DOOR: Providing and fixing glazed door made of 12 mm thick float glass (Make: saintgobin, modigurd) with frosted film fixed in between top & bottom rail and side stile teak wood framework of size 125 mm x 50 mm. The framework to be finished with 1.0 mm thick laminate on both side. Glass to have acid etched design pattern with logo as directed. Doors to be mounted on heavy duty floor spring. Rate shall includes all hardwares such as: Two nos S.S. finish handle, lock, door stopper, hinge, tower bolt etc. of approved make.	SQM	3.4		

BOQ FOR INTERIOR WORKS OF DISTRICT SALES HUB AT DIMAPUR BAZAR BRANCH					
Sl.No	Description of items	Unit	Qty	Rate(Rs.)	Amount
10	Providing & fixing in position Aluminium Composite Panel (ACP) Panelling with framing of min 20 gauge 35 mm x 25 mm Aluminium Tube section in 600 mm C/C both ways. Minimum 3 mm thick ACP to be fixed over the freamework with 3M or equivalent adhesive and mirror screw in 600 width panels or distributed equally. Joints to be finished with Silicon based sealant. Aluminium foil thickness to be min 0.20 mm on both sides. Make: Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used.	SQM	16.7		
11	Shutter Boxing: Providing & fixing in position Aluminium Composite Panel (ACP) with with framing of min 20 gauge 35 mm x 25 mm Aluminium Tube section in 600 mm C/C both ways. Minimum 3 mm thick ACP to be fixed over the freamework with 3M or equivalent adhesive and mirror screw in 600 width panels or distributed equally. Joints to be finished with Silicon based sealant. Aluminium foil thickness to be min 0.20 mm on both sides. ACP Trap door will be 12 mm ply finished with 3 mm thick ACP. Make: Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used. Shades to be as per Bank's approval.	SQM	4.61		
12	False ceiling : Providing and fixing suspended false ceiling with 600x600 mm size & 12mm thick mineral fiber ceiling tiles of Armstrong dune or approved make. Suspender, frame work as per manufacturer's specifications. The item to include cost of making necessary cut-outs for lights/air-conditioning grills as per design direction by bank.	SQM	48.3		
13	Gypsum board false ceiling : Providing and fixing suspended 12mm thick Gypsum board false ceiling with GI framework of standard gauge and as per the specifications of India Gypsum Co. The rate to include painting with lustre paint and making necessary design,pattern & cut outs for light fittings, cove light etc. complete as per design direction by bank.	SQM	47.34		
14	Providing & fixing in place 100 mm. Vertical blinds with scotch guard of approved make, quality and colour shade & pattern. Rate shall include necessary fittings, scotch guard treatment on both sides etc. complete. The overlaps should be uniform & adequate.	SQM	14.89		
15	Dismantling of existing walls, doors etc and carting away from the site	SQM	54.43		
16	Scrapping off the old paint and finishing walls with two coats paint of required shade. Make: Asian paint, Dulux and including scaffolding complete	SQM	35.4		
17	Providing two coat of Asian white wall care putty (water resistant white cemnet based putty for concrete/ mortar walls and ceiling both internal and external) after removing all loosely adhering material from the wall surface with the help of emery stone, putty blade or wire brush and moistering the wall with sufficent quantity of clean water as specifed and directed by the Bank.	SQM	35.4		
18	Painting of steelwork by removing the existing paint, dust and dirt as required .	SQM	30.69		
19	Providing & fixing vinyl flooring 1.5mm thick.	SQM	75		
Total					
NOTE :The estimated cost is exclusive of GST					