

**SBI INFRA MANAGEMENT SOLUTIONS PVT LTD(SBIIMS)  
(A WHOLLY OWNED SUBSIDIARY OF SBI), CIRCLE OFFICE, PATNA**

**DETAILED ESTIMATE OF PVC FLOORING WORK AT LHO PATNA**

S.NO.	PARTICULARS	UNIT	QTY.	RATE	AMOUNT
1	Providing and laying vinyl flooring (pvc flooring)of 2mm thick make of GREEN/CENTURY/Equivalent approved with pidilite adhesive solution including the cost of labour trancsporation ,cleaning fixing and with full finished &furnished all comple job as directed by Engineer IN Charge.	sq.m	1858.73		
		SUB TOTAL			
RS.					

**NOTE:-**

\* ABOVE PRICE IS EXCLUDING GST.

\* GST PAID EXTRA BY THE BANK AS PER RULE.

**SBI INFRA MANAGEMENT SOLUTIONS PVT LTD(SBIIMS)**  
**(A WHOLLY OWNED SUBSIDIARY OF SBI), CIRCLE OFFICE, PATNA**

DETAILED ESTIMATE OF CIVIL WORK FOR INTERIOR AND EXTERIOR PAINTING WORK OF GUEST HOU

S.NO.	PARTICULARS	UNIT	QTY.	RATE
1	Providing two or more coats of oil bound acrylic distemper paint, 1st quality Asian paints / ICI Du-lux/ Berger/Nerolac or equivalent approved brand over a coat of cement primer to give an even shade over newly plaster of parish finished walls & ceil-ings as per direction of Bank.(including the cost of scaffolding)	Sq.m	2413	90.00
2	Finishing walls with Premium Acrylic Smooth exterior paint(1st quality Asian paints / ICI Du-lux/ Berger/Nerolac or equivalent approved) with Siliconeadditives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)as directed by EIC.(including the cost of	Sq.m	1838	110.00
3	Painting with synthetic enamel paint of approved brand and manufacture of including all cost required colour to give an even shade : Two or more coats on new work over an under coat of suitable shadewith ordinary paint of approved brand and manufactureas directed by EIC.	Sq.m	118.875	90.00
4	Providing and applying with texture paint of approved shed by EIC as per bank approved quality or as directed by EIC.(with all complete job)	sq.m	92.93	700.00
5	French spirit polishing :	kg	241.63	269.00
6	Dismantalling the old exterior painting putty work preparing for new work of painting including the cost of labour and scaffolding and with all complete job.	sq.m	1838	4.00
RS.	SUB TOTAL			
	ADD CONTINGENCY @10%			
	TOTAL WORK VALUE			

**NOTE:-**

\* ABOVE PRICE IS EXCLUDING GST.

\* GST PAID EXTRA BY THE BANK AS PER RULE.

\* ABOVE WORK AS PER CORPORATE CENTER, MUMBAI APPROVED MATERIALS, C/LAMINATES AND SPECIFICATIONS AND DIRECTION OF ENGINEER-IN CHARGE/BANK

BANK ENGINEER

SE

AMOUNT
217170.00
202180.00
10698.75
65051.00
64998.47
7352.00
567450.22
56745.02
624195.24

OLOURS  
JK.

NEER

<b>SBI INFRA MANAGEMENT SOLUTIONS PVT LTD(SBIIMS)</b>					
<b>(A WHOLLY OWNED SUBSIDIARY OF SBI), CIRCLE OFFICE, PATNA</b>					
<b>DETAILED ESTIMATE OF CIVIL WORK FOR INTERIOR AND EXTERIOR PAINTING WORK OF SORC BUNGLOW</b>					
<b>S.NO.</b>	<b>PARTICULARS</b>	<b>UNIT</b>	<b>QTY.</b>	<b>RATE</b>	<b>AMOUNT</b>
2	Finishing walls with Premium Acrylic Smooth exterior paint(1st quality Asian paints / ICI Du-lux/ Berger/Nerolac or equivalent approved) with Siliconeadditives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)as directed by EIC.(including the cost of scaffolding and scrubbing the surface with complete job)	Sq.m	3595	110.00	395450.00
3	Painting with synthetic enamel paint of approved brand and manufacture of including all cost required colour to give an even shade : Two or more coats on new work over an under coat of suitable shadewith ordinary paint of approved brand and manufactureas directed by EIC.	Sq.m	425	90.00	38250.00
RS.	<b>SUB TOTAL</b>				<b>433700.00</b>
	<b>ADD CONTINGENCY @10%</b>				<b>43370.00</b>
	<b>TOTAL WORK VALUE</b>				<b>477070.00</b>

**NOTE:-**

- \* ABOVE PRICE IS EXCLUDING GST.
- \* GST PAID EXTRA BY THE BANK AS PER RULE.
- \* ABOVE WORK AS PER CORPORATE CENTER, MUMBAI APPROVED MATERIALS, LAMINATES AND SPECIFICATIONS AND DIRECTION OF ENGINEER-IN CHARGE/BANK.

**BANK ENGINEER**