

BILL OF QUANTITIES FOR FURNISHING WORK (LOOSE & FIXED FURNITURE) TO BE PROVIDED AT NEW PREMISES SBI MEVDA BRANCH (TO BE FILLED ONLINE)					
Sr. No.	Description	Quantity	Unit	Rate	Amount
[A]	FURNISHING WORK				
1	SINGLE WINDOW COUNTER AND CASH COUNTER SIZE 5'-0" X 2'-9" X 2'-6"	1.50	RMT		
	Supplying, fixing and keeping in position single window counter complete as per design, and drawing made out of 18mm thick commercial ply wood of approved make, complete with 19 mm. C.P. Teak wood lipping on all edges wherever required.				
	The cost shall be inclusive of S & F of a drawer and shelf unit with 18mm thick commercial plywood and with approved make multipurpose Auto Lock in drawer and shelf unit. The cost shall also be inclusive of the following.				
[a]	size :				
	Description: L B Ht.				
	Writing Top 5'-0" 2'-9" 2'-6"				
	Transaction Top 5'-0" 2'-6"				
	4 Drawers with				
	pegion hole 2'-0" 1'-3" 2'-0"				
	Computer key Board				
	Supplying and fixing metal key Board of approved make in counter as per design and instructions.				
[b]	Working table top and edges shall be finished with 1mm thick frosty white laminate of approved make, as per drawing and direction with all labour and materials all edges should be finished with laminate.				
[c]	Transaction Top : 2x6 mm thick flexy ply wood round shape with 1mm thick frosty white laminate shall be provided at front as per design, all edges should be finished with laminate.				
[d]	Front pannel (Front Apron) shall be finished with 1mm thick 18" high blue coloured laminate of approved make and fixed on 18mm thick commercial ply wood all complete as per drawing.				
[e]	Foot rest of 3" x 1.5" in C.P. Teak wood and CPU stand 16" x 24"				
[f]	All wood work shall be laquer polished to a smooth and uniform finish of choice colour and shade.				
[g]	All fittings like S.S. handle/ approved make Auto Lock to each drawer and cabinet doors, piano hinges, ball catcher stopper, metal cable manager etc. approved make heavy duty full extension channel in drawers.				
[h]	Heavy duty telescope full extension sliding channel of approved make shall be used in all drawers.				
[i]	All the surface without lamination shall be Synthetic enamel paint/polishing of approved shade etc complte				
[j]	Counter shall be made independent in Length of 5'-0" and properly placed between two partition.Counter measured between two partition and paid (FOR DETAILS REFER DRG. NO- 1)				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : 1mm thick frosty white laminate				
	2) Front Appron : Round frosty white laminate and blue coloured laminate.				
	3) Facing of Drawers : 1.00 mm thick laminate finish				
2	Providing and fixing 12 mm thick Toughened Glass partition on counter front side top as follows. (5'-0" x 2'-6" x 2nos)	2.32	SQMT		
	Providing and fixing 12 mm thick Toughened float glass with polished edges shall be fixed with necessary S.S Brush finish brackets support on wooden partition as directed. Making necessary cut out in glass all edges of glass shall be Diamond cut polished edges as directed complete. [REFER DRG NO-1				

Sr. No.	Description	Quantity	Unit	Rate	Amount
3	Providing and fixing 12mm thick Toughened float Glass partition between Single Window counter partition front side as follows. (1'-0" x 3'- 8 1/2" X 3 NOS)	1.05	SQMT		
	12 mm thick Toughened clear float glass with polished edges shall be fixed with silicon and T.W beading support on wooden partition as directed. All edges of glass shall be Diamond cut polished edges as directed complete. (Glass for Measurement outer longer width and height shall be measured and paid) REFER DRG NO-1				
4	Side Credenza For S.W Counter Size 3'-0"x1'-4" x 2'-6" x 2NOS ht. With openable shutter Side Table top and edges shall be finished with 1mm thick frosty white laminate on Top and Edges. All other visible surface shall be finished with 1.00 mm th laminate of approved make & shade.	1.40	SQMT		
	Supplying and providing side cabinet for keeping computer and printer size 1'-4" width 2'-6" height and 3'-0" length. Openable shutters as directed. Cabinet shall be made from 18mm thick commercial ply wood &. Back shall be made from 6mm th commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with 1.0mm th laminate and approved group lock, handle, hinges, magnet catch. Edges to be finished with teak wood lipping etc. including all internal surface to be polished/ Synthetic enamel paint etc. [REFER DRG NO-1				
	As per drawing and instruction of Architect/Bank Complete				
5	EXTENSION OF EXISTING MANAGAER TABLE :	1	NO		
	Size : 1'-4"x 2'-9"x 2'-6"				
	Made of 18mm thick commercial ply wood of 18mm thick commercial ply wood for top, front apron and vertical side support finished with 1mm thick laminate of approved make and shade. All exposed edges of plywood top and vertical support shall be provided with teak wood beading of the size of the existing table and finished with lackqur polish. All non visible . interior surfaces of extenion shall be finished with paint / polish as per the finishing of the existing table.				
6	GRAHAK MITRA TABLE Approx. Size (5'-0" X 2'-3")	1.52	RMT		
	Same as above item no 5 but Approx Size 5'-6"/ 8'-6"x 2'-3" wide with storage unit in Table with 4mm thick MDF board + laminate on all exposed visible surface As per drawing and instruction of Architect/Bank Complete For Grahak Mitra/Tech Mitra (Help Desk Table)				
	Table top made from 18mm thick ply wood + 1mm thick laminate				
	Apron (Front side) made from 18mm thick ply wood + 1mm thick laminate				
	Both sides made from 18mm thick ply wood + 1mm thick laminate				
	3" thick Partition above working table top made from 18mm thick+6mm thick ply wood with necessary framing with 4mm thick MDF board + 1mm thick laminate.				
	Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	Drawer Storage Unit- 1'-4" W x 2'-0" D, 2 Nos Drawer on top and rest 1 No shutter-				
	As per drawing and instruction of Architect/Bank Complete (FOR DETAILS REFER DRG. NO-6)				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : 18mm Thick Plywood with 4mm thick MDF with High 1mm thick laminate				
	2) Front Apron & Sides: 4mm thick MDF with1mm thick laminate				
	3) Facing of Drawers: 1.0 mm thick Laminate finish				
7	DINING TABLE Approx Size 4'-0"x 2'-0"	1.00	NO		

Sr. No.	Description	Quantity	Unit	Rate	Amount
	Supplying and Providing Dining Table of 6'-0" x 3'-0" x 2'-6" height 1" x 1.5 ht." T.W beading shall be fixed on border .Top shall be made of 18 mm thick commercial plywood with additional 18mm thick Ply wood patta of required width on edges with 1.0 mm thick laminate on top of approved shade brand and. supports of the Table shall be made of 2" x 2" T.W. members in a Design as directed. All surfaces not laminated shall be lacquer polished.				
	Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
8	SIDE STORAGE CABINATE :	3.95	SQ.MT		
	Making and supplying side storage cabinet made of 18mm thick commercial ply wood of approved make for the top, sides, shelf and the front shutters and 6mm ply for the back. All visible surfaces like the top, sides and the front shutters shall be finished with 1mm thick laminate of approved make and shade. All internal as well as non visible surfaces shall e finished with two coats of paint, polish as directed by architect.				
	The front shutters shall be provided with s. s. hinges tower bolts, powder coated handles, ball catches, s. s. group lock of approved make etc. complete. Edges of the ply wood shall be finished with 1/2" thick teak wood beading finished with the lacquer polish etc. complete.				
	Size : 9'-6"x 1'-4"x 2'-6" in manager chamber				
	7'-6"x 1'-4"x 2'-6" near S. W. counter.				
9	P/F ELECTRIC CUB BOARD (3'-0" x 5'-0")	1.40	SQMT		
	Providing and fixing Electric cup board using 18mm thick bision panel for verticale and shelves and aluminium framing of 50x25x1.20mm thick with 6mm thick bision panel on both side for shutter with 1.0 mm thick laminate on all exposed surface and polishing/ synthetic enamel paint on all internal surface. shutter with approved make lock handle, hinges,ball catches P&fixing S.S Perforated jali shall be provided in shutter etc.complete as directed, depth of cup board 1'-3".Shutter height up to 7'-0" and above fixed Type up to false ceilling bottom.				
10	P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION FOR S.W COUNTER AND CASH CABIN (size : 5'-3" x 4'-6" x 3 nos)	6.60	SQMT		
	Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade of approved brand on both side of aluminium skeleton and fixing 1.0 mm thick laminate of approved shed on both sides. Fixing 1.0 laminate in a shape as directed shall be fixed on all exposed edges. Fixing 12 mm transparent toughened glass as directed. Applying polish on exposed steam beach members with lacquer polished edges as directed complete. Laminate to be provided only on visible surface [FOR DETAILS REFER DRG. NO-1]				
	For Low height Single window and Cash cabin partition, Average height of partition shall be measured and paid.				
11	PROVIDING AND FIXING WICKET GATE WITH BOTH SIDE LAMINATE (size : 2'-6" x 4'-0" x 2 nos)	1.86	SQMT		
	Same as item no 24 but P/F 30 mm thick flush shutter with both side laminate including SS hinges with countersunk SS screws, Approved make Night latch Lock, S.S Handles,Door stoppers, doorstep etc complete as directed.				
12	P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION Nr. S. W. (size : 3'-0" x 4'-0")	1.11	SQMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
	Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade of approved brand on both side of aluminium skeleton and fixing 1.0 mm thick laminate of approved shed on both sides. Fixing 1.0 laminate in a shape as directed shall be fixed on all exposed edges. Fixing 12mm th free clear float glass as directed. Applying polish on exposed steam beach members with lacquer polished edges as directed complete. Laminate to be provided only on visible surface				
13	P/F BOTH SIDE LAMINATED FULLY GLAZED PARTITION : 3'-0" x 4'-0" x 2NOS	2.23	SQMT		
	Providing and fixing both sides laminate full height partly glazed partition using 50mm x25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade on both sides, 1.0mm laminate of approved make shall be fixed on plywood, Providing 8.0 mm th float glass as directed in the partition. Providing door shutter using 30mm thick flush shutter with both side laminate and fixing 6 mm thick glass shall be provided in door shutter providing 5" Long 3 Nos stainless steel hinges/doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter Steam beach Beading shall be provided for fixing glass. All visible members if not laminated shall have lacquer polished as directed.[REFER DRG NO-5]				
14	Providing and Fixing Partition between manager chamber and UPS Room as above but providing both sides 12mm thick bison board with 1mm thick laminate of approved shade as manager chamber side and two coats of synthetic enamel paint of approved make and shade on UPS side. (Partition Size - 12'-8 1/2" x 9'-11")	11.75	SQMT		
15	Providing and fixing isolated flush door shutter (Partly Glazed and Partly Laminate) with frame as follows. (Doors : 3'-0" x 6'-9" x 2nos, 2'-6" x 6'-9" x 1 no)	5.33	SQMT		
	Providing and fixing 4"x2" steam beach member for frame and Flush door shutter made out of 31 mm thick flush door with 6 mm thick clear float glass vision panel secured with 12 mm thick steam beach beading, 31x 12 mm thick steam beach periphery patti around shutter edges, 1 mm thick laminate on both sides, 35x12mm thick steam beach stopper patti on frame including 3 Nos 5" long SS hinges with countersunk SS screws, Approved make Ded Lock, S.S Handles, 150 mm long Door stoppers, doorstop of approved make etc. all exposed surface /edges not laminated be provided with lacquer polish complete as per drawing & instructions [REFER DRG NO-5]				
	GLASS DOORS AND PARTITIONS				
16	P & F FULLY GLAZED DOOR WITH PATCH FITTINGS for Main Entrance Door For Branch (size : 5'-0" x 7'-0")	3.26	SQMT		
	Providing & Fixing fully glazed main door at the main entrance and ATM. The Item includes fixing of 12 mm th. Toughened glass with the help of top patch & bottom patch fittings . The door will have patch lock, pti pivot, floor spring & 400 mm long handles both sides, (Approved Make) , fixed with the glass by making necessary cutouts & holes. The glass edges shall be polish on all sides. The entire door shall be erected in complete line & level. The door will have S.S brush finish Signage for pull & push.				
	The patch fittings (Approved make) shall be of aluminium with s,s, matt finish coating & signage shall be of kich make. The entire door, complete in all respect should be installed in positions as req.				
17	Same as above but Providing & Fixing Wall panelling with Veneer PU coating paint finishing for wall etc in Manager Cabin (Szie : 6'-6" x 5'-6") (Size : 6'-6" x 1'-6" x 1no, 6'-6" x 0'-6" x 1no, 0'-6" x 3'-6" x 2nos)	1.55	SQMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
18	Panelling for Display wall with 3M Vinyl Films with printed design and lamination finishing (Back side grahak mitra : 5'-6" x 4'-6")	2.30	SQMT		
	Providing and laying panelling on wall having 8mm th MDF Board exterior grade with 3M vinyl films with printed design and lamination fixed on wall with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways etc. complete as directed. panelling as per design and instruction of Architect. Only Finished visible surface area shall be measured for payment (MDF board with 0.60 mm thick laminate) Front surface area shall be measured for payment purpose.				
	Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width.				
19	Panelling for Digital wall with Blue/white high gloss PU Coating finishing (back side S. W. size : 6'-5" x 5'-0" : 6'-5" x 1'-0" x1no, 6'-5" x 0'-6" x 1no, 0'-6" x 3'-6" x 2 nos)	1.25	SQMT		
	Providing and laying pannelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20mm thick at maximum 2'-0" c/c bothways etc. complete as directed. pannelling as per design and instruction of Architect. . Only Finished visible surface area shall be measured for payment				
20	P/A WALL PAPERS on Digital wall	3.55	SQMT		
	Providing and applying Wall paper approved by Architect / Bank's Engineer, wall paper basic price of Rs 100=00 Per Sq.Ft				
	Size : Manager chamber 5'-6" x 3'-6" & Back side S. W. 5'-5" x 3'-6"				
21	SOFT BOARD (Size : 4'-0" x 2'-6")	0.93	SQMT		
	Providing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6mm thick commercial plywood on back side and 12mm th soft board on front. Fixing cloth of selected design of Basic rate of Rs. 150 per mt.steam beach member shall have lacquer polish as directed complete.				
22	CUSTOMER WRITING DESK	1	NO		
	Writing Desk Size 3'-0" x 1'-3" x 0'-6"+3'-0" ht.				
	Verticle Sides and bottom shall be made out of 36 mm (2X18) thick Commercial plywood and back side 12mm thick ply wood with Laminate on Top and Edges on all sides including inside divisions. Top shall be made from 12mm th Toughend glass with polished edges making diff divisions by 18mm th plywwod with laminate on both side for slips or forms as per detail drawing and inststruction complete. (Drawing as enclosed herewith) Laminate to be provided on all visible surface [REFER DRG NO-07]				
23	Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shed. (Basic Price of Rs 135=00 Per Sq.Ft) (Size : 5'-0" x 5'-0" x 1no, 3'-0" x 5'-0" x 2nos)	5.11	SQMT		
24	Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surfaces as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. (Size : 5'-0" x 4'-0") Front door	1.86	SQMT		
25	ALUMINUM COMPOSITE PANEL FOR FRONT SIDE ELEVATION for BRANCH AND ATM ROOM IN SIDE WALL AND OUT SIDE	18.15	SQMT		
	(Front side : 5'-6" x 9'-0" x 2nos, 5'-0" x 2'-0")				
	False ceiling below slanting slab in the front : 32'-6" x 2'-6"				

Sr. No.	Description	Quantity	Unit	Rate	Amount
	Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond with 0.25 mm foil with 2" x 1" x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building This item will be carried out as per manufacturer specifications. Rate also including trap door shutter including hinges stopers etc complete as directed. Design as per Bank standered Drawing and Architects instruction etc complete.				
	FALSE CEILING WORK				
26	P/F GYPSUM BOARD FALSE CEILLING	40.00	SMT		
	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA (Gypsteel Ultra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India.				
	After completion of work to certificate from Saint Gobin Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification				
	Note : (1) Rate includes making necessary cutouts for lighting fixtures (2) Pattas of Less than 1'-0" shall be measured in Sqft and not in Rft and paid in Sqft. (3) Only finished visible surface area shall be measured for payment.				
27	Providing and Fixing of Armstrong Mineral Fibre Acoustical Suspended ceilling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid	33.10	SMT		
	Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be duceducted for payment purpose				
	After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications				
28	Providing and fixing "Dorma/Ozone/Godrej" or equivalent make door closure. etc complete	3	NO		
29	Supplying and providing 1'-9" x 1'-9"x 1'-3" height Center Tepoy as follows.	1	NO		
	Providing and making open box structure type Teapoy made out of 36 mm (2X18) thick plywood with all over 1.0 mm thick laminate finish provided with bevelled & diamond polished edges 12mm thick glass top supported on SS studs with complete as directed.				
	RECONDITIONING FURNITURE WORK				
30	Providing and fixing 1.0 mm thick laminate on any existing laminate surfaces of Tables, Side Tables, , cupboards,panelling etc.Rate Including removing existing laminate by Hot Iron. and finishing surface etc complete. Only laminate finished surface area shall be measured for payment. (Manager table : 5'-0" x 2'-5" x 2'-6", Side unit 3'-0" x 1'-4" x 2'-6" ; S. W. top, front & drawer box- 4'-1/2"x 5'-0"x 1no, 5'-0"x 2'-6"x 1no)	10.90	SMT		
31	Removing refixing and realignment of existing Furnitures				
	Refixing and alignment of Tables,Side Tables, cup board ,Misc.and Other furnitures to be used from existing premises including polishing and minor repairs. Contractor must visit site to assess work involved before quoting.				
	Removing refixing and realignment of existing Tables				

Sr. No.	Description	Quantity	Unit	Rate	Amount
	Repaing of drawers and shutter and painting /polishing complete as directed.				
31.1	Table Size 5'-0" x 2'-6" For Officer.	1	NO		
31.2	Side Table Size 3'-3"/3'-0" x 1'-4" x 2'-6"ht	1	NO		
31.3	S.W Counter with necessary cutting and modification includes paiting/polishing etc. Complete Rate also including Transaction Top : 2x6 mm thick flexy ply wood round shape shall be provided at front as per design.	1.50	RMT		
32	Replacing of approved make multipurpose lock & handle/slidding channels wherewer required etc. complete as directed.				
	Replacing of Existing cup board locks	11	NO		
33	Replacing of Existing cup board handles	11	NO		
34	Providing and fixing 12mm th glass on table top including bevelled & polished edges.etc. complete as directed (manager table 6'-4" x 2'-5")	1.42	SQ.MT		
35	Providing & fixing 6 mm thick best quality commercial plywood with IS 303 as per approved make, fitted on both sides of the frame work/prevailaing work for full height and low height partition/Panelling etc. with approved screws nails and glue/adhesive etc. Actual executed area on both sides of the partition measured separately for payment.	10.90	SQ.MT		
35.1	6mm thick flexi ply on existing counter	1.39	SQ.MT		
	Providing and applying 6mm thick felxi ply on the existing counter.				
36	Same as above but Providing and Fixing 2 nos sheets of 18"x 24" clear acrylic (poster to be sandwitched in between)	2.00	NO		
	TOTAL COST "A"		RS.		
[B]	BUY BACK OF OLD FURNITURE				
	Less Dismantallating of entire furniture and fixtures from existing premises and buy back of furniture not required by Bank as follows				
1	CASH/S.W COUNTER	1.52	RMT		
2	12 mm thick glass partition on S.W Counter Size : 5'-0" x 1'-5"	0.66	SQMT		
3	Wooden partition for S.W Counter Size : 4'-0" x (4'-8" + 4'-4" / 2), 5'-1" x 4'-4"	3.71	SQMT		
4	Wooden Partition for Server Room/Manager Cabin & other partition Size : 5'-3" x 6'-1" x 1no, 3'-3" x 6'-1" x 1no	4.80	SQMT		
5	Table Size 5'-0"x2'-6"	2	NO		
6	Table Size 4'-6"x2'-6" Size : 3'-11" x 1'-11" x 2'-6"	1 2	NO NO		
7	Wooden Side Table 36" x16" x 30"ht	2	NO		
8	Customer Writing Desl	1	NO		
	TOTAL COST OF BUY BACK "B"			RS.	
	SUMMARY				
[A]	FURNISHING WORK			RS.	
[B]	BUY BACK OF OLD FURNITURE			RS.	
	NET TOTAL TENDER COST [A -B]			RS.	

Sr. No.	Description	Quantity	Unit	Rate	Amount
		Seal & Signature of the contractor			