

**SCHEDULE OF QUANTITIES FOR INTERIOR FINISHING WORKS AT SBILD
VIZIANAGARAM**

S.No	Description of item	Unit	Qty	Rate	Amount
1	GRID FALSE CEILING :Providing and fixing in true horizontal level false ceiling grid system of approved brand The suspension system shall be Trulok Silhouette revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitered ends with "birds mouth " notches to provide mitered cruciform junctions. Main runners to be spaced at 120mm c/c fixed by using 2mm pre-straightened GI wire. Main tee, rotary stitched of size 15mm x 44mm x 3600mm at every 1200mm c/c maximum and 1200mm cross tee of size 15mm x 44mm x 1200mm at every 600mm c/c maximum and 600mm cross tee of size 15mm x 44mm x 600mm at every 1200mm c/c maximum and 19mm x 19mm x 3000mm wall angle all-round the wall to form grid size of 600mm x 600mm and suspending the grid using 2mm pre-straightened GI wire and 6mm nylon rawl plug at every 1200mm intervals at the main tee and laying of dunne premier miro look mineral fiber tiles manufactured by Armstrong World Industries of size 600mm x 600mm x 15mm over the formed grid etc., complete as directed.	Sq.mt	100		
2	GYPSUM FALSE CEILING: Providing and fixing suspended ceiling system of 12.5mm La Gyp / Boral Plaster Boards fixed to Frame Work / Rondo / Boral Metal System concealed grid key lock suspended ceiling system consisting of 5mm suspension rod, adjustable spring loaded suspension clip, top cross rail of 3000mm long of 0.55BMT and furring channel 4000mm long made of 0.5mm BMT the top cross rail to be suspended from ceiling at every 1200mm and furring channel to be fixed to top cross rail at every 600mm to make a grid of 1200 x 600m. All the above components are to be made of galvanized steel. The rates to include cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary	Sq.mt	50		

	strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed. The rate quoted should include finishing the surface with putty, a coat of primer and two coats of royal emulsion paint.				
3	Roller blinds: Providing and fixing roller blinds of make Vista/Hunter Douglas/Marvel	Sq.mt	45		
4	Wall / Column paneling(LAMINATE): Providing & fixing metal stud wall paneling with the following specification: a) Supporting system comprising 51 X 35 X 0.55 mm thick metal studs @ 600 mm c/c and 51 X 32 mm metal tracks at floor, middle, with joints staggered. The verticals should touch the ceiling with horizontal ceiling channel at slab/beam bottom. b) 12 mm cement board on one side with 25 mm dry wall screws for the entire height of paneling. c) 1 mm glossy laminate and 1mm thick texture laminate/Cement Fibre Board (finished with painting) as shown in drawing. (Length X height up to false ceiling will be measured for payment.) The rate quoted should include making niches in paneling.	Sq.mt	200		
5	Removal of existing damaged wall paneling and carting away derbies	Ls	1		
	Total				
	Discount if any in terms of percentage				
	NET TOTAL				

Signature of Agency with seal