

TENDER**DILIP KULKARNI & ASSOCIATES - ARCHITECT, INTERIOR, LANDSCAPE DESIGNER & SURVEYOR.**

Address:15/3, Metro House, "C" Wing, II Floor, Opp. Delhi Darbar Hotel, Colaba Causway, MumbaiI - 400 039, Maharashtra

E-Mail - dkulkarniasso@gmail.com / rajandk1956@gmail.com

Mobile - Mr.Rajan - 98200 76349 / 97694 01774

NAME OF CLIENT: - **STATE BANK OF INDIA**

ADDRESS: - Karad Branch, Vakhan Road, Budhar Peth, Karad, Dist. Satara

NATURE OF WORK: - **AIR CONDITIONING WORK**

NO.	Particulars	QTY	UNIT	RATE	AMOUNT
A	<u>HIGH SIDE WORK</u>				
A01	Supply, Installation, Testing & Commissioning of a Ceiling mounted "Cassette" Air- Conditioner by cutting false ceiling & comprising of Indoor & Outdoor units. The Indoor unit comprising multi-row DX cooling coil, Drier, expansion valve/device , air blower driven by motor with mounting accessories. Outdoor unit will comprise the Rotory/Scroll compressor, condenser coil & fan, Cordless remote controller etc. including Refrigerant gas charging /(R.32 or R 410), water drain system etc.				
a	Supply, Installation, Testing & Commissioning of 3 Ton Cassette A.C. as per specifications given in item no 1 above .(Banking Hall)	1	NOS		
	RATE IN WORDS -				
b	Supply, Installation, Testing & Commissioning of 2 Ton Cassette A.C. as per specifications given in item no 1 above .(Banking Hall)	3	NOS		
	RATE IN WORDS -				
A02	Supply, Installation, Testing & Commissioning of a HighWall mounted "Split" Air- Conditioner by cutting false ceiling & comprising of Indoor & Outdoor units. The Indoor unit comprising multi-row DX cooling coil, Drier, expansion valve/device , air blower driven by motor with mounting accessories. Outdoor unit will comprise the Rotory/Scroll compressor, condenser coil & fan, Cordless remote controller etc. including Refrigerant gas charging (R.32 or R 410),,, water drain system etc.				
a	Supply, Installation, Testing & Commissioning of 1.5 Tr. Three Star Tye A.C. with other specifications as above.(E-Lobby + Grahak Mitra +Banking Hall (Real Existing)	4	NOS		
	RATE IN WORDS -				
b	Supply, Installation, Testing & Commissioning of 1.0 Tr. Three Star Tye A.C. with other specifications as above.(Manager Cabin + Server Room)	3	NO.		
	RATE IN WORDS -				
TOTAL (A)					
GST WILL BE EXTRA @ 28 %					

NO.	Particulars	QTY	UNIT	RATE	AMOUNT
B	<u>LOW SIDE WORK</u>				
B01	S.I.T.C. of 19 mm dia & 16 mm dia Copper Refrigerant Pipes with Foam insulation between Indoor & Out door units.with breaking of wall wherever required for 3 Tr Cassette/ Air conditioners.	60	MTRS		
<input checked="" type="checkbox"/>	RATE IN WORDS -				
B02	S.I.T.C. of 12.5 Sq.mm. & 6.25 Sq.mm. dia. Copper refrigerant pipe with foam Insulation between Indoor & Out door units with breaking of wall for making hole wherever required For Split Air- Conditioners.	40	MTRS		
<input checked="" type="checkbox"/>	RATE IN WORDS -				
B03	S.I.T.C. of 3xCopper conductor flexible cable between Indoor & Outdoor Unit through holes made as above for Cassette / Inverter A.C.	60	MTRS		
<input checked="" type="checkbox"/>	RATE IN WORDS -				
B04	S.I.T.C. of copper conductor flexible cable between Indoor & Outdoor units through holes as made above for Split A.C.'s.	40	MTRS		
<input checked="" type="checkbox"/>	RATE IN WORDS -				
B05	S.I.T.C. of 19 mm. PVC conduit pipe to be used as a drain water pipe. Through holes as made above.	80	MTRS		
<input checked="" type="checkbox"/>	RATE IN WORDS -				
B06	S.I.T.C. of 25 mm. PVC conduit pipe to be used as a drain water pipe. Through holes as made above.	20	MTRS		
<input checked="" type="checkbox"/>	RATE IN WORDS -				
B07	S.I.T.C. of L shape / suitable shape M.S. Frame stand for mounting Outdoor Units on wall / On floor with all fixing hardwares. Within above Catwalk for cassette & split A.C.'s. along with cat wak made of 50mm x25 mm x5mm thk.M.S. angle frame work with 25mm x 3mmthk.m.s. split angle to wall with anchor fasner ext.as per side requirement.	11	NOS		
<input checked="" type="checkbox"/>	RATE IN WORDS -				
TOTAL (B)					
GST WILL BE EXTRA @ 18 %					
TOTAL OF (A+B) (EXCLUSIVE OF GST)					