

Page 1 of 3
STATE BANK OF INDIA
RBO 2 ERNAKULAM

NAME OF WORK		LAMINATION CHANGE WORK OF MULAVUKAD AND PUTHUVYPE BRANCHES			
NAME AND ADDRESS OF THE CONTRACTOR					
SCHEDULE OF ITEMS FOR LAMINATE CHANGE FOR MAKING UNIFORM LAYOUT FOR MULAVUKAD AND PUTHUVYPE BRANCHES					
Sl No.	Description of work	Quantity	Unit	Rate	Amount
MULAVUKAD BRANCH					
1	Providing and fixing 6 mm marine flexy plywood with high glossy white flexy laminate of approved make and shade with curved bend in front modesty to the existing surface of counters using necessary frames with 19 mm plywood.	16	Sq.M		
2	Providing and fixing 6 mm ply wood finished with 1 mm laminate of approved make and shade to the existing table top finishing with necessary beedings etc complete.	10	Sq.M		
3	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing partition/ panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings/ handles/ locks etc. complete. Edges should be neatly finished using edge band if necessary	100	Sq.M		
4	Remove the existing laminate and fix with new 1 mm laminate of approved make and shade	60.00	Sq.M		
5	Providing and fixing side portion glazing with "Blue Laminated / Lacquered transperated glass of 12mm thick of approved brand and shall be fixed with 'Doma' (or) equivalent brand 'SS ' 'D' brackets. The curved 12mm thick lacquered transperant toughened glass shall be fixed at front size in between counters as per drawing and shall be fixed suitably with 'SS' brackets.	5.00	Sq.M		
6	Providing and fixing front Modesty with 8 mm thick Aqua blue shade of Saint Gobain glass or equivalent fixed 3M stickering suitable at front vertical finished with 1 mm laminate.	6.00	Sq.M		
7	Painting the false ceiling with 1 coats of plastic emulsion paint of approved color	200.00	Sq.M		
8	Painting banking hall using approved quality ' Asian paint or equivalent two coats without putty finish	300.00	Sq.M		

9	Paint the windows with synthetic enamel paint 2 coats after cleaning the surface	50.00	Sq.M		
10	Providing PVC telescopic key board tray with channel	6.00	Nos.		
11	Removing the existing drawer channel and fixing new telescopic channel of approved make	15.00	set		
12	Providing and fixing Godrej auto lock	10.00	Nos.		
13	Providing and fixing Godrej night latch	3.00	Nos.		
14	<p>Low Level Storage :Providing and fixing low level storage to detail as shown in the drg. Size about 450mm wide, 750mm high comprising. 18 mm Plywood for top, bottom, rear, sides and One intermediate with necessary TW reeper.The unit top shall be with 25mm thick Plywood Board of approved make with 1mm thickne laminate of approved color and brand with front side half rounded edge and all the edges and all the three sides with 3mm thick band strip.Exposed faces of Plywood at top and sides of unit to be finished with 1mm thick laminate of approved color and shade.All concealed faces of Plywood finished with one coat of wood preservative paint and exposed faces of Steam beach molding / beading polished to the satisfaction of the Bank. The inside faces of unit wax and finished with varnish of approved color and shade.</p> <p>All concealed faces of Plywood finished with one coat of wood preservative paint and exposed faces of Steam beach molding / beading polished to the satisfaction of the Bank. The inside faces of unit wax and finished with</p>	5.00	Sq.M		
<u>PUTHUVYPE BRANCH</u>					
15	Providing and fixing 6 mm marine flexy plywood with mm high glossy white flexy laminate of approved make and shade with curved bend in front modesty to the existing surface of counters using necessary frames with 19 mm plywood.	18	Sq.M		
16	Providing and fixing 6 mm ply wood finished with 1 mm laminate of approved make and shade to the existing table top finishing with necessary beedings etc complete.	9	Sq.M		
17	Providing and fixing 6 mm plywood with 1 mm laminate of approved make and shade to the existing partition/ panelling/ counter and table sides etc. and wherever necessary making the surface in level. Rate includes charges for removing and refixing existing glass /beedings/ handles/ locks etc. complete. Edges should be neatly finished using edge band if necessary	95	Sq.M		

18	Remove the existing laminate and fix with new 1 mm laminate of approved make and shade	75.00	Sq.M		
19	Providing and fixing side portion glazing with "Blue Laminated / Lacquered transperated glass of 12mm thick of approved brand and shall be fixed with 'Doma' (or) equivalent brand 'SS ' 'D' brackets. The curved 12mm thick lacquered transperant toughened glass shall be fixed at front size in between counters as per drawing and shall be fixed suitably with 'SS' brackets.	5.00	Sq.M		
20	Providing and fixing front Modesty with 8 mm thick Aqua blue shade of Saint Gobain glass or equivalent fixed 3M stickering suitable at front vertical finished with 1 mm laminate.	6.00	Sq.M		
21	Painting the false ceiling with 1 coats of plastic emulsion paint of approved color	240.00	Sq.M		
22	Painting banking hall using approved quality ' Asian paint or equivalent two coats without putty finish	300.00	Sq.M		
23	Paint the windows with synthetic enamel paint 2 coats after cleaning the surface	50.00	Sq.M		
24	Providing PVC telescopic key boad tray with channel	6.00	Nos.		
25	Removing the existing drawer channel and fixing new telescopic channel of approved make	15.00	set		
26	Providing and fixing Godrej auto lock	10.00	Nos.		
27	Providing and fixing Godrej night latch	3.00	Nos.		
	TOTAL				
	GST				
	GRAND TOTAL				