

**SBILD, PURNEA****DETAILED REVISED ESTIMATE FOR THE REPAIRING / RENOVATION OF HOSTEL UNITS ,TRAINING UNITS,GENERATOR ROOM ,OUTER BACK SIDE TOILETS & BOUNDARY WALLS ETC. OF SBILD ,PURNEA VIDE LHO ,PATNA LETTER NO- P & E / SMK / 729 DATED 25.02.2020.**

<b>Sl. No</b>	<b>Particulars of Items</b>	<b>Unit</b>	<b>Quantity</b>	<b>Rate (Rs.)</b>	<b>Amount</b>
1.	Cleaning the old surface by scrapping the entire old painting area carefully by using the coir and wire brush etc. including cost of labor etc to complete job as per the direction of E/I.	<b>Sq.m</b>	<b>3,970.00</b>		
2.	Dismantling of entire damaged plaster of hostel unit room walls & stairs etc. with carefully at all levels and heights & rubbish should be carried out by tractor out side of the Municipal area including cost of labor etc to complete job as per the direction of E/I.	<b>Sq.m</b>	<b>650.00</b>		
3.	Providing two or more coats of weather proof cement paint over a coat of cement primer of ICI, Berger Paints (India) Ltd, Jenson & Nicholson (India) Ltd, Shalimar Paints Ltd and Asian – do—to complete job.	<b>Sq.m</b>	<b>3,970.00</b>		
4.	Providing plastering work in C.M (1:4) of average thickness 12 to 20 mm thick by using standard make cement ACC, Ulteratech, Binani, Jaypee etc to complete job as per the direction of E/I.	<b>Sq.m</b>	<b>650.00</b>		
5.	Providing average 2mm to 3mm thick wall putty of approved shed and make of J.K. / Birla as per specifications includes all labor, material and transportation etc.	<b>Sq.m</b>	<b>4,620.00</b>		
6.	Providing two or more coats of Plastic emulsion paint over a coat of cement primer of ICI, Berger Paints (India Ltd, Jenson & Nicholson (India) Ltd, Shalimar Paints Ltd and Asian – do—to complete job.	<b>Sq.m</b>	<b>4,170.00</b>		
7.	Providing two or more coats of synthetic enamel paint over a coat of cement primer of ICI, Berger Paints (India Ltd, Jenson & Nicholson (India) Ltd, Shalimar Paints Ltd and Asian – do—to complete job.	<b>Sq.m</b>	<b>654.00</b>		
8.	Scaffolding for repairing work by using steel pipes fitting /bamboo of required diameter from ground floor to roof level including cost of strings & nettings etc & all safety arrangements to be made by the Party including insurance of workers etc	<b>Sq.m</b>	<b>1,100.00</b>		

	to complete job as per the direction of E/I.				
9.	Cleaning of drainage / sewerage systems with minor repairing and providing RCC cover slab of main hole and drain slab etc. of premises including cost of labor as per the direction of E/I.	L.S	One item		
10.	Removing and replacing of old rainwater pipes with 0'-4" diameter PVC pipes of Supreme/Prince or equivalent make including cost of all types of fittings bend, collar & shoe etc. to complete job.	Meter	201.00		
11.	Dismantling of floor and wall tiles and supplying , fitting & fixing ceramic tiles of approved quality, size and shade to floor, wall , skirting window still etc of Kajaria, Nitco,Euro, Regency,Novino, Romano and Spartek brand laid in panels & patterns and set in position with water proof tile fixing adhesive of M/S Pidilite Industries Ltd or M/S Bauchemie (India) Pvt Ltd. make and quality on the base prepared with cement mortar(1:4) including cost of base mortar of required thickness and tile fixing adhesive including pointing the joints of tiles with white cement with admixture of pigment to match with the shade of tiles including cost of leveling course in cement mortar(1:4) to match with adjacent floor and undulation in sub base complete with all labor & materials to all floors and laying of tiles shall be done as per specification & direction of manufacture of tiles and tile fixing adhesive.	Sq.m	278.00		
12.	S/F/F flushing cistern of 10.00 litres of "Parryware", Hindware or any other approved make with its all accessories etc. to complete job.	Nos.	06.00		
13.	Supplying, fitting & fixing 20 gauge G.C.I, sheet gate fitted on M.S. Angle frame of size 60 x 60 x 6mm including cost of fabrication, providing necessary locking arrangements with haskal & domny duly fixed in C.C (1:2:4) blocks of required size, applying a priming red lead paint over steel work, taxes after taking out of chaukhat and door shutter etc to complete as per drawing, specification & direction of E/I( Mumty room entrance at roof).	Sq.m	3.00		
14.	Supplying fitting and fixing vitreous white	Nos.	06.00		

	glazed earth ware E.W.C of Parry ware, Hinidware or any other I.S.I approved make with 100mm H.C.I. 'P' trap, 15 liters low level PVC flushing cistern of ISI equivalent make, complete with all fitting C.I or R.S bracket, 32mm alkathone/P.V.C. telescopic flush pipe with brass coupling & plumber joint at one end & supplying & fixing, 15mm brass stopcock of weight not less than 450mm , 15mm P.V.C connection pipe 45mm long and with brass coupling with white / black plastic solid seat cover & lid etc. doing plumber joints and painting all the exposed pipe with two coats of approved paint over a coat of red/oxide primer etc. all complete as per specification and direction of E/I.				
15.	S/F/F 75mm diameter PVC pipes of Prince / Supreme or any other I.S.I approved make with its accessories to complete job.	Meters	60.00		
16.	Providing tore reinforcement of Tata / Sail makes including cutting, bending, binding & placing of rods etc to complete job.	Kg	15.00		
17.	Providing P.C.C (1:2:4) in floor of front side entrance portion etc with stone chips & approved quality of sand including cost of labour & materials etc. to complete job.	Cu.m	15.00		
18.	Providing R.C.C (1:1.5:3) for the chajjas etc with stone chips & approved quality of sand including cost of labour & materials etc. to complete job.	Cu.m	1.00		
19.	Providing, laying and fixing vitrified flooring / skirting in specified area with vitrified tiles approx size 600mm x 600 mm X 8mm in light colors specified by the SBIIMS as per approved shade and colour of standard make i.e. Naveen/ Johnson/Nitco/ Euro(Premium quality) only, with the help of Pedilite or equivalent make pasting chemicals after required chipping and leveling the surface by 1:4 cement sand mortar if required all complete including cost of materials, labours etc.	Sq.m	8.00		
20.	S/F/F 20mm diameter CPVC pipes of Ashirwad ,Prince & Supreme make for water supply pipe including cost of labour & materials to complete job.	Meters	225.00		
21.	S/F/F bibcock / pillar cock / angle cock of Jaguar make etc including cost of labour	No's.	20.00		

	& materials etc to complete job.				
22.	Providing two or more coats of O.B.D over a coat of cement primer of ICI, Berger Paints (India Ltd, Jenson & Nicholson (India) Ltd, Shalimar Paints Ltd and Asian – do—to complete job	Sq.m	1,626.00		
23.	Removing of back side Pavers block and re-fixing the same with 50 mm thick sand with proper leveling etc .to complete job as per direction of E / I.	Sq.m	56.00		
24.	Taking out of electric Gyser & S/F /F 25 litres capacity Gyser of Bajaj / Usha make etc to complete job.	No's.	5.00		

**Place:-**

**Date:-**

**Signature of the vendor**