

AIR-CONDITIONING WORK AT DSH & RACC LAKHIMPUR													
S.N.	DESCRIPTION (rate must be quoted excluding GST)	UNIT	QTY	RATE	AMOUNT								
1	Supply, Installation, Testing and Commissioning (SITC) of air cooling type, <b>2.0 Tr, Cassette type split air conditioner</b> in recessed manner in false ceiling & comprising of Indoor & Outdoor units. The Indoor unit comprising multi-row DX cooling coil, Drier, expansion valve/device , air blower driven by motor with mounting accessories. Outdoor unit will comprise the Rotary/Scroll compressor, condenser coil & fan, Cordless remote controller etc. including Refrigerant gas charging , water drain system stabilizer etc. Make : Daikin/Hitachi/Carrier/ Blue Star/Voltas/Toshiba ( For Banking Hall Area)	Nos	3.00										
2	Supply and Installation testing commissioning of wall mounted <b>High Wall Split AC 1.5 Ton Inverter AC (five star)</b> The Indoor unit comprising multi-row DX cooling coil, Drier, expansion valve/device , air blower driven by motor with mounting accessories. Outdoor unit will comprise the Rotary/Scroll compressor, condenser coil & fan, Cordless remote controller etc. including Refrigerant gas charging , water drain system etc. Make : Daikin/Hitachi/Carrier/ Blue Star/Voltas/Toshiba.	No	1.00										
3	S.I.T.C. of L shape / suitable shape powder coated under mentioned M.S. Frame and stand for mounting Outdoor Units on wall / On floor with all fixing hardwares.	No	3.00										
4	<b>a) Automatic stabilizer for 2.0 Tr AC</b> Providing & Installation of <b>5 KVA</b> voltage Stabilizers with range of 130 - 280V of standard make as per the approval of the Architect of (Inmag, Served, Stambh, Vgaurd)	No	3.00										
	<b>b) Automatic stabilizer for 1.5 Tr AC</b> Providing & Installation of <b>4 KVA</b> voltage Stabilizers with range of 130 - 280V of standard make as per the approval of the Architect of (Inmag, Served, Stambh, Vgaurd)	No	1.00										
5	a) Copper Piping Refrigerant along with insulator Piping for Hi Wall 1.5 ton and 1 ton Ac 1/2 and 1/4. Soft Copper Refrigerant piping with complete fitting, elbows bends supporting arrangements Nissan, Merchant, MET tube, Totaline tube, pressure tested tube .	Rm	60.00										
	b) S.I.T.C. of 4 core Copper conductor flexible cable between Indoor & Outdoor Unit through holes made as above	Rm	60.00										
6	PVC Drain Water Piping	No	60.00										
TOTAL PART-I ( DSH COST excluding GST )													
RACC AC													
7	Supply, Installation, Testing and Commissioning (SITC) of air cooling type, <b>2.0 Tr, Cassette type split air conditioner</b> in recessed manner in false ceiling & comprising of Indoor & Outdoor units. The Indoor unit comprising multi-row DX cooling coil, Drier, expansion valve/device , air blower driven by motor with mounting accessories. Outdoor unit will comprise the Rotary/Scroll compressor, condenser coil & fan, Cordless remote controller etc. including Refrigerant gas charging , water drain system stabilizer etc. Make : Daikin/Hitachi/Carrier/ Blue Star/Voltas/Toshiba ( For Banking Hall Area)	Nos	2.00										
8	Supply and Installation testing commissioning of wall mounted <b>High Wall Split AC 1.5 Ton inverter AC (five star)</b> The Indoor unit comprising multi-row DX cooling coil, Drier, expansion valve/device , air blower driven by motor with mounting accessories. Outdoor unit will comprise the Rotary/Scroll compressor, condenser coil & fan, Cordless remote controller etc. including Refrigerant gas charging , water drain system etc. Make : Daikin/Hitachi/Carrier/ Blue Star/Voltas/Toshiba.	No	1.00										
9	S.I.T.C. of L shape / suitable shape powder coated under mentioned M.S. Frame and stand for mounting Outdoor Units on wall / On floor with all fixing hardwares.	No	3.00										
10	<b>a) Automatic stabilizer for 2.0 Tr AC</b> Providing & Installation of <b>5 KVA</b> voltage Stabilizers with range of 130 - 280V of standard make as per the approval of the Architect of (Inmag, Served, Stambh, Vgaurd)	No	2.00										
	<b>b) Automatic stabilizer for 1.5 Tr AC</b> Providing & Installation of <b>4 KVA</b> voltage Stabilizers with range of 130 - 280V of standard make as per the approval of the Architect of (Inmag, Served, Stambh, Vgaurd)	No	1.00										
11	a) Copper Piping Refrigerant along with insulator Piping for Hi Wall 1.5 ton and 1 ton Ac 1/2 and 1/4. Soft Copper Refrigerant piping with complete fitting, elbows bends supporting arrangements Nissan, Merchant, MET tube, Totaline tube, pressure tested tube .	Rm	40.00										
	b) S.I.T.C. of 4 core Copper conductor flexible cable between Indoor & Outdoor Unit through holes made as above	Rm	40.00										
12	PVC Drain Water Piping	No	50.00										
TOTAL PART -II (RACC cost excluding GST)													
GRAND TOTAL (PART I DSH + PART-II RACC)													