



SBI INFRAMANAGEMENTSOLUTIONS PVT. LTD. (**SBIIMS**)
(A Wholly Owned Subsidiary of SBI)

Circle Office: 4th Floor, SBI, Local Head Office, III/1, Pt. J N Marg,
Kharvelnagar, Bhubaneswar-751001

Tender for Interior Furnishing works of
FI Hub at SBI Nawapara
(Pricel Bid)

Tender ID: BHU202004005
Date: 30.04.2020

Name of the Tenderer.....

Address:.....

.....

GSTIN:.....

(Eligible for doing business at Orissa)

FI HUB AT SBI NAWAPARA
BOQ FOR INTERIOR FURNISHING WORK

SI	Item Description	Qty	Unit
1	Shifting of existing Lead Bank Tables to the Ground Floor	2	Each
2	Low height double skin partly glazed partition		
	Supplying, fitting and fixing low height partly glazed double skin partition for specified enclosure, made out of 25 mmX 50 mm locally available Aluminium Metal Studs, in combination of 6mm BWP ply + 1mm matt/ mirror finish laminates on both sides and 8 mm glass with necessary beading as per the design and instruction of E-I-C, The bottom member shall be fixed to the R.C.C. floor with wedge bolt and rawl plugs at suitable intervals. The glass shall be fixed with required beading as per approved design and direction of Engineer-in-charge. All materials are to be of approved make, shade and quality. The rate shall include cost of all materials, labour, taxes, T&P, transportation, royalties etc. for complete work. The glass portion of the partition should be provided with deep etching as directed by the Engineer in charge.	5	Sqm
3	False Ceiling		
	P&F modular grid ceiling with Armstrong make Rh-95 and tegular edge 600x600 x15mm as specified by manufacturer. Installation to comprise main runner at 1200 centres fixed to structural outfits. First and last Armstrong suspension system should not be greater than 6000 from adjacent wall. 600x600 cross tees shall be provided between 1200 tees. M6 anchor fastener with vertical hangers made of galvanised steel 26x26x25x1.2mm , a pre straight hanger wire 2.68mm dia, adjustable hooks clips of 0.8mm thick spring steel of 2.68mm shall be used. Thre work shall be executed as per manufacturers specification. Ceiling frame shall be rigidly fixed to the wall, RCC rigidly so that it will not fall down while fixing boards, providing lights, electrical cables, pipes etc. Provision shall be made for light fitting, fire equipment, CCTV equipment. Extra support shall be given if necessary as per site requirement.	60	Sqm
4	Work-station for CM FI		
	BM table 6'x3 x2'6"along with side unit of 20"x42": Made with 19mm MR grade BB in table top, sides with one drawer unit of 450mm x 500deepx750mm with one drawer along with sliding channels and one cup board. The side units shall have one shutter with provision of storage units (450x4500x750). All necessary hardware's, locks, handles, PVC KBT of approved make shall be provided including foot rest. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table units shall be polished. A 40mm drop shall be provided on customer side with 19mm BB and laminate. Edges shall be finished with half round wood lipping on writing desk side and PU polished for smoothness. Drawers shall be finished with lipping polished. Ply: MR KITPLY/Mayur/Century/ Sylvan / Green, and laminate: Green/ Marino/ Century/Kit ply as approved	1	Each
5	Work-station for Officers		
	Officers table 5'x2-6" x2'6"along with side unit of 18"x42": Made with 19mm MR grade BB in table top, sides with one drawer unit of 450mm x 500deepx750mm with one drawer along with sliding channels and one cup board. The side units shall have one shutter with provision of storage units (450x4500x750). All necessary hardware's, locks, handles, PVC KBT of approved make shall be	2	Each

	provided including foot rest. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table units shall be polished. A 40mm drop shall be provided on customer side with 19mm BB and laminate. Edges shall be finished with half round wood lipping on writing desk side and PU polished for smoothness. Drawers shall be finished with lipping polished. Ply: MR KITPLY/Mayoor/Century/ Sylvam / Green, and laminate: Green/ Marino/ Century/Kit ply as approved.		
6	Work station for Asst.		
	'Staff Table 4'x2 x2'6": Made with 19mm MR grade block board in table top, sides with one drawer unit of 400mm x 500deepx750mm with one drawer along with sliding channels and one cup board. All necessary hardwares, locks, handles, PVC KBT of approved make shall be provided including foot rest. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table units shall be polished. A 40mm drop shall be provided on customer side with 19mm BB and laminate. Edges shall be finished with half round wood lipping on writing desk side and PU polished for smoothness. Drawers shall be finished with lipping polished. Ply: MR KITPLY/Mayoor/Century/ Sylvam / Green, and laminate: Green/ Marino/ Century/Kit ply as approved.	2	Each
7	Storage Cabinet		
	Storage units 450mm deep: Made with 19mm MR grade Block board on all five sides and 6mm backing ply. Vertical separators shall be provided at each 3' Centres with door leaf of each shutter of 18" wide supported by auto closing hinges. All inside surface shall be finished with 0.80mm thick laminate. Exposed surface including shutter edges shall be finished 1mm laminate of approved shade. Hardwraes like locks, handles shall be provided. Make: Mr Ply: Kit ply/Century/green/mayoor, Laminate: Kit ply/century/green/ Marino; Hardware Godrej/ebco/ Hettich as approved Make	5	Sqm
8	Finishing the wall surface with putty of thickness 2mm average to make the surface in true line and level including scrapping the surfaces with sand paper etc	150	SQM
9	Finishing the wall surface with tractor emulsion paint of Asian/ equiv as approved in two or more coats over a coat of primer as specified by the manufacturer	150	SQM
10	Finishing the Wooden/ MS surface with synthetic enamel paint in two or more coats of Asian/ equiv as approved by engineer in charge	100	SQM
11	P&L premium quality joint free double charged vitrified tile of size 600x600mm as per sample approved by engineer in charge laid in 15 to 20mm thick base cement mortar 1:4 (C:CS) in line, level and in pattern, jointing with grey cement slurry mixed with SBR polymer 2% by wt of cement, pointing the joint by tile matching epoxy grouts including surface preparation, cleaning the joints etc complete. The tiles surface shall be cured sufficiently. Tile joints shall be grouted with white cement. Work shall be executed at any level and height. Rate includes providing & laying PCC 1:2:4 wherever required to make the surface in line and level. (make: Somany/ Kajaria/ Johnson/RAK as per sample approved) Floor shall be chipped or hacking to make the proper bonding.	20	SQM
Note :			
i) Contractor Should Visit the site before quoting the rates. Item rates to be quoted inclusive of cost of required dismantling, disposal of debris as directed. No extra payment to be claimed on this account.			
ii) Work is to be executed at the first floor, item rates to be quoted accordingly, no extra payment will be considered for lifting materials to the first floor.			