

PRICE BID : INTERIOR & FURNISHING WORK FOR ATM AT AMNOUR AND DIGHWARA

1	FALSE CEILING	<p>Providing and fixing of Armstrong's Mineral Fiber Acoustical False ceiling tiles of type Prima Fine Fissured RH-99% of approx. size 600mm x 600mm x 12mm with square / tegular edge at all heights laid on Armstrong's Prelude XL Hot dipped galva-nized exposed grid with 15 m with T-Section exposed flingers which shall be powder coated white. The framework will comprise of main Runner made from 0.33 mm thick GS sheet and of size 24 mm x 38mm x 3600 mm and spaced at 1200 mm centre securely fixed to the structural soffit by approved hangers at 1200 mm maximum centre. Hangers (GI wire of 4.0 mm diameter) to be fixed by approved Rawl plug, level adjusters and screws etc. All complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank. The last hanger at the end of each main Runner should not be greater than 450 mm from the adjacent wall. Flush fitting of 1200 mm long cross tee (with double stitching) to be inter-locked between main Runners at 600 mm centre to form 1200 mm x 600 mm modules. Cut cross Tees longer than 600 mm to be supported independent-ly. 600 mm x 600 mm modules top be formed by fitting 600 mm x 600 mm modules to be formed by fitting 600 mm long cross Tee centrally between the 12 mm cross Tee. Perimeter wall Angle shall be of 0.45 thick GS Steel and of size 22 mm and 3000 mm long of white color. The work shall be as per standards and specifications laid down by the manufacturers. Full provision of weight of a/c ducting (if provided) and light fittings, wiring for any use, including co-coordinating with all trades and making any cutouts required for the same, all complete with a minimum of 2 coats of premium quality Acrylic emulsion paint and full finishing for light fittings all complete work as per drawing, design., specification and direction of Engineer-in-charge .</p>	32	sqm		
2		Vinyl branding	50	SQM		
3	ACP PARTATION	<p>PARTITION set with an inner wooden /GI framework of 50 mm x 50 mm well seasoned Ma-laysian sal wood sections, placed at suitable spac-ings not exceeding 600 mm c/c. The framework shall be covered by 12 mm thick BWR plywood. The work is to be finished with 3 mm thick exterior/interior grade Aluminium Composite Pan-el(ACP) cladding of approved shade AND COLOUR & make with grooves duly treated with silicon sealant.</p> <p>The work is to include all necessary materials, accessories, labour, tools & tackles. Executed covered area shall be measured for finished work.</p>	35	sqm		

4	ACP PANELLING	Providing and fixing of ACP Panelling to be set with an inner wooden frame work of 50 mm x50 m well seasoned Malasian sal wood sections,placed at suitable spacing not exceeding 600 mm c/c.The frame work will be covered by 12 mm thick BWR plywood and will be finished with 3 mm thick exteri-ro/interior grade Aluminium Composit Panel (ACP) cladding of approved shade & make with grooves duly treated with silicon sealant. The work includes all necessary materials,accessories,labour,tools & tackles.Executed covered area shall be measured for finished work.	75	sqm		
5	FULLY GLAZED FIXED PARTITON	Providing and fixing / fitting 12 mm thick toughened glass of approved make with all necessary hard-ware accessories etc including cost of labours and materials etc as per Corporate Centre, Mumbai approved materials Colour etc and specifica-tions and the direction of E / I.	13	sqm		
6	12 MM THICK TOUGHENE D GLASS DOOR ETC	Providing and fixing / fitting 12 mm thick toughened glass of approved make with all necessary hard-ware accessories etc including cost of labours and materials etc as per Corporate Centre, Mumbai approved materials Colour etc and specifica-tions and the direction of E / I.	5	SQ. MTR.		
RS.	PRICE QUOTED SHOULD BE EXCLUSIVE OF GST .			TOTAL		